


# NIST Technical Note 1863-2



## Assessment of First Generation Performance-Based Seismic Design Methods for New Steel Buildings

### Volume 2: Special Concentrically Braced Frames



John L. Harris III  
Matthew S. Speicher

This publication is available free of charge from:  
<http://dx.doi.org/10.6028/NIST.TN.1863-2>



**NIST**  
National Institute of  
Standards and Technology  
U.S. Department of Commerce

## **Disclaimers**

Certain commercial software, equipment, instruments, or materials may have been used in the preparation of information contributing to this report. Identification in this report is not intended to imply recommendation or endorsement by NIST, nor is it intended to imply that such software, equipment, instruments, or materials are necessarily the best available for the purpose.

NIST policy is to use the International System of Units (metric units) in all its publications. In this report, however, information is presented in U.S. Customary Units (inch-pound), as this is the preferred system of units in the U.S. earthquake engineering industry.

**National Institute of Standards and Technology Technical Note 1863-2  
Natl. Inst. Stand. Technol. Tech Note 1863-2, 266 pages (February 2015)  
CODEN: NTNOEF**

**This publication is available free for charge from:  
<http://dx.doi.org/10.6028/NIST.TN.1863-2>**

# NIST Technical Note 1863-2

## Assessment of First Generation Performance- Based Seismic Design Methods for New Steel Buildings

### Volume 2: Special Concentrically Braced Frames

John L. Harris III  
Matthew S. Speicher

This publication is available free of charge from:  
<http://dx.doi.org/10.6028/NIST.TN.1863-2>

February 2015



U.S. Department of Commerce  
*Penny Pritzker, Secretary*

National Institute of Standards and Technology  
*Willie May, Acting Under Secretary of Commerce for Standards  
and Technology and Acting Director*



## Preface

In June 2008, the National Earthquake Hazards Reduction Program (NEHRP) sponsored a Performance-Based Seismic Design (PBSD) workshop for leading practitioners and researchers from around the United States to develop a comprehensive list of research needs to foster full development and implementation of PBSD. From this workshop, the Building Seismic Safety Council (BSSC) reported a prioritized list of key PBSD research and implementation needs in NIST GCR 09-917-2: *Research Required to Support Full Implementation of Performance-Based Seismic Design* (NIST 2009a). The highest priority need identified in this report was to “benchmark” current PBSD methodologies (e.g., ASCE/SEI 41-06: *Seismic Rehabilitation of Existing Buildings* (ASCE 2006)—hereafter referred to as ASCE 41) with code procedures for design of new buildings. Two observations from the report were that among workshop participants (1) ASCE 41 procedures are perceived to be overly conservative and (2) existing PBSD methods are not accepted by practitioners as providing a uniform level of confidence. A supporting reason for these two observations was that no systematic effort had been undertaken to benchmark structural performance as determined using ASCE 41 procedures, together with widely accepted procedures for designing new buildings using ASCE/SEI 7-10: *Minimum Design Loads for Buildings and Other Structures* (ASCE 2010)—hereafter referred to as ASCE 7.


Work was initiated at the National Institute of Standards and Technology (NIST) to support this priority study under the *Assessment of Design Methods in Existing PBSD Standards Project*. This task was conducted by the Earthquake Risk Reduction in Buildings and Infrastructure group, the research division of the NEHRP Office at NIST. This research involves problem-focused studies in PBSD assessing the applicability and accuracy of implementing first-generation PBSD analysis methods now used for evaluating existing buildings in the performance-based design of new buildings. The current study focuses on buildings with lateral systems utilizing structural steel frames. This project evaluates the results of the studies and identifies changes to current model building codes and standards provisions that will encourage more universal use of PBSD. The volume of data required to illustrate the results and conclusions necessitated three separate reports, as follows:

- Volume 1: Special Moment Frames
- Volume 2: Special Concentrically Braced Frames (this report)
- Volume 3: Eccentrically Braced Frames

A fourth report, Volume 4: Buckling Restrained Braced Frames, is under development.

A peer review panel (PRP) was engaged under a contract with the NEHRP Consultants Joint Venture (NCJV)—[www.nehrp-consultants.org](http://www.nehrp-consultants.org). The PRP was tasked to complement the NIST project by providing, where needed, individual subject matter expert guidance to improve the technical detail and outcome of the project; provide technical support on specific topics on seismic hazard analysis, ground motion scaling for

varying return periods, nonlinear dynamic analysis, structural behavior and design of building structures; and provide peer review services. The review panel for this project was structured as follows:



Jon Heintz (Program Manager)  
Applied Technology Council  
201 Redwood Shores Parkway, Suite 240  
Redwood City, California 94065

Ayse Hortacsu (Project Manager)  
Applied Technology Council  
201 Redwood Shores Parkway, Suite 240  
Redwood City, California 94065

Michael Engelhardt  
The University of Texas at Austin  
Dept. of Civil, Arch. and Environ. Eng.  
301 East Dean Keeton St., Stop C1747  
Austin, TX 78712

Robert Hanson  
University of Michigan, Emeritus  
5885 Dunabbey Loop  
Dublin, Ohio 43017

William Holmes (PRP Chair)  
Rutherford + Chekene  
55 Second Street, Suite 600  
San Francisco, California 94105

Nicolas Luco  
U.S. Geological Survey  
Box 25046 – DFC – MS 966  
Denver, Colorado 80225

Stephen Mahin  
University of California, Berkeley  
Dept. of Civil and Environ. Eng.  
777 Davis Hall  
Berkeley, California 94720

James Malley  
Degenkolb Engineers  
235 Montgomery St., Suite 500  
San Francisco, California 94104

Robert Pekelnicky  
Degenkolb Engineers  
235 Montgomery St., Suite 500  
San Francisco, California 94104

Charles Roeder  
University of Washington  
Dept. of Civil and Environ. Eng.  
Box 352700  
Seattle, WA 98195

Rafael Sabelli  
Walter P. Moore  
595 Market St., Suite 2130  
San Francisco, California 94105

Thomas Sabol  
Englekirk Institutional  
2116 Arlington Ave.  
Los Angeles, California 90018

Peter Somers  
Magnusson Klemencic Associates  
1301 Fifth Ave., Suite 3200  
Seattle, WA 98101

The authors gratefully acknowledge the members of the PRP for their input and guidance during this project and in the preparation of report volumes 1-3. Further, the authors wish to thank Jon Heintz and Ayse Hortacsu at Applied Technology Council for management of Task Order 12. Special thanks are also extended to Jack Hayes (NEHRP Director), Steve McCabe (NEHRP Deputy Director), and Bob Pekelnicky for reviewing the final NIST reports.

John L. Harris III  
Research Structural Engineer  
jay.harris@nist.gov

Matthew S. Speicher  
Research Structural Engineer  
matthew.speicher@nist.gov

National Institute of Standards and Technology  
Engineering Laboratory  
National Earthquake Hazards Reduction Program Office  
100 Bureau Dr., MS 8604  
Gaithersburg, MD 20899



# Table of Contents

<b>Preface</b> .....	<b>iii</b>
<b>Table of Contents</b> .....	<b>vii</b>
<b>List of Tables</b> .....	<b>xiii</b>
<b>List of Figures</b> .....	<b>xvii</b>
<b>List of Abbreviations</b> .....	<b>xxiii</b>
<b>Executive Summary</b> .....	<b>xxv</b>
<b>Chapter 1 Introduction</b> .....	<b>1-1</b>
1.1 Project Motivation and Background.....	1-3
1.2 Scope of Project .....	1-5
<b>Chapter 2 Overview and Design of Archetype Buildings</b> .....	<b>2-1</b>
2.1 General Information .....	2-1
2.2 Structural Design Loads .....	2-5
2.2.1 Load Combinations .....	2-5
2.2.2 Gravity Loads.....	2-5
2.2.3 Environmental Loads .....	2-6
2.2.3.1 Earthquake Forces .....	2-6
2.2.3.2 Wind Forces .....	2-9
2.3 Structural Analysis and Mathematical Model .....	2-9
2.4 SFRS Design .....	2-13
2.4.1 SMF Design.....	2-13
2.4.2 SCBF Design.....	2-22
<b>Chapter 3 Seismic Assessment</b> .....	<b>3-1</b>
3.1 Assessment Overview .....	3-1
3.1.1 Seismic Hazard.....	3-3
3.1.2 General Analysis Requirements .....	3-3
3.1.3 Analysis Procedures .....	3-6
3.1.3.1 Linear Analysis Procedures.....	3-6
3.1.3.1.1 Linear Static Procedure .....	3-7

	3.1.3.1.2	Linear Dynamic Procedure.....	3-8
	3.1.3.2	Nonlinear Analysis Procedures .....	3-9
	3.1.3.2.1	Nonlinear Static Procedure.....	3-10
	3.1.3.2.2	Nonlinear Dynamic Procedure .....	3-13
	3.1.4	Acceptance Criteria .....	3-14
	3.1.4.1	Linear Procedures.....	3-15
	3.1.4.1.1	Calculating Component Assessment Results .....	3-15
	3.1.4.2	Nonlinear Procedures .....	3-16
	3.1.4.2.1	Calculating Component Assessment Results .....	3-17
3.2		Concentrically Braced Frame .....	3-19
	3.2.1	Assessment Methodology.....	3-19
	3.2.1.1	Linear Procedures.....	3-19
	3.2.1.2	Nonlinear Procedures .....	3-32
	3.2.2	Seismic Assessment Results.....	3-44
	3.2.2.1	Four-Story Concentrically Braced Frame .....	3-45
	3.2.2.1.1	Linear Static Procedure .....	3-45
	3.2.2.1.1.1	..... BSE-1 Earthquake Hazard Level (LS BPL).....	3-45
	3.2.2.1.1.2	..... BSE-2 Earthquake Hazard Level (CP BPL).....	3-46
	3.2.2.1.2	Linear Dynamic Procedure.....	3-48
	3.2.2.1.2.1	..... BSE-1 Earthquake Hazard Level (LS BPL).....	3-48
	3.2.2.1.2.2	..... BSE-2 Earthquake Hazard Level (CP BPL).....	3-49
	3.2.2.1.3	Nonlinear Static Procedure.....	3-51
	3.2.2.1.4	Nonlinear Dynamic Procedure .....	3-55
	3.2.2.2	Eight-Story Concentrically Braced Frame .....	3-60
	3.2.2.2.1	Linear Static Procedure .....	3-60
	3.2.2.2.1.1	..... BSE-1 Earthquake Hazard Level (LS BPL).....	3-60
	3.2.2.2.1.2	..... BSE-2 Earthquake Hazard Level (CP BPL).....	3-62
	3.2.2.2.2	Linear Dynamic Procedure.....	3-64
	3.2.2.2.2.1	..... BSE-1 Earthquake Hazard Level (LS BPL).....	3-64
	3.2.2.2.2.2	..... BSE-2 Earthquake Hazard Level (CP BPL).....	3-66
	3.2.2.2.3	Nonlinear Static Procedure.....	3-68
	3.2.2.2.4	Nonlinear Dynamic Procedure .....	3-74
	3.2.2.3	Sixteen-Story Concentrically Braced Frame .....	3-79
	3.2.2.3.1	Linear Static Procedure .....	3-79
	3.2.2.3.1.1	..... BSE-1 Earthquake Hazard Level (LS BPL).....	3-79

3.2.2.3.1.2	..... BSE-2 Earthquake Hazard Level (CP BPL)	..... 3-82
3.2.2.3.2	Linear Dynamic Procedure	..... 3-85
3.2.2.3.2.1	..... BSE-1 Earthquake Hazard Level (LS BPL)	..... 3-85
3.2.2.3.2.2	..... BSE-2 Earthquake Hazard Level (CP BPL)	..... 3-88
3.2.2.3.3	Nonlinear Static Procedure	..... 3-91
3.2.2.3.4	Nonlinear Dynamic Procedure	..... 3-100
3.2.3	Seismic Assessment Discussion	..... 3-105
3.2.3.1	Linear Assessment Procedures	..... 3-105
3.2.3.1.1	Brace Members	..... 3-105
3.2.3.1.2	Member Cross-section Strength (flexural hinge) and Global Strength (member stability)	..... 3-107
3.2.3.1.3	Summary	..... 3-109
3.2.3.2	Nonlinear Assessment Procedures	..... 3-110
3.2.3.2.1	Brace Members	..... 3-110
3.2.3.2.2	Member Cross-section Strength (flexural hinge) and Global Strength (member stability)	..... 3-111
3.2.3.2.3	Summary	..... 3-112
3.2.3.3	Comparison between Linear and Nonlinear Assessment Results	..... 3-113
<b>Chapter 4</b>	<b>Summary, Conclusions, and Recommendations</b>	<b>..... 4-1</b>
4.1	Summary of Project Work	..... 4-1
4.2	Assumptions and Limitations of this Study	..... 4-3
4.3	Conclusions and Observations	..... 4-5
4.3.1	ASCE 41	..... 4-5
4.3.1.1	General	..... 4-5
4.3.1.2	Special Concentrically Braced Frame	..... 4-6
4.4	Recommendations for Future Research	..... 4-7
4.4.1	ASCE 41	..... 4-7
4.4.1.1	General	..... 4-7
4.4.1.2	Concentrically Braced Frames	..... 4-8
4.4.2	ASCE 7	..... 4-9
4.4.3	AISC 341 / 360 / 358	..... 4-9
4.4.3.1	Special Concentrically Braced Frames	..... 4-9
<b>Appendix A</b>	<b>Ground Motions for Response History Analysis</b>	<b>..... A-1</b>
A.1	Ground Motion Record Set	..... A-1
A.2	Ground Motion Selection and Scaling	..... A-1

A.3	Four-Story Archetype Building.....	A-3
A.3.1	4-Story Special Concentrically Braced Frame .....	A-3
A.4	Eight-Story Archetype Building.....	A-6
A.4.1	8-Story Special Concentrically Braced Frame .....	A-6
A.5	Sixteen-Story Archetype Building .....	A-9
A.5.1	16-Story Special Concentrically Braced Frame .....	A-9
A.6	FEMA P-695 Far-Field Record Set.....	A-12
<b>Appendix B Supplemental Design Information and Design Examples.....</b>		<b>B-1</b>
B.1	Horizontal Design Forces.....	B-1
B.1.1	Wind Forces .....	B-1
B.1.2	Seismic Forces.....	B-3
B.1.2.1	Effective Seismic Weights and Story Gravity Forces .....	B-3
B.1.2.2	Horizontal Seismic Forces, E-W Direction.....	B-4
B.1.2.2.1	MC4 (Special Moment Frame) .....	B-4
B.1.2.2.2	MC8 (Special Moment Frame) .....	B-7
B.1.2.2.3	MC16 (Special Moment Frame) .....	B-10
B.1.2.3	Horizontal Seismic Forces, N-S Direction.....	B-13
B.1.2.3.1	MC4 (Special Concentrically Braced Frame) .....	B-13
B.1.2.3.2	MC8 (Special Concentrically Braced Frame) .....	B-15
B.1.2.3.3	MC16 (Special Concentrically Braced Frame) .....	B-18
B.2	Horizontal and Vertical Irregularities.....	B-21
B.2.1	Special Moment Frame .....	B-21
B.2.2	Special Concentrically Braced Frame .....	B-23
B.3	SMF AISC Frame Stability (Effective Length Method) .....	B-25
B.4	Example Design Calculations .....	B-29
B.4.1	Special Concentrically Braced Frame Example.....	B-29
B.4.1.1	Member Selection .....	B-29
B.4.1.2	SCBF Brace.....	B-30
B.4.1.2.1	Axial Demand .....	B-30
A.1.1.1.1	Axial Strength .....	B-30
B.4.1.2.2	Strength Check .....	B-30
B.4.1.3	SCBF Column .....	B-31
B.4.1.3.1	Axial and Flexural Demand .....	B-31
B.4.1.3.2	Axial Strength .....	B-31

	B.4.1.3.3	Strength Check .....	B-32
<b>Appendix C</b>	<b>Example Assessment Calculations</b> .....		<b>C-1</b>
C.1	Linear Assessment Examples .....		C-1
	C.1.1 SCBF Brace .....		C-1
	C.1.1.1 Axial Demand .....		C-1
	C.1.1.2 Axial Strength .....		C-1
	C.1.1.3 Acceptance Criteria .....		C-2
	C.1.1.4 Acceptance Criteria Check .....		C-2
C.2	Nonlinear Assessment Examples .....		C-3
	C.2.1 SCBF Brace .....		C-3
	C.2.1.1 Deformation Demand .....		C-3
	C.2.1.2 Acceptance Criteria .....		C-3
	C.2.1.3 Acceptance Criteria Check .....		C-4
<b>Appendix D</b>	<b>References</b> .....		<b>D-1</b>



## List of Tables

Table 1-1. Comparison of Seismic Hazard and Associated Performance for ASCE 7 and ASCE 41 .....	1-4
Table 1-2. Performance Comparison between IBC and ASCE 41 – (From IEBC Table 301.1.4.1) .....	1-4
Table 2-1. Structural Characteristics of Archetype Buildings.....	2-1
Table 2-2. Design Gravity Loads .....	2-6
Table 2-3. Spectral Response Acceleration Parameters .....	2-7
Table 2-4. Seismic Analysis and Design Parameters, E-W.....	2-8
Table 2-5. Seismic Analysis and Design Parameters, N-S.....	2-8
Table 3-1. Seismic Performance Targets (from ASCE 41-06).....	3-2
Table 3-2. Seismic Performance Targets (from ASCE 41-13).....	3-2
Table 3-3. Spectral Response Parameters.....	3-3
Table 3-4. Displacement Multiplier—E-W (SMF) .....	3-5
Table 3-5. Displacement Multiplier—N-S (SCBF).....	3-6
Table 3-6. Analytical Fundamental Periods (seconds).....	3-8
Table 3-7. Empirical Fundamental Periods (seconds).....	3-8
Table 3-8. Story Shear Ratio - ELF .....	3-12
Table 3-9. Story Shear Ratio – RSA .....	3-12
Table 3-10. Basic <i>m</i> -factors for Linear Procedures, SCBF .....	3-27
Table 3-11. NSP General Information, 4-Story SCBF (kip, inch) .....	3-51
Table 3-12. CP NSP Analysis Parameters, 4-Story SCBF BSE-2 CP (kip, inch).....	3-51
Table 3-13. LS NSP Analysis Parameters, 4-Story SCBF BSE-1 LS (kip, inch) .....	3-51
Table 3-14. NSP General Information, 8-Story SCBF (kips, inch).....	3-69
Table 3-15. CP NSP Analysis Parameters, 8-Story SCBF BSE-2 CP (kip, inch).....	3-69
Table 3-16. LS NSP Analysis Parameters, 8-Story SCBF BSE-1 LS (kip, inch) .....	3-69
Table 3-17. NSP General Information, 16-Story SCBF (kip, inch) .....	3-92
Table 3-18. CP NSP Analysis Parameters, 16-Story SCBF BSE-2 CP (kip, inch).....	3-92
Table 3-19. LS NSP Analysis Parameters, 16-Story SCBF BSE-1 LS (kip, inch) .....	3-92
Table 3-20. Performance Summary of Brace Members (BM) per Frame, Linear Procedures.....	3-106
Table 3-21. Effect of Design and Assessment Provisions on $DCR_N$ of a Brace – LS SPL at the BSE-1 EHL .....	3-106
Table 3-22. Performance Summary of Columns Members (CM) per Frame, Linear Procedures.....	3-107
Table 3-23. BSO Performance Summary of Archetype Buildings, Linear Procedures .....	3-109

Table 3-24. Summary of Base Shears, Linear Procedures (kips).....	3-109
Table 3-25. Performance Summary of Brace Members (BM) per frame, Nonlinear Procedures .....	3-110
Table 3-26. Performance Summary of Columns Hinges (CH) per frame, Nonlinear Procedures.....	3-111
Table 3-27. Performance Summary of Column Members (CM) per frame, Nonlinear Procedures.....	3-112
Table 3-28. BSO Performance Summary of Archetype Buildings, Nonlinear Procedures .....	3-112
Table 3-29. BSO Performance Summary of Archetype Buildings.....	3-114
Table A-1. Ground Motion Records for N-S Direction of MC4 .....	A-3
Table A-2. Ground Motion Records for N-S Direction of MC84 .....	A-6
Table A-3. Ground Motion Records for N-S Direction of MC16 .....	A-9
Table B-1. Wind Forces on MC4 (kips).....	B-2
Table B-2. Wind Forces on MC8 (kips).....	B-2
Table B-3. Wind Forces on MC 16 (kips).....	B-2
Table B-4. Effect Seismic Weights and Story Gravity Forces, MC4 (kips).....	B-3
Table B-5. Effect Seismic Weights and Story Gravity Forces, MC8 (kips).....	B-3
Table B-6. Effect Seismic Weights and Story Gravity Forces, MC16 (kips).....	B-4
Table B-7. Seismic Strength Design Forces, E-W MC4 .....	B-4
Table B-8. Seismic Drift Forces, E-W MC4 .....	B-5
Table B-9. ASCE 7 Allowable Drift and Stability Verification, E-W MC4 RSA .....	B-6
Table B-10. ASCE 7 Allowable Drift and Stability Verification, E-W MC4 ELF .....	B-7
Table B-11. Seismic Strength Design Forces, E-W MC8 .....	B-7
Table B-12. Seismic Drift Forces, E-W MC8 .....	B-8
Table B-13. ASCE 7 Allowable Drift and Stability Verification, E-W MC8 RSA .....	B-9
Table B-14. ASCE 7 Allowable Drift and Stability Verification, E-W MC8 ELF .....	B-9
Table B-15. Summary of Seismic Strength Design Forces, E-W MC16 .....	B-10
Table B-16. Summary of Seismic Drift Forces, E-W MC16 .....	B-11
Table B-17. ASCE 7 Allowable Drift and Stability Verification, E-W MC16 RSA .....	B-12
Table B-18. ASCE 7 Allowable Drift and Stability Verification, E-W MC16 RSA .....	B-13
Table B-19. Summary of Seismic Strength Design Forces, N-S MC4 .....	B-13
Table B-20. Summary of Seismic Drift Forces, N-S MC4.....	B-14
Table B-21. ASCE 7 Allowable Drift and Stability Verification, N-S MC4 RSA.....	B-15
Table B-22. ASCE 7 Allowable Drift and Stability Verification, N-S MC4 ELF .....	B-15
Table B-23. Summary of Seismic Strength Design Forces, N-S MC8 .....	B-16
Table B-24. Summary of Seismic Drift Forces, N-S MC8.....	B-16
Table B-25. ASCE 7 Allowable Drift and Stability Verification, N-S MC8 RSA.....	B-18
Table B-26. ASCE 7 Allowable Drift and Stability Verification, N-S MC8 ELF .....	B-18

Table B-27. Summary of Seismic Strength Design Forces, N-S MC16 .....	B-18
Table B-28. Summary of Seismic Drift Forces, N-S MC16 .....	B-19
Table B-29. ASCE 7 Allowable Drift and Stability Verification, N-S MC16 RSA.....	B-21
Table B-30. ASCE 7 Allowable Drift and Stability Verification, N-S MC16 ELF .....	B-21
Table B-31. Horizontal Irregularity Type 1 (a and b) Verification .....	B-22
Table B-32. Vertical Irregularity Type 1 (a and b) Verification (Exception 1).....	B-22
Table B-33. Vertical Irregularity Type 5 (a and b) Verification, ELF (kip, feet).....	B-23
Table B-34. Vertical Irregularity Type 5 (a and b) Verification, RSA (kip, feet).....	B-23
Table B-35. Horizontal Irregularity Type 1 (a and b) Verification .....	B-24
Table B-36. Vertical Irregularity Type 1 (a and b) Verification (Using Exception 1).....	B-24
Table B-37. Vertical Irregularity Type 5 (a and b) Verification, ELF (kip, feet).....	B-25
Table B-38. Vertical Irregularity Type 5 (a and b) Verification, RSA (kip, feet).....	B-25
Table B-39. AISC 360 Frame Stability (Effective Length Method), 4-Story SMF ELF (kip, inch).....	B-26
Table B-40. AISC 360 Frame Stability (Effective Length Method), 4-Story SMF RSA (kip, inch).....	B-26
Table B-41. AISC 360 Frame Stability (Effective Length Method), 8-Story SMF ELF (kip, inch).....	B-26
Table B-42. AISC 360 Frame Stability (Effective Length Method), 8-Story SMF RSA (kip, inch).....	B-26
Table B-43. AISC 360 Frame Stability (Effective Length Method), 16-Story SMF ELF (kip, inch)....	B-27
Table B-44. AISC 360 Frame Stability (Effective Length Method), 16-Story SMF RSA (kip, inch)...	B-27
Table B-45. Adjusted Effective Length Factors – 4-Story SMF .....	B-27
Table B-46. Adjusted Effective Length Factors – 8-Story SMF .....	B-28
Table B-47. Adjusted Effective Length Factors – 16-Story SMF .....	B-28
Table B-48. Controlling Load Combinations (kips, feet).....	B-31



# List of Figures

Figure 2-1. Isometric View of MC4 Archetype Building .....	2-2
Figure 2-2. Isometric View of MC8 Archetype Building .....	2-2
Figure 2-3. Isometric View of MC16 Archetype Building .....	2-3
Figure 2-4. Typical Floor Framing Plan, MC4 and MC8.....	2-4
Figure 2-5. Typical Floor Framing Plan, MC16.....	2-4
Figure 2-6. Typical FR RBS Beam-to-Column Connection Assembly .....	2-10
Figure 2-7. FR RBS Beam-To-Column Connection Subassembly Model for Linear Analysis.....	2-11
Figure 2-8. Typical Brace-to-Beam / Column Connection Assembly .....	2-12
Figure 2-9. Brace-to-Beam / Column Connection Subassembly Model for Linear Analysis .....	2-12
Figure 2-10. Flow Chart of SMF Design Process .....	2-14
Figure 2-11. 4-Story SMF Schematic.....	2-17
Figure 2-12. 8-Story SMF Schematic.....	2-18
Figure 2-13. 16-Story SMF Schematic.....	2-20
Figure 2-14. Flow Chart of SCBF Design Process.....	2-22
Figure 2-15. 4-Story SCBF Schematic.....	2-24
Figure 2-16. 8-Story SCBF Schematic.....	2-25
Figure 2-17. 16-Story SCBF Schematic.....	2-27
Figure 3-1. Acceleration Response Spectra.....	3-3
Figure 3-2. Generalized Component Backbone Curve (adopted from ASCE 41 Figure C2-1) .....	3-9
Figure 3-3. NSP Process.....	3-11
Figure 3-4. <i>P-M</i> Interaction on Section <i>m</i> -factor (in-plane) and Member Instability (Primary Component) .....	3-24
Figure 3-5. Compactness Requirements as a Function of Axial Load Ratio, LS Acceptance Criteria ..	3-25
Figure 3-6. Acceptance Criteria as a Function of Axial Load Ratio and Section Compactness, LS Acceptance Criteria .....	3-26
Figure 3-7. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 4-Story SCBF ELF .....	3-28
Figure 3-8. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 4-Story SCBF RSA .....	3-28
Figure 3-9. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 8-Story SCBF ELF .....	3-29
Figure 3-10. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 8-Story SCBF RSA .....	3-29
Figure 3-11. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 16-Story SCBF ELF .....	3-30
Figure 3-12. Frame Capacity Schematic ( <i>m</i> -factor), LS and CP, 16-Story SCBF RSA .....	3-31
Figure 3-13. SCBF Brace-to-Beam / Column Subassembly Analytical Schematic.....	3-33

Figure 3-14. PERFORM-3D Brace Calibration .....	3-33
Figure 3-15. In-plane Flexural Hinge Yield Surface Model (Including Force-Controlled Response)...	3-36
Figure 3-16. Variation in Acceptance Criteria and Hinge Model for Axial Force.....	3-37
Figure 3-17. <i>P-M</i> Interaction on Plastic Rotation, LS Acceptance Criteria (Primary Component).....	3-38
Figure 3-18. <i>P-M</i> Interaction Curve (Section Yield Surface).....	3-39
Figure 3-19. <i>P-M</i> Interaction Curve (Member Instability).....	3-39
Figure 3-20. Frame Capacity Schematic (Inelastic), LS and CP, 4-Story SCBF ELF and RSA.....	3-40
Figure 3-21. Frame Capacity Schematic (Inelastic), LS and CP, 8-Story SCBF ELF and RSA.....	3-41
Figure 3-22. Frame Capacity Schematic (Inelastic), LS and CP, 16-Story SCBF ELF .....	3-42
Figure 3-23. Frame Capacity Schematic (inelastic), LS and CP, 16-Story SCBF RSA.....	3-43
Figure 3-24. LSP Assessment Results, 4-Story SCBF ELF, BSE-1 LS.....	3-45
Figure 3-25. LSP Assessment Results, 4-Story SCBF RSA, BSE-1 LS .....	3-45
Figure 3-26. LSP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-1.....	3-46
Figure 3-27. LSP Assessment Results, 4-Story SCBF ELF, BSE-2 CP.....	3-47
Figure 3-28. LSP Assessment Results, 4-Story SCBF RSA, BSE-2 CP .....	3-47
Figure 3-29. LSP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-2.....	3-47
Figure 3-30. LDP Assessment Results, 4-Story SCBF ELF, BSE-1 LS .....	3-48
Figure 3-31. LDP Assessment Results, 4-Story SCBF RSA, BSE-1 LS .....	3-48
Figure 3-32. LDP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-1 .....	3-49
Figure 3-33. LDP Assessment Results, 4-Story SCBF ELF, BSE-2 CP.....	3-50
Figure 3-34. LDP Assessment Results, 4-Story SCBF RSA, BSE-2 CP .....	3-50
Figure 3-35. LDP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-2.....	3-50
Figure 3-36. 4-Story SCBF ELF Pushover, BSE-2 .....	3-52
Figure 3-37. 4-Story SCBF RSA Pushover, BSE-2 .....	3-52
Figure 3-38. 4-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2 .....	3-53
Figure 3-39. 4-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2.....	3-53
Figure 3-40. Schematic of Flexural Actions in Columns, 4-Story SCBF (NSP and NDP).....	3-54
Figure 3-41. NSP Assessment Results, 4-Story SCBF ELF, BSE-1 LS (+push to left).....	3-55
Figure 3-42. NSP Assessment Results, 4-Story SCBF RSA, BSE-1 LS (+push to left).....	3-55
Figure 3-43. NSP Assessment Results, 4- Story SCBF ELF, BSE-2 CP (+push to left) .....	3-55
Figure 3-44. NSP Assessment Results, 4-Story SCBF RSA, BSE-2 CP (+push to left).....	3-55
Figure 3-45. NDP Assessment Results, Brace Struts, 4-Story SCBF ELF, BSE-1 LS .....	3-56
Figure 3-46. NDP Assessment Results, Brace Struts, 4-Story SCBF RSA, BSE-1 LS .....	3-57
Figure 3-47. NDP Assessment Results, Brace Struts, 4-Story SCBF ELF, BSE-2 CP .....	3-57
Figure 3-48. NDP Assessment Results, Brace Struts, 4-Story SCBF RSA, BSE-2 CP .....	3-57

Figure 3-49. NDP Assessment Results, Column Hinges, 4-Story SCBF ELF, BSE-2 Yield .....	3-58
Figure 3-50. NDP Assessment Results, Column Hinges, 4-Story SCBF RSA, BSE-2 Yield.....	3-59
Figure 3-51. NDP Assessment Results, Column Members, 4-Story SCBF ELF, BSE-2 .....	3-59
Figure 3-52. NDP Assessment Results, Column Members, 4-Story SCBF RSA, BSE-2.....	3-60
Figure 3-53. LSP Assessment Results – 8-Story SCBF ELF – BSE-1 – LS.....	3-61
Figure 3-54. LSP Assessment Results, 8-Story SCBF RSA, BSE-1 LS .....	3-61
Figure 3-55. LSP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-1 .....	3-62
Figure 3-56. LSP Assessment Results, 8-Story SCBF ELF, BSE-2 CP.....	3-63
Figure 3-57. LSP Assessment Results, 8-Story SCBF RSA, BSE-2 CP.....	3-63
Figure 3-58. LSP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-2 .....	3-64
Figure 3-59. LDP Assessment Results, 8-Story SCBF ELF, BSE-1 LS .....	3-65
Figure 3-60. LDP Assessment Results, 8-Story SCBF RSA, BSE-1 LS .....	3-65
Figure 3-61. LDP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-1 .....	3-66
Figure 3-62. LDP Assessment Results, 8-Story SCBF ELF, BSE-2 CP .....	3-67
Figure 3-63. LDP Assessment Results, 8-Story SCBF RSA, BSE-2 CP .....	3-67
Figure 3-64. LDP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-2.....	3-68
Figure 3-65. 8-Story SCBF ELF Pushover, BSE-2 .....	3-69
Figure 3-66. 8-Story SCBF RSA Pushover, BSE-2 .....	3-70
Figure 3-67. 8-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2 .....	3-71
Figure 3-68. 8-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2.....	3-71
Figure 3-69. Schematic of flexural actions in columns, 08-Story SCBF (NSP and NDP).....	3-72
Figure 3-70. NSP Assessment Results, 8-Story SCBF ELF, BSE-1 LS (+push to left) .....	3-73
Figure 3-71. NSP Assessment Results, 8-Story SCBF RSA, BSE-1 LS (+push to left).....	3-73
Figure 3-72. NSP Assessment Results, 8-Story SCBF ELF, BSE-2 CP (+push to left) .....	3-73
Figure 3-73. NSP Assessment Results, 8- Story SCBF RSA, BSE-2 CP (+push to left).....	3-73
Figure 3-74. NDP Assessment Results, Brace Struts, 8-Story SCBF ELF, BSE-1 LS .....	3-74
Figure 3-75. NDP Assessment Results, Brace Struts, 8-Story SCBF RSA, BSE-1 LS .....	3-75
Figure 3-76. NDP Assessment Results, Brace Struts, 8-Story SCBF ELF, BSE-2 CP.....	3-75
Figure 3-77. NDP Assessment Results, Brace Struts, 8-Story SCBF RSA, BSE-2 CP .....	3-76
Figure 3-78. NDP Assessment Results, Column Hinges, 8-Story SCBF ELF, BSE-2 Yield .....	3-77
Figure 3-79. NDP Assessment Results, Column Hinges, 8-Story SCBF RSA, BSE-2 Yield.....	3-77
Figure 3-80. NDP Assessment Results, Column Members, 8-Story SCBF ELF, BSE-2 .....	3-78
Figure 3-81. NDP Assessment Results, Column Members, 8-Story SCBF RSA, BSE-2.....	3-78
Figure 3-82. LSP Assessment Results, 16-Story SCBF ELF, BSE-1 LS.....	3-80
Figure 3-83. LSP Assessment Results, 16-Story SCBF RSA, BSE-1 LS .....	3-81

Figure 3-84. LSP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-1.....	3-82
Figure 3-85. LSP Assessment Results, 16-Story SCBF ELF, BSE-2 CP.....	3-83
Figure 3-86. LSP Assessment Results, 16-Story SCBF RSA, BSE-2 CP.....	3-84
Figure 3-87. LSP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-2.....	3-85
Figure 3-88. LDP Assessment Results, 16-Story SCBF ELF, BSE-1 LS .....	3-86
Figure 3-89. LDP Assessment Results, 16-Story SCBF RSA, BSE-1 LS .....	3-87
Figure 3-90. LDP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-1 .....	3-88
Figure 3-91. LDP Assessment Results, 16-Story SCBF ELF, BSE-2 CP.....	3-89
Figure 3-92. LDP Assessment Results, 16-Story SCBF RSA, BSE-2 CP .....	3-90
Figure 3-93. LDP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-2.....	3-91
Figure 3-94. 16-Story SCBF ELF Pushover, BSE-2 .....	3-92
Figure 3-95. 16-Story SCBF RSA Pushover, BSE-2 .....	3-93
Figure 3-96. 16-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2 .....	3-93
Figure 3-97. 16-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2.....	3-94
Figure 3-98. Schematic of flexural actions in columns, 16-Story SCBF (NSP and NDP).....	3-95
Figure 3-99. NSP Assessment Results, 16-Story SCBF ELF, BSE-1 LS (+push to left).....	3-96
Figure 3-100. NSP Assessment Results, 16-Story SCBF RSA, BSE-1 LS (+push to left).....	3-97
Figure 3-101. NSP Assessment Results, 16-Story SCBF ELF, BSE-2 CP (+push to left).....	3-98
Figure 3-102. NSP Assessment Results, 16-Story SCBF RSA, BSE-2 CP (+push to left).....	3-99
Figure 3-103. NDP Assessment Results, Brace Struts, 16-Story SCBF ELF, BSE-1 LS .....	3-100
Figure 3-104. NDP Assessment Results, Brace Struts, 16-Story SCBF RSA, BSE-1 LS .....	3-101
Figure 3-105. NDP Assessment Results, Brace Struts, 16-Story SCBF ELF, BSE-2 CP.....	3-101
Figure 3-106. NDP Assessment Results, Brace Struts, 16-Story SCBF RSA, BSE-2 CP .....	3-102
Figure 3-107. NDP Assessment Results, Column Hinges, 16-Story SCBF ELF, BSE-2 Yield .....	3-103
Figure 3-108. NDP Assessment Results, Column Hinges, 16-Story SCBF RSA, BSE-2 Yield.....	3-103
Figure 3-109. NDP Assessment Results, Column Members, 16-Story SCBF ELF, BSE-2 .....	3-104
Figure 3-110. NDP Assessment Results, Column Members, 16-Story SCBF RSA, BSE-2.....	3-104
Figure 3-111. Effect of Design and Assessment Provisions on the $DCR_N$ .....	3-107
Figure 3-112. NDP Assessment Results, Story Drift Ratios, 8-Story SCBF RSA, BSE-2 CP .....	3-115
Figure A-1. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC4 .....	A-4
Figure A-2. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC4 .....	A-5
Figure A-3. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC8 .....	A-7

Figure A-4. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC8 .....	A-8
Figure A-5. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC16 .....	A-10
Figure A-6. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC16 .....	A-11
Figure A-7. 1994 Northridge Earthquake at Beverly Hills, Mulholland Drive Station, Comp. 009 .....	A-12
Figure A-8. 1994 Northridge Earthquake at Beverly Hills, Mulholland Drive Station, Comp. 279 .....	A-12
Figure A-9. 1994 Northridge Earthquake at Canyon Country WLC Station, Comp. 000.....	A-13
Figure A-10. 1994 Northridge Earthquake at Canyon Country WLC Station, Comp. 270.....	A-13
Figure A-11. 1999 Duzce, Turkey Earthquake at Bolu Station, Comp. 000 .....	A-14
Figure A-12. 1999 Duzce, Turkey Earthquake at Bolu Station, Comp. 090 .....	A-14
Figure A-13. 1999 Hector Mine Earthquake at Hector Station, Comp. 000 .....	A-15
Figure A-14. 1999 Hector Mine Earthquake at Hector Station, Comp. 090 .....	A-15
Figure A-15. 1979 Imperial Valley Earthquake at Delta Station, Comp. 262.....	A-16
Figure A-16. 1979 Imperial Valley Earthquake at Delta Station, Comp. 352.....	A-16
Figure A-17. 1979 Imperial Valley Earthquake at El Centro Array Station #11, Comp. 140.....	A-17
Figure A-18. 1979 Imperial Valley Earthquake at El Centro Array Station #11, Comp. 230.....	A-17
Figure A-19. 1995 Kobe, Japan Earthquake at Nishi-Akashi Station, Comp. 000 .....	A-18
Figure A-20. 1995 Kobe, Japan Earthquake at Nishi-Akashi Station, Comp. 090 .....	A-18
Figure A-21. 1995 Kobe, Japan Earthquake at Shin-Osaka Station, Comp. 000.....	A-19
Figure A-22. 1995 Kobe, Japan Earthquake at Shin-Osaka Station, Comp. 090.....	A-19
Figure A-23. 1999 Kocaeli, Turkey Earthquake at Duzce Station, Comp. 180 .....	A-20
Figure A-24. 1999 Kocaeli, Turkey Earthquake at Duzce Station, Comp. 270 .....	A-20
Figure A-25. 1999 Kocaeli, Turkey Earthquake at Arcelik Station, Comp. 000.....	A-21
Figure A-26. 1999 Kocaeli, Turkey Earthquake at Arcelik Station, Comp. 090.....	A-21
Figure A-27. 1992 Landers Earthquake at Yermo Fire Station, Comp. 270 .....	A-22
Figure A-28. 1992 Landers Earthquake at Yermo Fire Station, Comp. 360 .....	A-22
Figure A-29. 1992 Landers Earthquake at Coolwater Station, Longitudinal Direction .....	A-23
Figure A-30. 1992 Landers Earthquake at Coolwater Station, Transverse Direction .....	A-23
Figure A-31. 1989 Loma Prieta Earthquake at Capitola Station, Comp. 000 .....	A-24
Figure A-32. 1989 Loma Prieta Earthquake at Capitola Station, Comp. 090 .....	A-24
Figure A-33. 1989 Loma Prieta Earthquake at Gilroy Array Station #3, Comp. 000 .....	A-25
Figure A-34. 1989 Loma Prieta Earthquake at Gilroy Array Station #3, Comp. 090 .....	A-25
Figure A-35. 1990 Manjil, Iran Earthquake at Abbar Station, Longitudinal Direction .....	A-26
Figure A-36. 1990 Manjil, Iran Earthquake at Abbar Station, Transverse Direction.....	A-26

Figure A-37. 1987 Superstition Hills Earthquake at El Centro, Imperial County, Comp. 000 .....	A-27
Figure A-38. 1987 Superstition Hills Earthquake at El Centro, Imperial County, Comp. 090 .....	A-27
Figure A-39. 1987 Superstition Hills Earthquake at Poe Road, Comp. 270 .....	A-28
Figure A-40. 1987 Superstition Hills Earthquake at Poe Road, Comp. 360 .....	A-28
Figure A-41. 1992 Cape Mendocino Earthquake at Rio Dell Overpass, Comp. 270 .....	A-29
Figure A-42. 1992 Cape Mendocino Earthquake at Rio Dell Overpass, Comp. 360 .....	A-29
Figure A-43. 1999 Chi-Chi, Taiwan Earthquake at CHY101 Station, E-W Component .....	A-30
Figure A-44. 1999 Chi-Chi, Taiwan Earthquake at CHY101 Station, N-S Component .....	A-30
Figure A-45. 1999 Chi-Chi, Taiwan Earthquake at TCU045 Station, E-W Component .....	A-31
Figure A-46. 1999 Chi-Chi, Taiwan Earthquake at TCU045 Station, N-S Component .....	A-31
Figure A-47. 1971 San Fernando Earthquake at Los Angeles Hollywood Store Station, Comp. 090 ..	A-32
Figure A-48. 1971 San Fernando Earthquake at Los Angeles Hollywood Store Station, Comp. 180 ..	A-32
Figure A-49. 1976 Friuli, Italy Earthquake at Tolmezzo Station, Comp. 000 .....	A-33
Figure A-50. 1976 Friuli, Italy Earthquake at Tolmezzo Station, Comp. 270 .....	A-33
Figure B-1. Strength Design Lateral Forces and Story Shears .....	B-5
Figure B-2. Drift Design Lateral Forces and Story Shears .....	B-5
Figure B-3. Story Drift Ratios and Deflected Shape .....	B-6
Figure B-4. Strength Design Lateral Forces and Story Shears .....	B-7
Figure B-5. Drift Design Lateral Forces and Story Shears .....	B-8
Figure B-6. Story Drift Ratios and Deflected Shape .....	B-9
Figure B-7. Strength Design Lateral Forces and Story Shears .....	B-10
Figure B-8. Drift Design Lateral Forces and Story Shears .....	B-11
Figure B-9. Story Drift Ratios and Deflected Shape .....	B-12
Figure B-10. Strength Design Lateral Forces and Story Shears .....	B-14
Figure B-11. Drift Design Lateral Forces and Story Shears .....	B-14
Figure B-12. Story Drift Ratios and Deflected Shape .....	B-15
Figure B-13. Strength Design Lateral Forces and Story Shears .....	B-16
Figure B-14. Drift Design Lateral Forces and Story Shears .....	B-17
Figure B-15. Story Drift Ratios and Deflected Shape .....	B-17
Figure B-16. Strength Design Lateral Forces and Story Shears .....	B-19
Figure B-17. Drift Design Lateral Forces and Story Shears .....	B-20
Figure B-18. Story Drift Ratios and Deflected Shape .....	B-20
Figure B-19. SCBF Member Sizes, 8-Story RSA .....	B-29

## List of Abbreviations

AISC	American Institute of Steel Construction
ASCE	American Society of Civil Engineers
ASTM	American Society for Testing and Materials
ATC	Applied Technology Council
BPL	Building Performance Level
BSE	Basic Safety Earthquake
BSO	Basic Safety Objective
BSSC	Building Seismic Safety Council
CBF	Concentrically Braced Frame
CP	Collapse Prevention
DC	Deformation-Controlled
DCR	Demand to capacity ratio
EBF	Eccentrically Braced Frame
EHL	Earthquake Hazard Level
ELF	Equivalent Lateral Force
E-W	East-West
FC	Force-Controlled
FEMA	Federal Emergency Management Agency
FR	Fully Restrained
GSA	General Services Administration
GCR	Grant/Contract Report
HD	Highly Ductile
HSS	Hollow Structural Section
IBC	International Building Code
ICC	International Code Council
IEBC	International Existing Building Code
IO	Immediate Occupancy
LC	Load Combination
LDP	Linear Dynamic Procedure
LFRS	Lateral Force Resisting System
LRFD	Load and Resistance Factor Design

LS	Life Safety
LSP	Linear Static Procedure
LTB	Lateral Torsional Buckling
MC	Moment Curvature
MCE (MCE <sub>R</sub> )	Maximum Considered Earthquake
MD	Moderately Ductile
MR	Moment Rotation
MRSA	Modal Response Spectrum Analysis
MWFRS	Main Wind Force Resisting System
NDP	Nonlinear Dynamic Procedure
NEHRP	National Earthquake Hazards Reduction Program
NIBS	National Institute of Building Sciences
NIST	National Institute of Standards and Technology
NPL	Nonstructural Performance Level
N-S	North-South
NSP	Nonlinear Static Procedure
PBS	Public Buildings Service
PBSD	Performance-Based Seismic Design
RBS	Reduced Beam Section
RHA	Response History Analysis
RSA	Response Spectrum Analysis
SCBF	Special Concentrically Braced Frame
SCWB	Strong Column Weak Beam
SDC	Seismic Design Category
SDOF	Single Degree of Freedom
SEAONC	Structural Engineers Association of Northern California
SEI	Structural Engineering Institute
SFRS	Seismic Force Resisting System
SMF	Special Moment Frame
SPL	Structural Performance Level
SRSS	Square Root Sum of the Squares
W.P.	Work Point

## Executive Summary

This report presents the results of a study investigating the correlation between the seismic performance of an ASCE 7 code-compliant building and its performance as quantified using ASCE 41 analysis procedures and structural performance metrics. This investigation is performed by evaluating a suite of structural steel buildings in a high seismicity region that are designed using ASCE 7 and evaluated using ASCE 41. *The basic question is whether the standards for designing new steel buildings and assessing existing steel buildings provide consistent levels of performance.* An additional outcome of this research is to advance the state-of-knowledge in performance-based seismic design and assessment of buildings using ASCE 41. Further, results provide the technical background for provisions that target equivalent seismic performance between a new building and an existing building that is required to meet the seismic performance objective of a new building.

This report presents the results of a structural seismic performance assessment using ASCE 41 procedures and performance measures of buildings utilizing steel special concentrically braced frames (SCBF) as the lateral force-resisting system (LFRS).

A suite of archetype buildings that incorporate SCBFs along one principal direction of the buildings is designed in accordance with ASCE 7. The suite consists of 4-, 8-, and 16-story buildings designed using both the Equivalent Lateral Force (ELF) Procedure and Modal Response Spectrum Analysis (RSA). Both analysis procedures are used to provide a generally applicable range of LFRS strength within the selected seismic intensity region. As such, an LFRS may include significant overstrength to resist nonseismic loads or to satisfy other design criteria. A design space is created to investigate the effects of design methodology, building height and other LFRS-specific geometric modifications on seismic performance. In reality, the design space is infinitely large and many design choices made in this study can also have different configurations to evaluate the variation in performance specific to a design choice.

The seismic performance assessment of the building suite is conducted using both linear and nonlinear analysis procedures prescribed in ASCE 41:

- Linear Static Procedure (LSP)
- Linear Dynamic Procedure (Response Spectrum) (LDP)
- Nonlinear Static Procedure (NSP)
- Nonlinear Dynamic Procedure (NDP)

For this study, the performance assessment targets the Basic Safety Objective (BSO) prescribed in ASCE 41. This objective includes the interrelated goals of Life Safety (LS) Building Performance Level (BPL) at the Basic Safety Earthquake-1 (BSE-1) earthquake hazard level (EHL) and Collapse Prevention (CP) BPL at the BSE-2 EHL. This performance objective is chosen to align with the intended structural performance objective of an ordinary building in ASCE 7, which is qualitatively defined here as “life safety” provided by collapse prevention of the building, given a maximum considered earthquake (MCE) event.

To evaluate seismic assessment criteria, each component of the SCBFs is designated as a *primary* or component in accordance with ASCE 41 §2.2.5 (and ASCE 41 §2.4.4.2). Similarly, quantitative performance measures (i.e., acceptance criteria) for *primary* components are used for all assessment procedures, although performance measures for *secondary* components are permitted by ASCE 41 for some primary components. The consistent use of primary acceptance criteria keeps all components and associated assessment results correlated among the assessment procedures for this study.

The goals of this research are as follows:

- Assess *new* structural steel buildings utilizing SCBFs designed per ASCE 7 requirements and, in turn, evaluated using ASCE 41,
- Develop a qualitative link between the performance implied in ASCE 7 in light of the performance identified by ASCE 41 procedures and performance measures,
- Provide guidance or technical support for improved or new provisions in ASCE 41 (and to a lesser extent, ASCE 7),
- Reduce uncertainty in first-generation PBSD procedures for performance-based seismic assessment, and
- Identify any inconsistencies, ambiguities, and confusing provisions in ASCE 41.

The primary conclusions of this research can be divided into two parts: General Observations and Specific Observations about ASCE 41 analytical procedures.

A. *General Observations for Special Concentrically Braced Frames:*

- The LSP generally results in more conservative normalized demand to capacity ratios,  $DCR_N$ , values than that of the LDP, because of the differences in the distribution of seismic demands and the lack of modal representation other than the fundamental mode in the LSP.
- The NSP generally results in less conservative  $DCR_N$  values than that of the NDP, contrary to what would be expected with increasing the analytical complexity, because of the differences in the distribution of seismic demands and the lack of modal representation other than the fundamental mode in the NSP.
- The nonlinear procedures provide a more rigorous assessment approach as compared to the linear procedures. The results from the LSP, and to a lesser extent the LDP, indicate more performance failures in force-controlled components than identified using the nonlinear procedures. The results presented emphasize the inherent conservatism in the linear procedures. However, this conservatism is accompanied by a reduction in required analytical resources and proficiency of the analyst.
- The linear procedures can illustrate the trend in demands but may fail to highlight critical performance zones within a given frame.
- No clear consistency exists between linear assessment results and nonlinear assessment results for brace members. Contrary performance results indicate acceptance criteria that need further calibration.

B. *Specific Observations for Special Concentrically Braced Frames:*

The following significant observations and conclusions are based on the collective results obtained from the assessment of the SCBFs. More details about the specific items are in the relevant sections of the assessment discussion in Chapter 3.

- Analytical results based on component-level performances indicate, dependent on the assessment procedure used, that new SCBFs designed in accordance with ASCE 7, and its referenced standards, have difficulty achieving the ASCE 41 BSO for an existing building intended to be equivalent to a new building. This observation is driven by the performance of the braces and, to a lesser extent, the columns. Assessment results for brace members from the nonlinear procedures provide a conclusion opposite to that provided for the linear procedures in that nonlinear assessment reveals higher  $DCR_N$  values than the linear assessment.
- *Assuming* the archetype buildings meet the collapse performance objective of ASCE 7, the results of the assessment procedures indicate that ASCE 41 is generally conservative for SCBFs. ASCE 41 analysis would require retrofit or replacement of specific components of a code-compliant SFRS to satisfy the CP BPL, given an MCE event. The results highlight that columns (i.e., beam-columns) with high axial and flexural demands and brace members have difficulty in satisfying the performance criteria in ASCE 41. Future research is needed to couple the collapse performance objectives of the two standards, as well as other performance objectives associated with a seismic hazard with a lower return period.
- Analysis results indicate that the linear procedures generally give smaller  $DCR_N$  values than that obtained from nonlinear procedures, contrary to what would be expected from increasing the analytical complexity. Given a properly designed new brace member, the linear procedures will result in a maximum  $DCR_N$  of approximately the ratio of  $C_u T_a / T_1$ , which is less than or equal to unity.
- A significant number of brace members did not satisfy the acceptance criteria for the nonlinear procedures. Brace performance is based on high fidelity analytical modeling parameters (except for brace fracture); thus, room for brace modeling enhancement is limited, although alternative modeling practices could be investigated. Future research should investigate the influence of the loading protocol adopted to establish the deterministic acceptance criteria for brace members.
- A significant number of columns, primarily at the base of the frames, did not satisfy the ASCE 41 acceptance criteria. The results for columns can be enhanced by more mechanistically consistent assessment provisions and analytical modeling parameters for columns (e.g., column/brace-to-base connection modeling). Refinement of the relevant interaction equations to evaluate specific failure mechanisms could assist by allowing what would be a force-controlled column to be classified as “deformation-controlled”.
- Components of the SCBFs that do not satisfy the CP acceptance criteria would need to be strengthened to achieve the performance required by ASCE 41. However, the results from the various assessment procedures were seen to be inconsistent in some cases for a given design routine (i.e., LSP vs. NDP) or the same assessment procedure was inconsistent between design routines (i.e., ELF and RSA). This makes it difficult to definitively suggest that using ASCE 41 to design a new SCBF would produce a system capable of achieving the seismic performance objective of ASCE 7. Future research is needed to evaluate the collapse probability of a new system

strengthened by ASCE 41 relative to the seismic performance objective of ASCE 7. The same is required for a new system that has component strengths reduced from that required by ASCE 7 to meet an ASCE 41 performance objective. Further, the adequacy of the components of the enhanced frame (those required to satisfy ASCE 41) would be dependent upon which analysis procedure is used to iterate between design and assessment, and therefore the fidelity of the analytical model and analysis parameters.

- Results of this study indicate that for ASCE 41 to be used as a seismic design procedure for new steel buildings, as a performance-based alternative to ASCE 7 (see ASCE 7 §1.3.1.3), acceptance criteria for the various analysis methods must be calibrated to each other to consistently result in a uniform collapse risk. Additionally, ASCE 41 would need to reference material-specific design standards (e.g., AISC 341) for their seismic design requirements, as well as consistent requirements for defining acceptance criteria for a component (e.g., plastic rotation).

# Chapter 1 Introduction

In 1997, the Federal Emergency Management Agency (FEMA) published FEMA 273: *NEHRP Guidelines for the Seismic Rehabilitation of Buildings* (FEMA 1997) as a first step towards standardizing seismic performance assessment procedures for existing buildings. This effort, produced under the Applied Technology Council’s project 33 (ATC-33), was the first significant step in implementing performance-based seismic design (PBSD) into practice. Subsequently in 2000, FEMA and the American Society of Civil Engineers (ASCE) published FEMA 356: *Prestandard and Commentary for the Seismic Rehabilitation of Buildings* (FEMA 2000e). This publication introduced many changes to FEMA 273 to refine the accuracy and applicability of the provisions. The changes are chronicled in FEMA 357: *Global Topics Report on the Prestandard and Commentary for the Seismic Rehabilitation of Buildings* (FEMA 2000f). In 2006 ASCE published ASCE/SEI 41-06: *Seismic Rehabilitation of Existing Buildings* (ASCE 2006) as an ASCE Standard—hereafter referred to as ASCE 41. This document is referenced by the *International Existing Building Code* (IEBC) published by the International Code Council (ICC) (ICC 2012a).

ASCE 41 represents the current state-of-practice in seismic evaluation and rehabilitation of existing buildings. This standard is referenced by the California Building Standards Code (CBSC 2010), Federal government building standards (e.g., NIST 2011a), and a number of other local jurisdictions. ASCE 41 provides analytical procedures and criteria for evaluating buildings and designing seismic retrofits based on a defined performance goal (i.e., Life Safety and Collapse Prevention). This ability to explicitly define a performance goal and then assess a building design against that goal has led practitioners to adapt ASCE 41 methodology for use in new building design. The performance-based methodologies in ASCE 41 provide an alternative to the traditional prescriptive approaches used in the current standard for new buildings, ASCE/SEI 7-10: *Minimum Design Loads for Buildings and Other Structures* (ASCE 2010)—hereafter referred to as ASCE 7. Referenced by the *International Building Code* (IBC) (ICC 2012b), ASCE 7 is widely used throughout the country for seismic design of new buildings. However, with the trend toward performance-based design, the correlation between the performance of a building designed with the prescriptive provisions of ASCE 7 and assessed with the performance-based provisions of ASCE 41 is largely unknown.

The next version of ASCE 41 (ASCE 41-13<sup>1</sup>) will offer a new track for application of the provisions to existing buildings whose performance goal is equivalent to that of a building designed with the new building standard. Consequently, this new track will allow direct seismic performance assessment of new buildings or, alternatively, a substitute seismic design approach via Chapter 1 of ASCE 7. For example, the PBS-P100: *Facility Standards for the Public Buildings Service* (GSA 2012) prescribes that ASCE 41-06 shall

---

<sup>1</sup> ASCE 41-13: *Seismic Evaluation and Retrofit of Existing Buildings* (ASCE 2014) was being developed during this project period. As such, new or updated provisions in ASCE 41-13 were not incorporated, except where changes were required to align with the seismic hazard prescribed in ASCE 7-10.

be used for the seismic design of new GSA facilities<sup>2</sup> and that the guidelines from ASCE 41 are intended to be applied to new buildings. This document does not permit a building to be designed for seismic performance below the minimum level specified by IBC. The National Institute of Building Sciences (NIBS) is using PBS-P100 as the basis for developing their *National Performance Based Design Guide* (NIBS 2013). Further, the Provisions Update Committee for the Building Seismic Safety Council is currently deliberating expanded provisions for performing nonlinear response history analysis (Chapter 16 in ASCE 7) for the 2015 edition of the *NEHRP Recommend Provisions for Seismic Regulations for New Buildings and Other Structures* (FEMA 2015). These expanded provisions reference ASCE 41-13 in the commentary for modeling and acceptance criteria for the design of new buildings.

This report presents the results of a study investigating the correlation between the seismic performance of an ASCE 7 code-compliant building and its performance as quantified using ASCE 41 analysis procedures and structural performance metrics. This investigation is performed by evaluating a suite of structural steel buildings in a high seismicity region that are designed using ASCE 7 and evaluated using ASCE 41. *The basic question is whether the standards for designing new steel buildings and assessing existing steel buildings provide consistent levels of performance.* The intended outcome of this research is to advance the state-of-knowledge in performance-based seismic design and assessment of buildings using ASCE 41. Further, results provide the technical background for provisions that target equivalent seismic performance between a new building and an existing building that is required to meet the seismic performance objective of a new building.

### **Applicability of ASCE 41-13 to this Study**

During this project, ASCE/SEI 41-13, *Seismic Evaluation and Retrofit of Existing Buildings* (ASCE 2014), completed committee balloting and was sent out for public comment as well as for approval for inclusion in the IEBC. Any significant differences between ASCE 41-06 and ASCE 41-13 regarding assessment of steel structural systems will be highlighted in the discussions where applicable—unless otherwise noted, reference to ASCE 41 refers only to ASCE 41-06.

One significant addition to ASCE 41-13 is a process for applying the provisions for the seismic assessment of *existing* buildings where the intended performance is equivalent to that which is intended for new buildings designed in accordance with ASCE 7, including a correlation matrix between the two standards. While ASCE 41-06 is being used currently in practice to justify seismic performance of new buildings in compliance with ASCE 7 (as well as to identify noncompliance), this addition is the first step in conceptually aligning future editions of ASCE 41 and ASCE 7 so that ASCE 41 can be used for the seismic design of new buildings. Still, there are variations between material-specific provisions in ASCE 41 and provisions in material design standards referenced in ASCE 7 (e.g., AISC 360 and ACI 318) that need to be resolved.

---

<sup>2</sup> The seismic hazard used to characterize the design basis earthquake is that with a 10% probability of exceedence in 50 years. This differs from that used in ASCE/SEI 7-05 (ASCE 2005)—two-thirds of that with a 2% probability of exceedence in 50 years—and ASCE 7-10—two-thirds of that producing a 1% probability of collapse in 50 years.

In terms of assessment of steel systems, the technical content in ASCE 41-13 did not change in any significant manner that invalidates the results presented in this report. The few changes that would affect the results of individual components are highlighted where applicable. In fact, data from this study instigated some of these changes.

## **1.1 Project Motivation and Background**

Traditional prescriptive seismic provisions for new buildings principally concentrate on the Life Safety objective applied to all-encompassing arrangements of similar lateral force-resisting systems. Little consideration is given to either the actual performance of individual buildings or the economic loss and occupancy interruption that may occur after an earthquake. Thus, a need arises for seismic provisions that allow engineers to design buildings and assess them against varying levels of performance associated with varying levels of earthquake hazard. So doing provides a method where desired building damage levels can be coupled to both quantitative and qualitative definitions of performance so that building and operational stakeholders are integrated into a project. Conceptually, PBSD was conceived to satisfy this need. The objective of PBSD is to provide a means of integrating additional performance objectives into the seismic design of new buildings that explicitly measure and account for risk of casualties, occupancy interruption, and economic loss including repair costs.

Prescriptive building code procedures, such as those found in ASCE 7, tend to restrict design innovation and can lead to inefficient structural designs and higher construction costs. In lieu of its prescriptive provisions, ASCE 7 allows alternative “rational” design methods, such as PBSD, to be used in new building design. PBSD affords the designer the freedom to bypass prescriptive building code provisions by demonstrating that a building performs to an explicitly defined performance target that equals or exceeds the life safety objective in prescriptive provisions. The use of such methods must be approved by the local authority having jurisdiction and typically requires rigorous structural analysis coupled with a high level of expertise.

Although ASCE 7 allows PBSD (see ASCE 7 §1.3.1.3) to be used in new building design, it provides no substantial guidance on implementing PBSD for this purpose. Therefore, many practitioners and local authorities have turned to the provisions in ASCE 41 as a way of implementing PBSD into new building design. These provisions, widely considered to be “first generation” PBSD principles, were originally intended to be used in the evaluation of existing buildings by assessing performance compliance with a selected rehabilitation objective. Since ASCE 41 is applicable to existing buildings, it does not provide a direct correlation between the rehabilitation objective and the intended performance of an ASCE 7 code-compliant new building (see Table 1-1). However, the IEBC does provide a correlation between ASCE 41 performance levels and IBC (and thus ASCE 7) Risk Categories, thus providing the link between the prescriptive requirements for new building design and the nonprescriptive requirements of existing building assessment and PBSD. A matrix showing this correlation is shown in Table 1-2. Still, this matrix has not been comprehensively validated nor have the seismic performance expectations for new buildings been quantitatively assessed to standardize acceptable performance within the framework of ASCE 41, or vice versa. ASCE 7 has not expressly adopted Table 1-2 for seismic design.

**Table 1-1. Comparison of Seismic Hazard and Associated Performance for ASCE 7 and ASCE 41**

		Target Building Performance Level <sup>1</sup>			
		Operational	Immediate Occupancy (IO)	Life Safety (LS)	Collapse Prevention (CP)
Earthquake Hazard Level	ASCE 41 50% / 50 year <sup>2</sup>	ASCE 41 (nonstructural)	ASCE 41 Limited	ASCE 41 Limited	ASCE 41 Limited
	ASCE 41 20% / 50 year <sup>2</sup>	ASCE 41 Enhanced	ASCE 41	ASCE 41 Limited	ASCE 41 Limited
	ASCE 7 "Frequent" <sup>1</sup>	ASCE 7 Risk Category III & IV	ASCE 7 Risk Category I & II (anticipated) <sup>3</sup>	N.A.	N.A.
	ASCE 41 BSE-1 ~ 10% / 50 year <sup>2</sup>	ASCE 41 Enhanced	ASCE 41 Enhanced	ASCE 41 BSO	ASCE 41 Limited
	ASCE 7 $\frac{2}{3} \times MCE_R$ <sup>1</sup>	N.A.	ASCE 7 Risk Category III & IV	ASCE 7 Risk Category I & II (design)	N.A.
	ASCE 41 BSE-2 ~ 2% / 50 year <sup>2</sup>	ASCE 41 Enhanced	ASCE 41 Enhanced	ASCE 41 Enhanced	ASCE 41 BSO
ASCE 7 $MCE_R$ <sup>1</sup>	N.A.	N.A.	ASCE 7 Risk Category III & IV	ASCE 7 Risk Category I & II (objective) <sup>3</sup>	

1. Seismic hazard defined in ASCE 7-10.
2. Seismic hazard defined in ASCE 41-06.
3. See ASCE 7, Expanded Seismic Commentary (ASCE 7-10 3<sup>rd</sup> printing).

**Table 1-2. Performance Comparison between IBC and ASCE 41 – (From IEBC Table 301.1.4.1)**

Risk Category (Based on IBC Table 1604.5)	Performance Level for use with ASCE 41 BSE-1 Earthquake Hazard Level	Performance Level for use with ASCE 41 BSE-2 Earthquake Hazard Level
I	Life Safety (LS)	Collapse Prevention (CP)
II	Life Safety (LS)	Collapse Prevention (CP)
III	Note a	Note a
IV	Immediate Occupancy (IO)	Immediate Occupancy (IO)

- a. Acceptance criteria for Risk Category III shall be taken as 80 percent of the acceptance criteria specified for Risk Category II performance levels, but need not be less than the acceptance criteria specified for Risk Category IV performance levels

In June 2008 the National Earthquake Hazards Reduction Program (NEHRP) sponsored a PBSB workshop for leading practitioners and researchers from around the United States to develop a comprehensive list of research needs to foster full development and implementation of PBSB. From this workshop, the Building Seismic Safety Council (BSSC) reported a prioritized list of key PBSB research and implementation needs in NIST GCR 09-917-2: *Research Required to Support Full Implementation of Performance-Based Seismic Design* (NIST 2009a). The highest priority need identified in this report was to “benchmark” current PBSB methodologies (e.g., ASCE 41) with code procedures for design of new buildings. Two observations from the report were that among workshop participants (1) ASCE 41 procedures are perceived to be overly

conservative and (2) existing PBSB methods are not accepted by practitioners as providing a uniform level of confidence. A supporting reason for these two observations was that no systematic effort had been undertaken to benchmark structural performance as determined using ASCE 41 procedures, together with widely accepted procedures for designing new buildings using ASCE 7.

Additionally, needs for the advancement of PBSB have been highlighted by other researchers and practitioners (Toranzo-Dianderas 2009, SEAONC 2010, Paret, Searer, and Freeman 2011, and Pekelnicky and Poland 2012). The needs identified include, but are not limited to the following:

- Calibration / comparison of ASCE 41 to ASCE 7
- Reduced conservatism in linear procedures and acceptance criteria
- Better clarification of provisions and intent

Therefore, the research study presented in this report was undertaken in an effort to address some of these needs.

## 1.2 Scope of Project

This report presents the results of a structural seismic performance assessment using ASCE 41 procedures and performance measures of buildings utilizing steel special concentrically braced frames (SCBF) as the lateral force-resisting system (LFRS)<sup>3</sup>.

A suite of archetype buildings that incorporate SCBFs along one principal direction of the buildings is designed in accordance with ASCE 7. The suite consists of 4-, 8-, and 16-story buildings designed using both the Equivalent Lateral Force (ELF) Procedure and Modal Response Spectrum Analysis (RSA). Both analysis procedures are used to provide a generally applicable range of LFRS strength within the selected seismic intensity region. As such, components of an LFRS may include significant overstrength<sup>4</sup> to resist nonseismic loads or to satisfy other design criteria. A design space is created to investigate the effects of design methodology, building height, and other LFRS-specific geometric modifications on seismic performance. In reality, the design space is infinitely large and many design choices made in this study can also have different configurations to evaluate the variation in performance specific to a design choice (e.g., study of a locations to change brace sizes—every story, two, or four, etc.).

The seismic performance assessment of the building suite is conducted using both linear and nonlinear analysis procedures prescribed in ASCE 41:

- Linear Static Procedure (LSP)

---

<sup>3</sup> Although the LFRS is a component of a cohesive three-dimensional building system that includes structural framing intended to primarily resist gravity loads and nonstructural components, only the performance of the LFRS as identified by ASCE 41 procedures and measures is presented. The performance of an LFRS can be influenced by the inclusion of gravity framing in a analysis. Based on the analytical modeling used in this study, this interaction is deemed to be negligible because the LFRS resists nearly all forces and deformations resulting from lateral loads and movement.

<sup>4</sup> Overstrength is defined here as the additional elastic strength in a component that is in excess of the required minimum seismic strength.

- Linear Dynamic Procedure (Response Spectrum) (LDP)
- Nonlinear Static Procedure (NSP)
- Nonlinear Dynamic Procedure (NDP)

For this study, the performance assessment targets the Basic Safety Objective (BSO) prescribed in ASCE 41. This objective includes the interrelated goals of Life Safety (LS) Building Performance Level (BPL) at the Basic Safety Earthquake-1 (BSE-1) earthquake hazard level (EHL) and Collapse Prevention (CP) BPL at the BSE-2 EHL (see Table 1-2 above). This performance objective is chosen to align with the intended structural performance objective of an ordinary building<sup>5</sup> in ASCE 7, which is qualitatively defined here as “life safety” provided by collapse prevention of the building, given a maximum considered earthquake (MCE) event.

To evaluate seismic assessment criteria, each component of the SCBFs is designated as a *primary* member (or component) in accordance with ASCE 41 §2.2.5 (and ASCE 41 §2.4.4.2). Similarly, quantitative performance measures (i.e., acceptance criteria) for *primary* components are used for all assessment procedures, although performance measures for *secondary* components are permitted by ASCE 41 for some primary components. The consistent use of primary acceptance criteria keeps all components and associated assessment results correlated among the assessment procedures for this study.

The goals of this research are as follows:

- Assess *new* structural steel buildings utilizing SCBFs designed per ASCE 7 requirements and, in turn, evaluated using ASCE 41,
- Develop a qualitative link between the performance implied in ASCE 7 in light of the performance identified by ASCE 41 procedures and performance measures,
- Provide guidance or technical support for improved or new provisions in ASCE 41 (and to a lesser extent, ASCE 7),
- Reduce uncertainty in first-generation PBSB procedures for performance-based seismic assessment, and
- Identify any inconsistencies, ambiguities, and confusing provisions in ASCE 41.

This report does not discuss the correlation between deterministic performance metrics for components (e.g., *m*-factor in ASCE 41) and the system (e.g., *R*-factor in ASCE 7)—a topic for future research and one that is required to develop a qualitative link between the performance of an ASCE 7 code-compliant design and the associated performance identified by ASCE 41 procedures and performance measures. Here, it is assumed that the acceptance criteria for each BPL in ASCE 41 Chapter 5 are quantitatively rational and accurate interpretations of what deformations / actions are appropriate for the intended structural performance (see ASCE 41 Tables C1-2, C1-3, and C1-4). Clearly, this is a subjective and, at times, controversial topic, as some component actions are physically qualified only by experimental test results (i.e., SAC project, see FEMA 351 (FEMA 2000b)), but not necessarily for all performance levels.

---

<sup>5</sup> Buildings assigned Risk Category I or II.

In this report, the archetype building designs are presented in Chapter 2. Next, the results from the seismic assessment in accordance with ASCE 41 and supplementary discussions are presented in Chapter 3. In the discussion of the assessment results, special focus is given to highlighting any notable differences or similarities between ASCE 41 and ASCE 7 (including the referenced design standards in ASCE 7 for the design of structural steel buildings) and to making suggestions for improvements in ASCE 41. Conclusions are provided in Chapter 4. Selection and scaling of ground motions, including pertinent ground motion data, for the NDP are provided in Appendix A. Additional information applicable to the design of the archetype buildings and detailed design calculations for a few example members and connections are provided in Appendix B. Detailed assessment calculations for a few example members and connections are provided in Appendix C.

The hope is that other follow-on projects will be undertaken by NIST and / or other organizations to provide additional data sets that advance the state-of-practice and state-of-knowledge and facilitate the implementation of performance-based seismic engineering in design of buildings. Further studies of structural steel systems (e.g., buckling-restrained braced frames), as well as studies of reinforced concrete moment frame and shear wall buildings, are planned as next steps at NIST.



## Chapter 2 Overview and Design of Archetype Buildings

This chapter presents the design of the archetype buildings. General discussions are provided in Section 2.1 on the geometry of the buildings and the design criteria, including sizes of structural members not considered to principally resist lateral loads. Section 2.2 discusses the structural design loads and associated design criteria specific to them. Section 2.3 presents information regarding the structural analysis and mathematical model used in the structural member selection process. Section 2.4 provides the design of the structural systems principally required to resist lateral loads and stabilize the buildings.

### 2.1 General Information

A suite of three steel-framed office buildings is investigated in this study. It is presumed that the archetype buildings will be constructed in a high seismicity area (e.g., somewhere along the west coast of the United States—see Earthquake Forces section below). Building stability and resistance to environmental loads and deformations is provided by special moment frames along the East-West (E-W) direction and special concentrically braced frames along the North-South (N-S) direction. All lateral force-resisting systems (LFRS) are symmetrically located at the perimeter of the building and orthogonal. For purposes of design, the identified LFRS acts as both the seismic force-resisting system (SFRS) and the main wind force-resisting system (MWFRS). For completeness of the full design of the archetype buildings, design of both LFRSs is presented below. However, only the assessment of the braced frames will be presented in this report. Assessment of the moment frames is presented in NIST TN 1863-1: *Assessment of First Generation Performance-Based Design Methods for New Steel Buildings, Volume 1: Special Moment Frames* (Harris and Speicher 2015).

Each building is rectangular in plan, with five 30-foot bays in the E-W direction and generally five 20-foot bays in the N-S direction. The plan dimensions for all floors and roofs are 152 feet in the E-W direction and 102 feet in the N-S direction. For all buildings, the height of the first story is 18 feet and the remaining story heights are 14 feet. A summary of the geometric structural characteristics of each building is provided in Table 2-1. Building schematics are shown in Figure 2-1 through Figure 2-3. The typical floor framing plan is shown in Figure 2-4 and Figure 2-5. For brevity, the building schematics do not show symmetrical elevator core or stairwell diaphragm openings.

**Table 2-1. Structural Characteristics of Archetype Buildings**

Bldg. ID	Stories	E-W Dimension	N-S Dimension	E-W LFRS	N-S LFRS	Notes
MC4	4	150' = 5 bays @ 30'	100' = 5 bays @ 20'	SMF	SCBF	SMF: 3–30-foot bays SCBF: 1–20-foot bay inverted ‘V’ (Chevron) with HSS braces
MC8	8	150' = 5 bays @ 30'	100' = 5 bays @ 20'	SMF	SCBF	SMF: 3–30-foot bays SCBF: 1–20-foot bay two-story X-bracing with HSS braces
MC16	16	150' = 5 bays @ 30'	100' = Varies – see Figure 2-5	SMF	SCBF	SMF: 3–30-foot bays SCBF: 2–30-foot bays two-story X-bracing with HSS braces




Figure 2-1. Isometric View of MC4 Archetype Building





Figure 2-2. Isometric View of MC8 Archetype Building



**Figure 2-3. Isometric View of MC16 Archetype Building**




Figure 2-4. Typical Floor Framing Plan, MC4 and MC8




Figure 2-5. Typical Floor Framing Plan, MC16

The archetype buildings are analyzed and designed for all load effects in accordance with the following:

- IBC 2012: *International Building Code* (ICC 2012b)
- ASCE 7-10: *Minimum Design Loads for Buildings and Other Structures* (ASCE 2010)
- AISC 360-10: *Specification for Structural Steel Buildings* (AISC 2010a)
- AISC 341-10: *Seismic Provisions for Structural Steel Building* (AISC 2010b)
- AISC 358-10: *Prequalified Connections for Special and Intermediate Steel Moment Frames for Seismic Applications* (AISC 2010c)

The following material types and corresponding nominal properties were assumed in design:

- Wide-Flange Sections: A992 Grade 50,  $F_y = 50$  ksi,  $R_y = 1.1$
- HSS Sections: A500 Grade B,  $F_y = 46$  ksi,  $R_y = 1.4$
- Connections: A572 Grade 50,  $F_y = 50$  ksi,  $R_y = 1.1$
- $E = 29000$  ksi,  $G = 11200$  ksi,  $\nu = 0.3$

The archetype buildings do not contain any geometry-based or configuration-based horizontal irregularities, Type 2, 3, 4, or 5 as defined in ASCE 7 Table 12.3-1. Horizontal irregularity Type 1 is dependent on post-design analysis verification, and is presented in Appendix B. Similarly, the archetype buildings do not contain any geometry-based or configuration-based vertical irregularities, Type 2, 3, or 4 as defined in ASCE 7 Table 12.3-2. Vertical irregularity Types 1 and 5 are dependent on post-design analysis verification and are presented in Appendix B. The buildings are classified as Risk Category II structures in accordance with ASCE 7 §1.5.

## **2.2 Structural Design Loads**

### **2.2.1 Load Combinations**

Loads and load combinations used for analysis and strength design of members and connections are in accordance with ASCE 7 §2.3, including modifications to these combinations prescribed in ASCE 7 §12.4. This resulted in 189 load combinations for design of each component. Capacity design provisions for each SFRS type prescribed in AISC 341 as well as for beam-to-column connections in an SMF prescribed in AISC 358 provided several design load combinations in addition to those from ASCE 7.

Loads and load combinations for serviceability analysis and verification (e.g., wind drift), and seismic drift analysis and allowable drift compliance verification are discussed subsequently under Environmental Loads, §2.2.3.

### **2.2.2 Gravity Loads**

The floor and roof dead load consists of the weight of the steel members, metal deck, and concrete slab weight (3¼ inch lightweight concrete at 110 pcf on 18-gage, 3 inch metal deck  $\approx 46$  psf). Superimposed dead loads are taken as 15 psf for floors and 10 psf for the roof, representing mechanical, electrical, plumbing, and miscellaneous dead loads. A 250 plf superimposed dead load is also applied to the perimeter

horizontal framing to account for façade (curtain wall) weight. The edge of the slab is 1 foot from the perimeter framing. The design live load (unreduced) is 50 psf for floors and 30 psf for the roof (increased live load within egress areas is neglected in this study). A summary of the design gravity loads is presented in Table 2-2.

**Table 2-2. Design Gravity Loads**

Load	Load Type	Magnitude
Dead, $D$	Dead	46 psf <sup>1</sup>
Floor Superimposed Dead, $SD$	Dead	15 psf
Roof Superimposed Dead, $SD$	Dead	10 psf
Façade Dead (Curtain Wall), $SD$	Dead	250 plf
Unreduced Design Floor Live, $L_o$	Floor Live	50 psf (Office)
Unreduced Design Roof Live, $L_o$	Roof Live	30 psf <sup>2</sup>

<sup>1</sup> Weight of slab and metal deck only. Self-weight of steel components are included automatically in the structural analysis.

<sup>2</sup> 10 psf was added to the roof live load to represent non-inertial service equipment weight.

Verification of serviceability criteria under gravity loads is performed per IBC §1604.3, ASCE 7 §1.3.2, and AISC 360 Chapter L.

## 2.2.3 Environmental Loads

### 2.2.3.1 Earthquake Forces

The archetype buildings are located where it is assumed they would be assigned a Seismic Design Category (SDC) at the upper limit of D (i.e.,  $D_{max}$ —see footnote 6). Two designs are produced for each archetype building height and frame type as follows:

- One design using the ELF procedure per ASCE 7 §12.8 to determine the equivalent seismic effects.
- One design using the RSA procedure per ASCE 7 §12.9 to determine the equivalent seismic effects.

Two designs are performed to provide a common range of potential system strengths for seismic assessment using ASCE 41, and to a lesser extent, provide comparison points between the two design methodologies. There are cases when the two designs do not result in different member sizes because of material-specific minimum requirements. Further, wind effects are determined from statically applied design forces and thus the analysis method for wind does not vary between the two seismic analyses.

For the RSA procedure, enough modes are included in each principal direction to exceed 90 percent mass participation in both horizontal orthogonal directions. Masses were not modeled in the analysis to address vertical accelerations. Design forces determined from the RSA are scaled up so that the total modal base shear for design is equal to 85 percent of the corresponding base shear from applying the ELF procedure; story drifts are not scaled for verifying seismic drift compliance. Application of orthogonal seismic forces and accidental eccentricity prescribed in ASCE 7 §12.5 and ASCE 7 §12.8.4, respectively, are considered in the strength design analysis. The redundancy factor,  $\rho$ , is taken as 1.0 for each SFRS, and therefore does not affect the allowable seismic drift limits along the E-W direction (moment frames).

<sup>6</sup> See FEMA P695: *Quantification of Building Seismic Performance Factors* (FEMA 2009a) for further information.

Effective seismic weights for computing the horizontal earthquake forces are determined from dead loads plus 20 percent of the unreduced design floor live loads to represent partition weight (i.e.,  $0.2 \times 50 \text{ psf} = 10 \text{ psf}$ ). The effective seismic weights (lumped at each level) are tabulated in Appendix B. It is assumed in this study that there is no snow load on the building.

The story gravity loads for seismic drift analysis prescribed in ASCE 7 §12.8.6 (including period calculation) and stability verification prescribed in ASCE 7 §12.8.7 are determined from dead loads plus 25 percent of the unreduced floor live loads (i.e.,  $0.25 \times L_o \approx 0.5L$  where  $L$  is the *reduced* floor live loads). Roof live loads are considered not to be present for seismic drift analysis. The effective lumped gravity load acting on a story is tabulated in Appendix B. Vertical seismic loads are considered for strength design but not for drift or stability compliance. Similarly, application of orthogonal seismic forces and accidental eccentricity are not considered in the drift analysis because story drifts are computed at the center of mass (which aligns with the center of stiffness) of each story because of building symmetry and regularity. The centers of mass for all stories are vertically aligned.

The seismic hazard in ASCE 7 is based on a risk-targeted design philosophy and is defined as ground motions having a one percent probability of causing total or partial structural collapse (i.e., “risk”) of an appropriately designed structure in 50 years (except in areas controlled by the deterministic cap<sup>7</sup> on ground motions). This ground motion intensity is denoted in ASCE 7 as  $MCE_R$ . The following parameters summarize the seismic hazard used for design:

- Building Risk Category: II
- Site Soil Conditions: Site Class D, Stiff Soil – ASCE 7 Table 20.3-1
- Spectral Response Acceleration Parameters: shown in Table 2-3
- SDC: D—taken as  $D_{max}$  as used in FEMA P695

**Table 2-3. Spectral Response Acceleration Parameters**

SDC	$S_s$ (g)	$S_1$ (g)	$F_a$	$F_v$	$S_{MS}$ = $F_a S_s$ (g)	$S_{M1}$ = $F_v S_1$ (g)	$S_{DS}$ = $\frac{2}{5} S_{MS}$ (g)	$S_{D1}$ = $\frac{2}{5} S_{M1}$ (g)	$3.5 \times T_s$ (sec)
$D_{max}$	1.50	0.60 <sup>1</sup>	1.00	1.50	1.50	0.90	1.00	0.60	2.1

1.  $S_1$  is actually just under 0.60 (i.e., 0.599)

Allowable seismic drift limit is set to  $h_{sx} / 50$  (for amplified story drifts, see ASCE 7 §12.12) where  $h_{sx}$  is the story height below the level under consideration. Composite action between the beams of the SFRS and the concrete slab is not considered for checking seismic drifts or when computing the fundamental period,  $T_1$ . This action is commonly neglected in seismic analysis and design because research has shown that the slab does not contribute significantly to the strength or stiffness of the assembly at significant inelastic deformations (see FEMA 355D (FEMA 2000c)).

The seismic analysis and design parameters for each archetype building are provided in Table 2-4 for the E-W direction and Table 2-5 for the N-S direction. There is one archetype building system that is *not*

<sup>7</sup> Regions where probabilistic-based ground motion parameters exceed those resulting from deterministic ground motions based on the characteristic magnitudes of earthquakes from well-defined active fault systems.

permitted to be designed with the ELF procedure because its design period,  $C_u T_a$ , is greater than  $3.5 \times T_s$  (see ASCE 7 §12.6): E-W component of MC16 (SMF)—this system is shaded in Table 2-4. This frame is included to make a seismic performance comparison. Furthermore, ASCE 7 is vague about which  $T$  is referenced in ASCE 7 §12.6. For example, although the capped fundamental period ( $T = C_u T_a$ ) may satisfy  $3.5 \times T_s$ , the actual fundamental period ( $T = T_1$ ) may not, indicating that the ELF procedure may be used for strength design but not used for drift verification per ASCE 7 §12.8.6.2. Consequently, the same analysis procedure was used for both strength design and computation of the design story drifts in this study.

**Table 2-4. Seismic Analysis and Design Parameters, E-W**

Building	MC4		MC8		MC16	
SFRS	SMF		SMF		SMF	
$R, C_d, \Omega_o$	8, 5.5, 3		8, 5.5, 3		8, 5.5, 3	
$C_u T_a$ (seconds)	1.04		1.76		3.02	
ELF Permitted?	Yes		Yes		No <sup>8</sup>	
Height Limit (feet)	No Limit		No Limit		No Limit	
Analysis Procedure	ELF	RSA	ELF	RSA	ELF	RSA
$W^1$ (kips)	5172	5136	10618	10527	21782	21649
$V_b^1$ Design (kips)	374	316	467 <sup>2</sup>	394 <sup>2</sup>	958 <sup>2</sup>	810 <sup>2</sup>
$V_b^1$ Drift (kips)	213	166	273	192	375	295
RSA Scaling Factor <sup>3</sup>	NA	Design = 93 Drift = 266	NA	Design = 101 Drift = 266	NA	Design = 134 Drift = 266
$T_1^4$ (seconds)	1.82	2.22	2.91	3.81	4.36	5.01
$T_2^4$ (seconds)	0.55	0.61	1.02	1.30	1.58	1.83
$T_3^4$ (seconds)	0.26	0.29	0.56	0.68	0.91	1.05
$T_1^5$ (seconds)	1.83	2.24	2.94	3.86	4.40	5.07
$T_1^6$ (seconds)	1.77	2.12	2.79	3.55	4.15	4.70
Steel Wgt. <sup>7</sup> (tons)	37	29	74	53	193	163

**Notes:**

- <sup>1</sup> Inertial mass computed from Dead + Superimposed Dead + 0.2×Floor Live.  $W$  for ELF and RSA differ because of member size differences.
- <sup>2</sup>  $0.044 S_{DS} I_e$  min. controls strength design (not applied for drift).
- <sup>3</sup> Scaling for design =  $g \times I_e / R \times (0.85 \times V_{b,ELF}) / V_{b,RSA}$ . Scaling for drift =  $g \times I_e / R \times C_u / I_e$ . Scaling assumes the spectrum is defined as a function of  $g$ .
- <sup>4</sup> Computed from a second-order eigenvalue analysis with Dead + Superimposed Dead + 0.25×Floor Live gravity load.
- <sup>5</sup> Computed from a second-order eigenvalue analysis with 1.2×Dead + 1.2×Superimposed Dead + 0.25×Floor Live gravity load.
- <sup>6</sup> Computed from a first-order eigenvalue analysis.
- <sup>7</sup> Per single SFRS (see Table 1-1). Does not include connection or miscellaneous steel.
- <sup>8</sup> Analysis procedure not permitted per ASCE 7 §12.6. Shaded Area: design is included for seismic performance comparison purposes.

**Table 2-5. Seismic Analysis and Design Parameters, N-S**

Building	MC4		MC8		MC16	
SFRS	SCBF		SCBF		SCBF	
$R, C_d, \Omega_o$	6, 5, 2		6, 5, 2		6, 5, 2	
$C_u T_a$ (seconds)	0.60		0.99		1.64	
ELF Permitted?	Yes		Yes		Yes	
Height Limit (feet)	240		240		240	
Analysis Procedure	ELF	RSA	ELF	RSA	ELF	RSA
$W^1$ (kips)	5172	5136	10618	10527	21782	21649
$V_b^1$ Design (kips)	857	723	1073	904	1326	1120
$V_b^1$ Drift (kips)	782	627	735	633	1089	945
RSA Scaling Factor <sup>3</sup>	NA	Design = 74 Drift = 322	NA	Design = 92 Drift = 322	NA	Design = 76 Drift = 322
$T_1^4$ (seconds)	0.67	0.72	1.45	1.50	2.08	2.14
$T_2^4$ (seconds)	0.27	0.28	0.48	0.49	0.70	0.71
$T_3^4$ (seconds)	0.18	0.19	0.27	0.28	0.39	0.40
$T_1^5$ (seconds)	0.67	0.72	1.45	1.51	2.09	2.14
$T_1^6$ (seconds)	0.66	0.71	1.43	1.49	2.06	2.11
Steel Wgt. <sup>7</sup> (tons)	13	12	28	27	127	123

**Notes:**

- <sup>1</sup> Inertial mass computed from Dead + Superimposed Dead + 0.2×Floor Live.  $W$  for ELF and RSA differ because of member size differences.
- <sup>2</sup>  $0.044 S_{DS} I_e$  min. controls strength design (not applied for drift).
- <sup>3</sup> Scaling for design =  $g \times I_e / R \times (0.85 \times V_{b,ELF}) / V_{b,RSA}$ . Scaling for drift =  $g \times I_e / R \times C_u / I_e$ . Scaling assumes the spectrum is defined as a function of  $g$ .
- <sup>4</sup> Computed from a second-order eigenvalue analysis with Dead + Superimposed Dead + 0.25×Floor Live gravity load.
- <sup>5</sup> Computed from a second-order eigenvalue analysis with 1.2×Dead + 1.2×Superimposed Dead + 0.25×Floor Live gravity load.
- <sup>6</sup> Computed from a first-order eigenvalue analysis.
- <sup>7</sup> Per single SFRS (see Table 1-1). Does not include connection or miscellaneous steel.

The difference in the stiffness and strength of the SCBFs provided by the ELF and RSA procedures is negligible. This is primarily due to design provisions prescribed in AISC 341 (e.g., minimum width-to-thickness ratios for highly ductile braces). A summary of the equivalent seismic forces for each archetype building is provided in Appendix B.

### 2.2.3.2 Wind Forces

Basic wind speeds are taken from the ASCE 7 wind maps based on locations along the west coast that would have a high probability of producing structures assigned to SDC D. The basic wind speed is taken to be 110 mph for the 700-year wind for strength design of components and 72 mph for the 10-year wind for verifying story drifts (serviceability). Each archetype building is assigned to Exposure B and is not considered rigid, with gust factors,  $G_f$ , for each principal direction computed assuming two percent damping. Torsional wind effects are considered, and the directionality factor,  $k_d$ , is 0.85. A summary of the wind forces for each archetype building is provided in Appendix B.

Allowable wind drift limit is set to  $h_{sx} / 400$  (elastic) for the 10-year wind. Composite action between the beams of the MWFRS and the concrete slab is considered for checking wind drift and when computing the fundamental period,  $T_1$ , for wind vibrations using an average  $I_{eff}$  as recommended in AISC 360 commentary for Chapter I. The same gravity load combination used for the seismic drift analysis is used in the wind drift analysis (see previous discussion under Earthquake Forces—§2.2.3.1).

Not all practitioners will use the 10-year wind to verify drift compliance (see ASCE 7 commentary for Appendix C); the 25-year or 50-year may be used, depending on project-specific requirements. The 10-year wind is considered appropriate for these structures, as the façade (curtain wall) is designed to accommodate large in-plane seismic movements, and period control (i.e., acceleration) is typically not a concern for building geometries in the range used for this investigation.

## 2.3 Structural Analysis and Mathematical Model

The archetype buildings are analyzed in ETABS, ver. 9.7.4 (CSI 2011a). A conventional *second-order* elastic analysis is used to determine the required strength of components, and member and story deformation demands (elastic and virtual inelastic). This type of analysis uses a constant reduced stiffness matrix based on an initial gravity (i.e.,  $P-\Delta$ ) load combination applied in a pre-analysis as follows:

- $P-\Delta$  load combination for strength analysis:  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$
- $P-\Delta$  load combination for drift and stability verification analysis:  $1.0 \times \text{Dead} + 0.25 \times \text{Floor Live}$

The analyses do not account for material nonlinearity or geometric imperfections (except for gravity-only load combinations—see AISC 360 Chapter C). Because the stiffness matrix remains constant for all loads, superposition of individual load effects in load combinations is applicable.

Each building is considered globally restrained horizontally, vertically, and rotationally at the seismic base (taken at grade level). The base columns of the LFRSs are embedded into the foundation wall. As such, column bases are modeled as rotationally restrained in the plane of the frames and rotationally unrestrained

out-of-plane. Non-SFRS gravity column bases are considered rotationally unrestrained in both orthogonal directions.

The mathematical models are based on centerline dimensions with rigid end offsets at the beam-to-column, brace-to-beam / column, and brace-to-beam joints with panel zones explicitly modeled based on column web and doubler plate (if required) geometry. The slabs are modeled as semi-rigid membrane diaphragms (no out-of-plane bending stiffness) with a 0.5 in-plane stiffness modifier to account for cracking at the design loads—see NIST GCR 11-917-10: *Seismic Design of Composite Steel Deck and Concrete-filled Diaphragms: A Guide for Practicing Engineers* (NIST 2011b).

In the moment frames, reduced beam sections (RBS) are explicitly modeled in all SMF beams by subdividing each member into seven segments; the RBS is modeled as two linearly-tapered sections. The typical fully restrained (FR) beam-to-column connection is illustrated in Figure 2-6, and the equivalent assembly model for linear analysis is shown in Figure 2-7.




Figure 2-6. Typical FR RBS Beam-to-Column Connection Assembly

In the concentrically braced frames, member ends of the SCBF diagonal braces are rotationally unrestrained out-of-plane and restrained in-plane (though design forces do not vary significantly if modeled as unrestrained in both planes). Partially rigid end zones are included to capture gusset plate rigidity; the *tangible* length of SCBF diagonal braces is taken equal to 90 percent of the distance between work points (W.P.),  $L_{wp}$ .

The adopted brace-to-beam / column connection in the SCBF allows the beam to rotate near the edge of the gusset plate as shown in Figure 2-8—see AISC 341 Figure C-F2.8. The assembly model for linear analysis is shown in Figure 2-9. A rotationally unrestrained connection (adjacent to the gusset plate) was selected

because ASCE 41 does not prescribe flexural acceptance criteria for beam-to-column connections where a brace is present. This approach also provides a seismic design and assessment that does not rely on the contribution of non-brace assemblies for stiffness and strength. All other beam-to-column connections are simple-type connections (i.e., rotationally unrestrained).




Figure 2-7. FR RBS Beam-To-Column Connection Subassembly Model for Linear Analysis

Diagonal braces were analyzed without gravity loads. Thus, two analyses were performed for each archetype building: (1) a gravity load-only model with braces removed and (2) a lateral force and gravity load model with braces in place. Load effects then were taken from the respective analysis for input into load combinations.

Non-LFRS framing that primarily supports gravity loads is included in the mathematical models to capture the “leaning column” effect. The gravity beams are modeled as composite beams with rotationally unrestrained member ends (i.e., shear tab connections). The gravity columns are modeled as continuous along the height of the building and designed for deformation compatibility. The increase in lateral stiffness along the two principal axes due to these columns is negligible. Other than the columns, no other forms of lateral stiffness attributed to non-SFRS framing (e.g., stairs) and nonstructural components are considered in the mathematical model.




Figure 2-8. Typical Brace-to-Beam / Column Connection Assembly




Figure 2-9. Brace-to-Beam / Column Connection Subassembly Model for Linear Analysis

## 2.4 SFRS Design

### 2.4.1 SMF Design

SMF designs are included here to provide the required information of the building for SCBF designs. For the SMF designs, seismic drift criteria prescribed in ASCE 7 §12.12 tended to control member sizes for both 4-story archetype buildings and the 8-story ELF-designed archetype building. The seismic stability criteria prescribed in ASCE 7 §12.8.7 tended to control member sizes for the 8-story RSA-designed archetype building and both 16-story archetype buildings (ELF design was more drift controlled than the RSA design). The strong-column / weak-beam (SCWB) criteria using an amplified seismic load (axial) and section compactness requirements provided additional constraint on column sizes where required.


The RBS beam-to-column connections were designed in accordance with AISC 358 with the flange cut out dimensions optimized to produce the lowest *probable* moment,  $M_{pr}$ . Because the bay length did not change, the same beam depth was used for a given floor for uniform connection constructability and plastic hinge sequencing optimization (i.e., yield rotation is theoretically equal). The panel zones are designed for demands based on the *probable* moment of the RBS projected to the column face using nominal material properties. AISC 360 §J10.6 (b) is applicable for panel zone design because the effect of panel zone deformations on frame stability is explicitly considered in the analysis. The flow chart in Figure 2-10 illustrates the analysis and design process for an SMF. Additional details on design and construction of special moment frames can be found in NIST GCR 09-917-3: *Seismic Design of Steel Special Moment Frames: A Guide for Practicing Engineers* (NIST 2009b).

To reflect industry practice and reduce fabrication costs, column sizes were increased from that required by analysis rather than adding doubler plates. AISC Design Guide 13 (AISC 1999) and Troup (1999) showed that increasing the column size by up to 100 plf to eliminate both continuity plates and doubler plates was often the more economical alternative. Some seismic specifications (e.g., AISC 341), however, either require or suggest the use of transverse stiffeners in all high seismic applications. For these cases, eliminating the need for doubler plates alone may still prove to be the economical choice (Lee et al. 2002). In this study, this increase typically occurred at interior frame columns and on average was 100 plf for the frame as a whole.

The Effective Length Method (see AISC 360 §C1) is used for design of the SMF columns, with the Story Buckling Method (see commentary for AISC 360 Appendix 7) used to compute the effective length,  $KL = K_2L$  (see footnote 8) for determining the nominal compression strength,  $P_n$ , of the column in the plane of the frame. In all but one SMF, at least one story had  $B_2$ , as defined in AISC 360 Appendix 8, greater than 1.1; all stories were less than 1.5 (see AISC 360 Appendix 7). Tabulated values for  $B_2$  are provided in Appendix B.  $KL = L$  was adopted for determining  $P_n$  of the column out-of-plane of the frame.

---

<sup>8</sup> AISC 360-05 (AISC 2005) used the term  $K_2$  to define the in-plane effective length factor. AISC 360-10 Appendix 7 uses  $K$  in lieu of  $K_2$ . However,  $K_2$  is still used in the commentary of Appendix 7. Therefore,  $K_2$  is also used here. Additional information can be found in *Steel Design Guide 28: Stability Design of Steel Buildings* (AISC 2013).



**Figure 2-10. Flow Chart of SMF Design Process**

Computation of in-plane effective length factors is *generally* considered to be not required for columns in regular moment frames in high seismicity areas (i.e., adopting  $KL = L$ ). Seismic story drift and stability requirements in ASCE 7 typically result in significant in-plane story strength and stiffness above that required by the analysis. However, the concept of story drift control without consideration of its effects on a moment frame is a nontechnical rationale for neglecting the effective length factors for in-plane seismic design of frame columns. Essentially, the effects of drift control reduce the error in calculating the beam-column strength for load combinations including lateral forces because of the following (taken from White and Hajjar 1997):

- The in-plane, strong-axis radius of gyration,  $r_x$ , is increased thus lowering  $KL / r_x$  in the design equation. Column strength varies little with large variations of  $KL / r_x$ .
- The columns are heavily restrained at each end by deep beams, and subjected to nearly double-curvature bending under sideway of the frame.
- The beam-column interaction check for the lateral force-resisting columns is dominated by the moment term.

Designers must also consider the vertical strength of a story<sup>9</sup> loaded only with gravity-type loads, as well as the correlation of the actual demand relative to this vertical strength (e.g.,  $P_{story} / P_{e,story}$  as defined in AISC 360 Appendix 8). This story strength would represent the minimum value of  $P_n$  (in the absence of moment) for construction of the  $P$ - $M$  interaction diagram for the in-plane strength of a frame column in the story. Fundamentally, the effective length factor for a column is a function of the frame deformation demands and the loading on the column. Consequently, a  $P$ - $M$  interaction diagram would need to be constructed for each category of load combination (e.g., vertical load, vertical plus horizontal loads) considering the influence of the ratio of vertical to horizontal loading demands as well as which loading is being incremented until incipient buckling. Theoretically,  $KL = L$  should be adopted when the physical behavior of the column at its ultimate strength aligns with the theoretical definition of the compression strength. Future studies should investigate designing the selected frames using the Direct Analysis Method prescribed in AISC 360 Chapter C.

In proportioning frame members for this study, section depths were selected to maintain a low in-plane relative beam-to-column stiffness ratio,  $G$ . AISC 360 commentary for Appendix 7 defines  $G$  for bending about the strong-axis as Equation (2-1)—see AISC 360 for definitions of the variables and subscripts.

$$G = \frac{\sum \tau_b \frac{EI_{x,c}}{L_c}}{\sum \gamma \frac{EI_{x,b}}{L_b}} \quad (2-1)$$

Other relationships can be used to show that  $G$  can be computed as function of the in-plane flexural section strength,  $Z_x \times F_y$ , independent of the in-plane flexural stiffness,  $E \times I_x$ . Equation (2-2) shows that the strong-axis plastic section modulus,  $Z_x$ , is a function of the strong-axis moment of inertia,  $I_x$ , and section depth,  $d$ . Equation (2-3) rewrites the SCWB equation in AISC 341 (see §E3.4a) for a wide-flange section.

$$Z_x = \frac{2I_x}{d} \quad (2-2)$$

$$\frac{M_{p,c}}{M_{p,b}} = \frac{\min \left[ 1.18 \left( 1 - \frac{P_{u,\Omega}}{P_y} \right), 1.0 \right] Z_{x,c} F_y}{Z_{x,b} F_y} \geq 1 \rightarrow \therefore Z_{x,b} \leq \min \left[ 1.18 \left( 1 - \frac{P_{u,\Omega}}{P_y} \right), 1.0 \right] Z_{x,c} \quad (2-3)$$

$$\therefore G = \frac{\tau_b}{\min \left[ 1.18 \left( 1 - \frac{P_{u,\Omega}}{P_y} \right), 1.0 \right]} \frac{d_c L_b}{d_b L_c} \quad (2-4)$$

---

<sup>9</sup> The vertical story strength,  $P_{e,story}$ , is a function of the *elastic* lateral stiffness of the story.


In the previous equations,  $P_{u,\Omega}$  is the axial load demand in the column including the system overstrength factor,  $\Omega_o$ , in ASCE 7 as required by AISC 341 §E3.4a. An additional rule of thumb is that  $d_c \geq d_b / 2$  and  $d_c \leq d_b$ . For example, an 18-inch deep column and 24-inch deep beam were selected for the SMF in the 8-story building. Conservatively assuming a 15 percent reduction in plastic flexural strength of the column leads to  $G = 1.9$  (see Equation (2-5)). A 27-inch deep column and 36-inch deep beam could also have been selected, but this would have been at the expense of architectural constraints and construction budget.

$$G = \frac{\tau_b}{1.18 \left( 1 - \frac{P_{u,\Omega}}{P_y} \right)} \frac{d_c L_b}{d_b L_c} = \frac{1.0}{0.85} \frac{d_c}{d_b} \frac{360}{168} = 2.52 \frac{18}{24} = 1.9 \quad (2-5)$$


This approach assists in selecting member depths while attempting to minimize relative elastic flexural stiffness variations between the beams and columns within a story, and between adjacent stories. As discussed previously, computing  $G$  is not required unless the size of the frame column is governed by strength requirements and one is using the Effective Length Method; tabulated values for  $K$  are provided in Appendix B.

The lateral force distributions and story shears for each archetype building are provided in Appendix B. Allowable drift compliance verification is provided in Appendix B. Similarly, verification for drift amplification from global p-delta ( $P-\Delta$ ) effects and ASCE 7 stability verification are also provided in Appendix B. Design calculations for select members and connections are provided to illustrate the design process in Appendix B.

The 4-, 8-, and 16-story SMF frame designs are shown in Figure 2-11 through Figure 2-13. Each figure shows both the RSA design (a) and the ELF design (b)—underlined member sizes indicate changes from the RSA design. These figures also provide the RBS dimensions and fundamental periods of the archetype building for various gravity loads (e.g., drift and strength design).




(a) RSA




(b) ELF

Figure 2-11. 4-Story SMF Schematic




(a) RSA

Figure 2-12. 8-Story SMF Schematic



(b) ELF

Figure 2-12. 8-Story SMF Schematic, Cont'd



Roof  
(ELEV = 228 ft.)

16<sup>th</sup> Floor  
(ELEV = 214 ft.)

15<sup>th</sup> Floor  
(ELEV = 200 ft.)

14<sup>th</sup> Floor  
(ELEV = 186 ft.)

13<sup>th</sup> Floor  
(ELEV = 172 ft.)

12<sup>th</sup> Floor  
(ELEV = 158 ft.)

11<sup>th</sup> Floor  
(ELEV = 144 ft.)

10<sup>th</sup> Floor  
(ELEV = 130 ft.)

9<sup>th</sup> Floor  
(ELEV = 116 ft.)

8<sup>th</sup> Floor  
(ELEV = 102 ft.)

7<sup>th</sup> Floor  
(ELEV = 88 ft.)

6<sup>th</sup> Floor  
(ELEV = 74 ft.)

5<sup>th</sup> Floor  
(ELEV = 60 ft.)

4<sup>th</sup> Floor  
(ELEV = 46 ft.)

3<sup>rd</sup> Floor  
(ELEV = 32 ft.)

2<sup>nd</sup> Floor  
(ELEV = 18 ft.)

**RBS Dimensions:**

W24x55  $a = 3.75"$ ,  $b = 16"$ ,  $c = 1.75"$   
W27x94  $a = 5.00"$ ,  $b = 18"$ ,  $c = 2.50"$   
W30x108  $a = 5.25"$ ,  $b = 20"$ ,  $c = 2.50"$   
W33x130  $a = 5.75"$ ,  $b = 22"$ ,  $c = 2.75"$


□ = Panel Zone  
- - = Column Splice

**Fundamental Periods**

$T_1 = 4.70$  sec (First-Order)  
 $T_1 = 5.01$  sec ( $1.0D + 0.25L_o$ )  
 $T_1 = 5.07$  sec ( $1.2D + 0.25L_o$ )

(a) RSA

**Figure 2-13. 16-Story SMF Schematic**



**RBS Dimensions:**  
W24x55  $a = 3.75"$ ,  $b = 16"$ ,  $c = 1.75"$   
W27x94  $a = 5.00"$ ,  $b = 18"$ ,  $c = 2.50"$   
W30x108  $a = 5.25"$ ,  $b = 20"$ ,  $c = 2.50"$   
W33x130  $a = 5.75"$ ,  $b = 22"$ ,  $c = 2.75"$

□ = Panel Zone  
- - = Column Splice

**Fundamental Periods**  
 $T_1 = 4.15$  sec (First-Order)  
 $T_1 = 4.36$  sec ( $1.0D + 0.25L_o$ )  
 $T_1 = 4.40$  sec ( $1.2D + 0.25L_o$ )

(b) ELF

Figure 2-13. 16-Story SMF Schematic, Cont'd

## 2.4.2 SCBF Design

For the SCBF designs, seismic strength requirements prescribed in ASCE 7 and seismic compactness requirements in AISC 341 controlled brace sizes for all archetype buildings. Section compactness and capacity design requirements in AISC 341 §F2.3 (i) and (ii)—exception 2(a) is not considered here—governed column and beam sizes. The beams in the 4-story frames are laterally braced per AISC 341 and designed for the unbalanced load created by a buckled brace. For the 8- and 16-story frames, except at the second floor, beam sizes were maintained at each floor based on the largest required strength (usually at the third and fourth floors). The beams on the second floor had an atypical change in required strength because of the variation in adjacent story heights. The flowchart in Figure 2-14 illustrates the analysis and design process for an SCBF. Additional details on design and construction of special concentrically braced frames can be found in NIST GCR 13-917-24: *Seismic Design of Steel Special Concentrically Braced Frame Systems: A Guide for Practicing Engineers* (NIST 2013).





Figure 2-14. Flow Chart of SCBF Design Process

Wind drift criteria began to influence the 16-story SCBF when two isolated 20-foot two-story braced bays were used (as done in the 4- and 8-story archetype buildings). Therefore, a double 30-foot bay configuration was adopted to minimize nonseismic force contributions to member selections, as well as to allow seismic assessment of longer (potentially slender) braces.


The Effective Length Method (see AISC 360 §C1) is used for design of the SCBF braces, beams, and columns. The effective length factor,  $K$ , was conservatively taken as unity for determining the nominal compression strength,  $P_n$ , of the SCBF members, although a lower value could be justified by analysis. Though the gusset plate connections are not fully designed and detailed in this study, a lower value of  $K$  could have been adopted where the rotational stiffness of the connection can influence the assumed boundary conditions of the adjacent braces (out-of-plane buckling controlled design). Hollow structural sections (HSS) are used as the diagonal braces in all archetype buildings while keeping face dimensions within the adjacent column flange widths. The *tangible* length of SCBF braces is taken equal to 90 percent of the distance between work points,  $L_{wp}$ . Diagonal braces are designed *not* to carry gravity loads—see §2.3.

The lateral force distributions and story shears for each archetype building are provided in Appendix B. Allowable drift compliance verification is provided in Appendix B. Similarly, verification for drift amplification from global p-delta ( $P$ - $\Delta$ ) effects and ASCE 7 stability verification are also provided in Appendix B. Design calculations for select members and connections are provided to illustrate the design process in Appendix B.

The 4-, 8-, and 16-story SCBF frame designs are shown in Figure 2-15 through Figure 2-17, respectively. Each figure shows both the RSA design (a) and the ELF design (b)—underlined member sizes indicate changes from the RSA design. These figures also provide the fundamental periods of the archetype building for various gravity loads (e.g., drift and strength design).




(a) RSA




(b) ELF

Figure 2-15. 4-Story SCBF Schematic




(a) RSA

Figure 2-16. 8-Story SCBF Schematic



(b) ELF

Figure 2-16. 16-Story SCBF Schematic, Cont'd



(a) RSA

Figure 2-17. 16-Story SCBF Schematic



## Chapter 3      Seismic Assessment

This chapter presents the results of the seismic assessment of the special concentrically braced frames in accordance with ASCE 41. Section 3.1 provides general discussions on the global analysis requirements for assessment. Analysis requirements specific to concentrically braced frames and assessment results of *primary* components of the frames are provided in Section 3.2.

### 3.1 Assessment Overview

A seismic performance assessment of the special concentrically braced frames is conducted using both linear and nonlinear analysis procedures prescribed in ASCE 41 §2.4:

- Linear Static Procedure [ASCE 41 §3.3.1]
- Linear Dynamic Procedure (Response Spectrum) [ASCE 41 §3.3.2]<sup>10</sup>
- Nonlinear Static Procedure [ASCE 41 §3.3.3]<sup>11</sup>
- Nonlinear Dynamic Procedure [ASCE 41 §3.3.4]

Seismic assessment analyses follow the guidelines outlined in ASCE 41 Chapters 1 through 3, and, where applicable, ASCE 41 Chapter 5. Foundations, including soil-structure interaction, and geological site hazards (ASCE 41 Chapter 4) are not considered in this study. Modeling and assessment requirements for steel structural systems follow the provisions in ASCE 41 Chapter 5. Any deviations from these ASCE 41 guidelines are explained where applicable.

The seismic performance target (i.e., ‘rehabilitation objective’) for this study is selected as the Basic Safety Objective (BSO) in ASCE 41 §1.4.1. This selection allows the correlation between the seismic performance objective intended by ASCE 41 and the intended design objective of ASCE 7 for an ordinary building<sup>12</sup> to be evaluated. The BSO associated goals for Structural Performance Levels (SPLs) found in ASCE 41 §1.5.1 and Earthquake Hazard Levels (EHLs) found in ASCE 41 §1.6 are given in Table 3-1. Nonstructural Performance Levels (NPLs) found in ASCE 41 §1.5.2 are not considered in this study. The target Building Performance Levels (BPLs) found in ASCE 41 §1.5.3 are given in Table 3-1.

The only explicit connection between the target *structural* performance objectives (i.e., SPL) of the BSO in ASCE 41 and the intended *structural* design performance objective of ASCE 7 is ‘Collapse Prevention’ given an MCE event, assuming that the BSE-2 EHL is equivalent to the MCE defined by ASCE 7—see Table 1-1 and Table 3-1. It is presumed by ASCE 7 that an appropriately designed structure using a seismic hazard of  $\frac{2}{3}\times$ MCE will achieve this *structural* design performance objective. ASCE 7 does not explicitly

---

<sup>10</sup> The user can alternatively perform a linear response history analysis. This was not done in this study, although it would bypass the limitations of using modal response spectrum analysis.

<sup>11</sup> Simplified Nonlinear Static Procedure (NSP) is not considered.

<sup>12</sup> Structures assigned to Risk Category II or lower.

identify a target *structural* design performance objective for ‘Life Safety’ at  $\frac{2}{3}\times$ MCE. Rather, ASCE 7 contains implicit life safety measures to protect against loss of life from nonstructural damage at the design-level event,  $\frac{2}{3}\times$ MCE.

**Table 3-1. Seismic Performance Targets (from ASCE 41-06)**

Earthquake Hazard Level	Earthquake Intensity	Structural Performance Level	Nonstructural Performance Level	Building Performance Level
BSE-1 – §1.6.1.2	$\frac{2}{3}\times$ BSE-2	Life Safety (S-3)	Not Considered (N-E)	Life Safety (3-E)
BSE-2 – §1.6.1.1	Maximum Considered Earthquake (MCE)	Collapse Prevention (S-5)	Not Considered (N-E)	Collapse Prevention (5-E)

Prior to ASCE 7-10, the MCE was defined as a uniform seismic hazard associated with a two percent probability of being exceeded in 50 years, except near known faults where deterministic-based hazards controlled. ASCE 7-10 adopted a risk-targeted design philosophy that shifts from a uniform *hazard design basis* to a uniform *risk design basis*, and defines the MCE ground motion intensity (denoted as  $MCE_R$ ) as ground motions having a one percent probability of causing total or partial structural collapse in 50 years. This risk has a conditional probability (‘anticipated reliability’) of ten percent probability of total or partial structural collapse conditioned on the occurrence of an MCE event—see ASCE 7 Table C.1.3.1b. Several reference documents are available for more information about this implementation (FEMA 2009b, commentary of ASCE 7-10 (3<sup>rd</sup> printing), and NIST 2012). Therefore, the approved MCE in ASCE 41-06 §1.6.1.1 (see BSE-2 in Table 3-1) should be taken as the  $MCE_R$  in ASCE 7-10 to maintain equivalency between the standards. ASCE 41-13 §2.2.4 prescribes using the  $MCE_R$  to define the BSE-2 EHL for the new building equivalency track. The seismic performance targets for this study are taken from ASCE 41-13 and are given in Table 3-2.

**Table 3-2. Seismic Performance Targets (from ASCE 41-13)**

Earthquake Hazard Level	Earthquake Intensity	Structural Performance Level	Nonstructural Performance Level	Building Performance Level
BSE-1N <sup>1</sup> – §2.4.1.2	$\frac{2}{3}\times$ BSE-2N	Life Safety (S-3)	Not Considered (N-E)	Life Safety (3-E)
BSE-2N <sup>1</sup> – §2.4.1.1	Maximum Considered Earthquake ( $MCE_R$ )	Collapse Prevention (S-5)	Not Considered (N-E)	Collapse Prevention (5-E)

<sup>1</sup> ASCE 41-13 expanded the term ‘BSE’ to include ‘N’ or ‘E’ depending on the chosen assessment track. For this project, the ‘N’ is dropped to follow the terminology used in ASCE 41-06.

This study does not evaluate assessment results for earthquake hazard levels with return periods shorter than identified above or building performance levels below Life Safety. Future research efforts may evaluate incorporating other performance levels for design in ASCE 7—see NIST GCR 12-917-20: *Tentative Framework for Development of Advanced Seismic Design Criteria for New Buildings* (NIST 2012).

### 3.1.1 Seismic Hazard

The seismic hazard is defined in ASCE 41 §1.6. The spectral response parameters for the BSE-2 ( $\equiv$  BSE-2N—see above) and BSE-1 ( $\equiv$  BSE-1N—see above) EHLs are given in Table 3-3. The parameters summarize the seismic hazard<sup>13</sup> for Site Class D, Stiff Soil, in ASCE 41 §1.6.1.4.1.

**Table 3-3. Spectral Response Parameters**


EHL	$S_S$ (g)	$S_I$ (g)	$F_a$ <sup>3</sup>	$F_v$ <sup>3</sup>	$S_{XS}$ (g)	$S_{XI}$ (g)	$T_s$ (sec)	$T_0$ (sec)
BSE-2	1.5	0.60 <sup>1</sup>	1.0	1.50	1.50	0.90	0.60	0.12
BSE-1 <sup>2</sup>	1.5	0.60 <sup>1</sup>	1.0	1.50	1.00	0.60	0.60	0.12

<sup>1</sup>  $S_I$  is actually just under 0.60 (i.e., 0.599)

<sup>2</sup>  $S_S$  and  $S_I$  do not include 2/3 reduction prior to site class modification

<sup>3</sup> See ASCE 41 Table 1-4 and Table 1-5

Figure 3-1 illustrates the generalized response spectrum for BSE-1 and BSE-2.



**Figure 3-1. Acceleration Response Spectra**

### 3.1.2 General Analysis Requirements

This section discusses the implementation of the general analysis requirements prescribed in ASCE 41 §3.2 in this study.

ASCE 41 §3.2.2—Mathematical Modeling: The archetype buildings are modeled in three-dimensions. Increased forces and displacements because of torsional demands are inherently addressed in the three-

<sup>13</sup> The seismic hazard in ASCE 41-13 is the MCE<sub>R</sub>, ground motion based on a risk-targeted design philosophy in which an appropriately designed structure will have a one percent probability of collapse (i.e., risk) in 50-years (except in areas controlled by the deterministic cap on ground motions—see ASCE 7 commentary for Chapter 11).

dimensional analysis. Because of building symmetry, the inherent torsional moment at each floor is *theoretically* zero. Accidental torsional moment (i.e., five percent mass offset) at each floor is not considered in the assessment analyses because the displacement modifier,  $\eta$ , associated with the applied loads including accidental torsion is less than 1.1 at every floor for all buildings (see Table 3-4 and Table 3-5). The values in these tables for determining torsional irregularity are based on floor displacements relative to the base and not story drifts as used in ASCE 7<sup>14</sup>.

All members and connections of the seismic force-resisting system (SFRS) are classified as *primary* components in accordance with ASCE 41 §2.4.4.2 for both linear and nonlinear assessment procedures. Gravity framing (non-SFRS members and shear tab connections) is assumed in this study to provide negligible analytical lateral stiffness and strength—see ASCE 41 §3.2.2.3. Therefore, components of the non-SFRS framing are classified as *secondary* components for both linear and nonlinear assessment procedures. Similar to the assumptions adopted for design, specific component stiffnesses (e.g., partially restrained shear tab connections and stairs) are not modeled explicitly in the mathematical model. This is done to minimize the influence of secondary components on the demands imposed on primary components. This will allow assessment results between linear and nonlinear analysis to be compared. Performance assessment of these secondary members is outside the scope of this study—though would need to be checked in a *real* retrofit design. In addition, foundation or soil flexibility is not included in the analysis. Models for anticipated component inelastic actions in nonlinear assessment procedures include both strength and stiffness degradation—discussed subsequently in §3.2.

ASCE 41 §3.2.3—Configuration: Building irregularities are discussed in ASCE 41 §3.1.3.1. Building irregularities defined in ASCE 41 are used only to determine whether the linear procedures are applicable.

ASCE 41 §3.2.4—Diaphragms: Floor diaphragms are modeled for analysis as semi-rigid membranes (i.e., *stiff* per ASCE 41). The same assumptions adopted in design are maintained for assessment.

ASCE 41 §3.2.5—P- $\Delta$  Effects: Global  $P$ - $\Delta$  effects are considered in the linear and nonlinear analyses, for both static and dynamic. Local  $P$ - $\delta$  effects are not addressed either explicitly or implicitly in the analyses.

ASCE 41 §3.2.6—Soil-Structure Interaction: Soil-Structure Interaction is not considered in the seismic assessment of the archetype buildings.

ASCE 41 §3.2.7—Multidirectional Seismic Effects: The *principal* axes of the archetype buildings align directly with the E-W and N-W directions (performance in the N-S direction is presented in this report). Seismic effects are determined by applying the seismic forces independently in each of the two orthogonal directions. Per ASCE 41 §3.2.7.1, concurrent seismic effects are addressed in the assessment by combining the effects along each principal axes.

---

<sup>14</sup> Amplification of the accidental torsion, if required, is consistent between ASCE 41 and ASCE 7.

ASCE 41 §3.2.7—Vertical Seismic Effects: Vertical seismic effects are not considered for seismic assessment of the archetype buildings. Masses are input for horizontal accelerations only for dynamic analysis.

ASCE 41 §3.2.8—Gravity Loads: Gravity loads for the linear assessment procedures are applied using the following two load combinations (LC). Roof live loads are considered not to be present for seismic analysis. There is no snow load acting on the buildings.

- LC1 = 1.1×(Dead+0.25×Unreduced Floor Live)
- LC2 = 0.9×Dead

A *P-Δ* load combination based on LC1 above is used for the linear assessment analyses; consequently, this is conservative for analysis using LC2.

Both gravity load combinations above are used for the nonlinear static procedure. The average of the two combinations (LC1 and LC2) is applied in the nonlinear dynamic procedure.

- LC3 = 1.0×Dead+0.25×Unreduced Floor Live

A *P-Δ* load combination based on LC3 above is used for the nonlinear assessment analyses.

ASCE 41 §3.2.9—Verification of Design Assumptions: The following design objectives are verified with the nonlinear dynamic procedure.

- SCBF—in-plane and out-of-plane stability of columns (AISC 360)
- SCBF—adequate flexural strength in the beams and columns (AISC 341)

ASCE 41 §3.2.10—Overturning: Overturning is not considered for design or seismic assessment of the archetype buildings.

**Table 3-4. Displacement Multiplier—E-W (SMF)**

Floor	$\eta = \tilde{\delta}_{max} / \tilde{\delta}_{avg}$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof	-	-	-	-	1.010	1.008
16	-	-	-	-	1.009	1.007
15	-	-	-	-	1.009	1.007
14	-	-	-	-	1.009	1.007
13	-	-	-	-	1.009	1.007
12	-	-	-	-	1.009	1.007
11	-	-	-	-	1.008	1.007
10	-	-	-	-	1.008	1.007
9 (Roof MC8)	-	-	1.010	1.007	1.008	1.007
8	-	-	1.010	1.007	1.008	1.007
7	-	-	1.009	1.006	1.008	1.007
6	-	-	1.009	1.006	1.008	1.007
5 (Roof MC4)	1.006	1.006	1.008	1.005	1.008	1.007
4	1.006	1.006	1.008	1.005	1.008	1.007
3	1.005	1.005	1.007	1.005	1.008	1.007
2	1.005	1.005	1.007	1.005	1.008	1.007

Values shown to four significant figures are for comparison purposes only.

**Table 3-5. Displacement Multiplier—N-S (SCBF)**

Floor	$\eta = \delta_{max} / \delta_{avg}$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof	-	-	-	-	1.088	1.090
16	-	-	-	-	1.088	1.090
15	-	-	-	-	1.088	1.090
14	-	-	-	-	1.088	1.090
13	-	-	-	-	1.089	1.090
12	-	-	-	-	1.089	1.090
11	-	-	-	-	1.089	1.090
10	-	-	-	-	1.089	1.091
9 (Roof MC8)	-	-	1.087	1.091	1.089	1.091
8	-	-	1.087	1.091	1.089	1.091
7	-	-	1.088	1.091	1.089	1.091
6	-	-	1.088	1.092	1.090	1.091
5 (Roof MC4)	1.093	1.094	1.089	1.092	1.090	1.091
4	1.094	1.095	1.090	1.093	1.090	1.091
3	1.094	1.095	1.090	1.093	1.090	1.091
2	1.094	1.095	1.091	1.093	1.089	1.090

Values shown to four significant figures are for comparison purposes only.

### 3.1.3 Analysis Procedures

This section discusses the implementation of the specific analysis procedures prescribed in ASCE 41 §3.3 in this study.

#### 3.1.3.1 Linear Analysis Procedures

The archetype buildings are modeled and analyzed in ETABS 9.7.4 (CSI 2011a) for the linear analyses. The assumptions used in the mathematical model and analysis techniques are the same as those adopted for design (see Chapter 2). Modeling and analysis considerations for the linear procedures are outlined in ASCE 41 §3.2.2 with supplemental information provided in ASCE 41 §3.3.2.2 for the Linear Dynamic Procedure (LDP). Gravity loads and load combinations assumed present during the earthquake are computed from ASCE 41 §3.2.8 as discussed previously. The effective horizontal seismic weights,  $w$ , for analysis are computed in accordance with ASCE 41 §3.3.1, and are the same as those used for design (see Chapter 2). Global  $P$ - $\Delta$  effects (e.g.,  $B_2$  in AISC 360 Appendix 8) are addressed in the analysis by using a simplified algorithm—see ETABS User Manual. ETABS does not explicitly include local  $P$ - $\delta$  effects (e.g.,  $B_1$  in AISC 360, Appendix 8). System specific modeling assumptions and analysis techniques are described in their respective sections.

ASCE 41, §2.4.1.1 prescribes restrictions on the use of the linear procedures. First, a *retrofitted*<sup>15</sup> SFRS must not contain certain types of structural irregularities where the earthquake demands on the primary components of the SFRS fail to comply with the demand capacity ratio (DCR) limitations.

<sup>15</sup> This term is now used in lieu of ‘rehabilitation’.

$$DCR = \frac{Q_{UD}}{Q_{CE}} \leq 2.0 \quad (3-1)$$

where  $Q_{UD}$  is the demand on a component due to gravity and earthquake loads and  $Q_{CE}$  is the expected strength of the component. The archetype buildings do not contain any configuration-based in-plane or out-of-plane irregularities. Further, a linear analysis procedure must be performed to determine whether a building contains a weak story or torsional strength irregularity. Because of plan symmetry and regularity of the archetype buildings, there are no torsional irregularities. The required weak story irregularity verifications are discussed subsequently in the linear static procedure for each specific system type.

### 3.1.3.1.1 Linear Static Procedure

The Linear Static Procedure (LSP) is outlined in ASCE 41 §3.3.1. The provisions of the LSP closely resemble those of the ELF procedure in ASCE 7; as such, no additional analysis details are presented here. However, one place where ASCE 7 and ASCE 41 differ is in the determination of the fundamental period,  $T$ , in the direction being analyzed. ASCE 41 does not place an upper-bound limit on the period used for assessment as ASCE 7 does for strength design. In this study, the fundamental periods are determined by eigenvalue analysis per ASCE 41 §3.3.1.2.1.

Further restrictions on the use of the LSP are prescribed in ASCE 41 §2.4.1.2. The LSP cannot be used if any of the following occur:

- The fundamental period of the building,  $T$ , is greater than  $3.5 \times T_s$  ( $= 3.5 \times 0.6 = 2.1$  seconds in this study). This trigger is similar to that used in ASCE 7; however, like ASCE 7, which computation method for  $T$  to be used in this evaluation is not clear. If the analytical method (ASCE 41 §3.3.1.2.1) is used, only the E-W component of the ELF-designed MC4 and N-S components of all the buildings satisfy this requirement—see Table 3-6 (directional components that fail this criteria are shaded). If the empirical method (ASCE 41 §3.2.1.2.2) is used, all building components satisfy this constraint except the E-W component of MC16. In this study, this analysis constraint is disregarded to allow an assessment comparison between methods—see Table 3-7 (directional components that fail this criteria are shaded).
- The building has a ratio of the horizontal dimension at any story to the corresponding dimension in an adjacent story that exceeds 1.4. In this study, this constraint is satisfied because the building plan does not change at any story.
- The building has a torsional stiffness irregularity. This limitation is satisfied as discussed previously under accidental torsion as well as in Chapter 2. In this study, this check is based on the individual story drift rather than the floor displacement relative to the base.
- The building has a vertical stiffness irregularity. In this study, this limitation is automatically satisfied by using ASCE 7 §12.3.2.2 Exception 1 for the design of the archetype buildings.
- The building has a non-orthogonal SFRS. In this study, this limitation is not applicable to the archetype buildings.

Regardless of the restrictions on using the LSP, results from applying the LSP to the archetype buildings are included for the purpose of seismic performance comparison between the various assessment methods in this study.

**Table 3-6. Analytical Fundamental Periods (seconds)**

Direction	SFRS	MC4		MC8		MC16	
		ELF	RSA	ELF	RSA	ELF	RSA
E-W	SMF	1.83	2.23	2.93	3.84	4.39	5.05
N-S	SCBF	0.67	0.72	1.45	1.51	2.09	2.14

**Table 3-7. Empirical Fundamental Periods (seconds)**

Direction	SFRS	MC4		MC8		MC16	
		ELF	RSA	ELF	RSA	ELF	RSA
E-W	SMF	0.93	0.93	1.57	1.57	2.69	2.69
N-S	SCBF	0.43	0.43	0.71	0.71	1.17	1.17

### 3.1.3.1.2 Linear Dynamic Procedure

The Linear Dynamic Procedure (LDP) is outlined in ASCE 41 §3.3.2. The LDP requires the use of either response spectrum analysis (RSA) or response history analysis (RHA)—only the RSA is presented in this report. Though there are significant benefits of using the RHA (e.g., maintaining sign convention on response), the RSA was selected to align with the design methodology. The provisions of the LDP closely resemble those of the RSA procedure in ASCE 7; as such, no additional analysis details are presented here, except that no base shear scaling is required by ASCE 41. Damping for analysis is taken as five percent of critical for all modes for dynamic analysis to match the response spectrum (see ASCE 41 §1.6.1.5.3). A sufficient number of modes is used in the analysis to capture at least 90 percent of the mass participation in each of the two horizontal principal directions. Masses were not modeled in the analysis to address vertical accelerations. Furthermore, the square root of the sum of the squares (SRSS) rule is used to combine the modal responses so as to obtain the maximum forces and deformations.



### 3.1.3.2.1 Nonlinear Static Procedure

The Nonlinear Static Procedure (NSP) is outlined in ASCE 41 §3.3.3. ASCE 41 places limitations on the use of the NSP in ASCE 41 §2.4.2. First, if higher modes are significant, the NSP is permitted with supplemental verifications required using the LDP. Higher mode effects are considered significant when the story shear computed by analysis with at least 90 percent horizontal mass participation is at least 1.3 times greater than that computed considering only response in the fundamental mode. This condition is generally triggered in multistory buildings with fundamental periods greater than 1.0 second in the direction being considered (see Table 3-8 and Table 3-9—story shear ratios that fail this criteria are shaded).

Second, if  $R > R_{max}$  (as defined in ASCE 41 §3.3.3), dynamic instability is a potential failure mode and the NSP is not permitted. Information regarding this ductility criterion as applied to an idealized single-degree-of-freedom (SDOF) system is provided in FEMA 440: *Improvements of Nonlinear Static Seismic Analysis Procedures* (FEMA 2005). However, this verification is computationally cumbersome because a nonlinear static analysis has to be conducted to determine both  $R$  and  $R_{max}$ , prior to knowing if the NSP is permitted. This verification is illustrated subsequently in the NSP assessment results. The NSP procedure is graphically illustrated in the flowchart of Figure 3-3.




Figure 3-3. NSP Process

**Table 3-8. Story Shear Ratio - ELF**

Story	$V_{story} / V_{story,1st mode}$					
	MC4 E-W	MC8 E-W	MC16 E-W	MC4 N-S	MC8 N-S	MC16 N-S
Roof	-	-	2.96	-	-	2.07
16	-	-	2.03	-	-	1.83
15	-	-	1.61	-	-	1.61
14	-	-	1.41	-	-	1.43
13	-	-	1.29	-	-	1.28
12	-	-	1.20	-	-	1.17
11	-	-	1.14	-	-	1.09
10	-	-	1.09	-	-	1.05
9 (Roof)	-	1.98	1.07	-	1.57	1.04
8	-	1.41	1.07	-	1.31	1.05
7	-	1.19	1.06	-	1.13	1.07
6	-	1.10	1.07	-	1.03	1.12
5 (Roof)	1.45	1.05	1.08	1.07	1.02	1.17
4	1.10	1.03	1.11	1.01	1.06	1.22
3	1.01	1.05	1.15	1.00	1.13	1.26
2	1.06	1.10	1.19	1.02	1.20	1.29

**Table 3-9. Story Shear Ratio – RSA**

Story	$V_{story} / V_{story,1st mode}$					
	MC4 E-W	MC8 E-W	MC16 E-W	MC4 N-S	MC8 N-S	MC16 N-S
Roof	-	-	3.10	-	-	2.11
16	-	-	2.11	-	-	1.86
15	-	-	1.65	-	-	1.64
14	-	-	1.42	-	-	1.45
13	-	-	1.30	-	-	1.29
12	-	-	1.22	-	-	1.18
11	-	-	1.15	-	-	1.10
10	-	-	1.11	-	-	1.05
9 (Roof)	-	2.25	1.09	-	1.59	1.04
8	-	1.50	1.09	-	1.33	1.05
7	-	1.22	1.09	-	1.14	1.08
6	-	1.12	1.09	-	1.03	1.13
5 (Roof)	1.58	1.07	1.11	1.08	1.02	1.18
4	1.14	1.05	1.15	1.01	1.08	1.24
3	1.01	1.08	1.21	1.00	1.17	1.28
2	1.08	1.16	1.26	1.02	1.25	1.31

The mathematical model requirements for use with the NSP are outlined in ASCE 41 §3.2.2 and ASCE 41 §3.3.3.2. *Primary* components of the SFRS expected to experience inelastic deformations are modeled using full backbone curves that include strength degradation and residual strength (see ASCE 41 §3.2.2.3 and ASCE 41 §3.3.3.2). ASCE 41 §5.4.2.2.2 allows the *generalized* modeling parameters provided in ASCE 41 to model the full backbone curves of steel components for the NSP as an alternative to experimental calibration. In this study, all nonlinear components are modeled with the anchor points (A to E) bounding the full backbone curve as shown in Figure 3-2 and quantified in ASCE 41 Tables 5-6 and 5-7. Component strength at the ultimate deformation, point E on the backbone curve, retains residual strength

and does not experience complete strength loss. SFRS-specific modeling approaches are discussed in their respective sections.

For the nonlinear static analysis algorithm in PERFORM-3D, the following apply:

- The lateral force distribution is based on a non-adaptive first-mode shape (first-order elastic) and mass distribution.
- Damping is set to zero percent for all modes with no supplemental Rayleigh damping. All elements are assigned a beta- $K$  damping stiffness reduction factor of unity (no reduction).
- Strength degradation is included in the analysis.
- Global  $P$ - $\Delta$  are directly included in the analysis. Local  $P$ - $\delta$  effects are not addressed in the analysis. Geometric nonlinearity is assigned to all elements.
- Number of Steps is taken as 100 and Maximum Number of Events is taken as 1,000.
- Roof displacement at the center of mass relative to the base is used as the target displacement. The reference drift is therefore taken as the roof drift; the maximum allowable drift is taken as 10 percent. All story drifts are included in the list of Controlled Drifts.
- See PERFORM-3D *User Guide* for additional information.

#### 3.1.3.2.2 Nonlinear Dynamic Procedure

The Nonlinear Dynamic Procedure (NDP) is outlined in ASCE 41 §3.3.4. The NDP is intended to be the most rigorous of all the assessment procedures prescribed, with no limitations placed on types of buildings allowed for the assessment because of the intent of capturing the *true* behavior of the building subjected to strong ground motions.

The mathematical model requirements for use with the NDP are outlined in ASCE 41 §3.2.2 and ASCE 41 §3.3.4.2, except that the point-in-time gravity load present during strong ground motion is taken as  $(D + SD) + 0.25 \times L_{o, floor}$ , a slight but common alternative to ASCE 41 §3.2.8 (see ASCE 7 §16.2.3). Primary components of the SFRS expected to experience inelastic deformations are modeled using full backbone curves that include strength and stiffness degradation and residual strength (see ASCE 41 §3.2.2.3 and ASCE 41 §3.3.4.2).

For the NSP, ASCE 41 §5.4.2.2.2 allows using the *generalized* modeling parameters provided in Tables 5-6 and 5-7 to model the full backbone curves of steel components as an alternative to experimental calibration. However, for the NDP, ASCE 41 §5.4.2.2.3 requires all component hysteretic behavior be based on experimental data unless permitted by the authority have jurisdiction. The benefit of calibrating component models with experimental results is that the force-deformation relationship will more accurately reflect strength and stiffness degradation, both cyclic and in-cycle—see NIST GCR 10-917-5: *Nonlinear Structural Analysis for Seismic Design: A Guide for Practicing Engineers* (NIST 2010a) and FEMA P-440A: *Effects of Strength and Stiffness Degradation on Seismic Response* (FEMA 2009c). In this study, all nonlinear components are modeled with the anchor points (A to E) bounding the full backbone curve as shown in Figure 3-2 and quantified in ASCE 41 Tables 5-6 and 5-7. All nonlinear components are calibrated based on experimental results to determine cyclic and in-cycle stiffness degradation only; post-yield strength increases and strength degradation calibrations from experimental results were not included. Component strength at the ultimate deformation, point E on the backbone curve, retains the residual strength and does not experience complete strength loss. SFRS-specific modeling approaches are discussed in their

respective sections. Therefore, the same PERFORM-3D model used in the NSP is also used in the NDP; analytical results from the two procedures are thus consistent and directly comparable. Future ASCE 41 revisions should unify modeling practices for the NSP and NDP, as well as provide supporting data to the authority having jurisdiction. Future research should examine the response of these systems with hysteretic models calibrated completely to test results, including performing FEMA P695 analyses.

The nonlinear dynamic analysis algorithm in PERFORM-3D used the following parameters:

- Damping is taken as three percent of critical for all modes (elastic) and 0.3 percent of critical is added as Rayleigh damping (elastic stiffness component only, beta- $K$ ) for dynamic analysis. Damping computation in PERFORM-3D is not based on the tangent stiffness matrix. All elements are assigned a beta- $K$  damping stiffness reduction factor of unity (no reduction).
- Strength and stiffness degradation are included in the analysis.
- Global  $P$ - $\Delta$  are directly included in the analysis. Local  $P$ - $\delta$  effects are not addressed in the analysis. Geometric nonlinearity is assigned to all elements.
- Maximum Number of Events for each time step is taken as 200.
- Time steps for analysis are taken as the time step of the input motion, ranging from 0.005 to 0.02 seconds—see FEMA P695 Appendix A.
- See PERFORM-3D *User Guide* for additional information.

A critical aspect of the NDP is the selection and scaling of input ground motions (free-field motions) which is described in ASCE 41 §1.6.2.2. The methodology adopted in this study is discussed in Appendix A.

In addition to the analysis routine terminating when a solution fails to converge, the routine was also set to terminate when an arbitrarily selected roof drift ratio of twenty percent<sup>16</sup> is achieved (story drift ratios can be higher). While both of these methods are used to indicate and rationalize total or partial collapse of a system, the indicator of collapse used in this study is the component demands measured against the nonlinear modeling parameters and acceptance criteria. These component limits will typically be reached prior to an analysis routine failing to converge or an excessive roof drift is reached.

### 3.1.4 Acceptance Criteria

This section discusses the implementation of the acceptance criteria in ASCE 41 §3.4. Component actions are classified as *force-controlled* or *deformation-controlled* depending on the post-elastic behavior of the component (see ASCE 41 Table C2-1). Generally speaking, *deformation-controlled* actions are assigned to component actions capable of a ductile response (e.g., moment in a plastic hinge in a compact beam) and *force-controlled* actions are assigned to component actions with limited ductility (e.g., moment in a plastic hinge in a column with high axial load). Additionally, a knowledge factor,  $\kappa$ , is applied to account for uncertainties in the framing system and materials. Since the archetype buildings are new construction with quality control measures,  $\kappa$  is taken as unity in this study to represent *new component capacities or actions* as discussed in ASCE 41 §2.2.2 and ASCE 41 Tables 2-1, 2-2, and 2-3.

---

<sup>16</sup> This value does not change the qualitative performance result of a component; however, it can influence the mean value of a performance response for a set of records. For example, mean values would be slightly larger than if ten percent was selected.

### 3.1.4.1 Linear Procedures

Acceptance criteria of components for linear assessment procedures are provided as  $m$ -factors. The  $m$ -factor is intended to account for the ductility associated with a specific action and depends on the SPL and component type. ASCE 41 Table 5-5 provides the  $m$ -factors for steel components for linear assessment procedures. Adjustments to the  $m$ -factors for member or connection characteristics are detailed in ASCE 41 Chapter 5. In this study, actions in force-controlled components are assigned  $m = 1.0$  for simplicity and computational consistency in developed assessment spreadsheets. It should be noted that ASCE 41 does not assign an  $m$ -factor to force-controlled components.

#### 3.1.4.1.1 Calculating Component Assessment Results

Component forces and deformations obtained by the LSP or LDP are referred to as design actions,  $Q_U$  (e.g., flexure in a component).

Component design actions classified as *deformation-controlled*,  $Q_{UD}$ , are computed by

$$Q_{UD} = Q_G \pm Q_E \quad (\text{ASCE 41 §3.4.2.1.1}) \quad (3-2)$$

Component design actions classified as *force-controlled*,  $Q_{UF}$ , are computed by

$$Q_{UF} = Q_G + \frac{Q_E}{C_1 C_2 J} \quad (\text{ASCE 41 §3.4.2.1.2}) \quad (3-3)$$

where  $Q_G$  is the action due to gravity loads and  $Q_E$  is the action due to earthquake effects. Elastic force-controlled demands from earthquake effects are divided by  $C_1 C_2$  to remove the demand amplification for short period structures from non-ductile components (see ASCE 41 §3.3.1). Similarly, the demand is divided by  $J$ , which is the force-delivery reduction factor and is taken as the minimum demand capacity ration (DCR) of the components in the load path delivering force to the component. Alternatively,  $J$  can be taken as 2.0 when the system is located in a region of a high level of seismicity, independent of EHL. However, holding  $J$  constant for multiple performance levels (disregarding the change in intensity) is not consistent with a capacity design approach, resulting in potentially overly conservative estimates of component actions in force-controlled elements at the higher EHL, or vice versa.

ASCE 41 §3.4.2.2 requires that deformation-controlled and force-controlled actions in primary and secondary components satisfy:

$$\text{Deformation-controlled: } m\kappa Q_{CE} \geq Q_{UD} \quad (\text{ASCE 41 §3.4.2.2.1}) \quad (3-4)$$

$$\text{Force-controlled: } (m)\kappa Q_{CL} \geq Q_{UF} \quad (\text{ASCE 41 §3.4.2.2.2}) \quad (3-5)$$

where  $m$  is the component demand modification factor (taken as unity for force-controlled actions—see above),  $\kappa$  is the knowledge factor (taken as unity in this study),  $Q_{CE}$  is the expected strength of the component, and  $Q_{CL}$  is the lower-bound strength of the component.

The results of the linear assessment procedures are presented in this report as a *normalized* demand capacity ratio,  $DCR_N$ , so that the acceptance criteria verification becomes a unity check similar to that done in modern component design standards (e.g., AISC 360).  $DCR_N$  is computed by rearranging ASCE 41 Eq. 3-20 and ASCE 41 Eq. 3-21 as required. As such, a  $DCR_N$  value greater than unity indicates that the component does not satisfy the performance criteria for a given SPL.  $DCR_N$  is similar to, but different than, the  $DCR$  as used in ASCE 41. This approach is also a more consistent way to present results over the various types of assessment procedures used in this study. However, a slightly different interpretation is also taken in this study with regards to the  $DCR_N$ : in lieu of  $m$  and  $\kappa$  adjusting the apparent strength of a component, as illustrated in ASCE 41 §3.4.2.2,  $m$  and  $\kappa$  act to reduce the elastic demand to the *expected* demand given an EHL. Where required, the  $DCR_N$  is determined from an interaction equation from the appropriate equation.

$$\text{Deformation-controlled: } DCR_N = \frac{Q_{UD}}{m\kappa Q_{CE}} = \frac{DCR}{m\kappa} \quad (3-6)$$

$$\text{Force-controlled: } DCR_N = \frac{Q_{UF}}{(m)\kappa Q_{CL}} \quad [\text{with } m \text{ taken as 1.0}] \quad (3-7)$$

### 3.1.4.2 Nonlinear Procedures

Acceptance criteria of components for nonlinear assessment procedures are provided as plastic (inelastic) deformations dependent on the SPL and component type. ASCE 41 Tables 5-6 and 5-7 provide the plastic deformations limits for steel components for nonlinear assessment procedures. Adjustments to the acceptance criteria for member or connection characteristics are detailed in ASCE 41 Chapter 5.

Inelastic deformation parameters in ASCE 41 are provided for steel components in terms of plastic deformations rather than total deformations. The choice of whether to use plastic deformations or total deformations will depend on what nonlinear component model is adopted for each component action in the structural analysis (e.g., moment-curvature hinge or moment-rotation hinge). Consequently, yield and post-yield elastic deformations may need to be added to the values given in ASCE 41 to determine the total deformation for each SPL.

In this study, demands on *primary* components of new buildings are measured against acceptance criteria for *primary* components. ASCE 41 §3.4.3.2 allows *primary* component demands to be within the acceptance criteria for *secondary* components for the NSP if degradation effects are explicitly modeled—a change introduced in FEMA 356. This also includes NDP, although not explicitly stated. This allowance is neglected in this study for the following reasons:

- Bypassing nonlinear acceptance criteria set for primary components suggests that acceptance criteria for primary components for linear and nonlinear assessment procedures are not calibrated. In this study, acceptance criteria for primary components are maintained for all assessment methods to provide a uniform comparison basis.

- There is no technical justification provided in ASCE 41 as to why comprehensive component models for primary components, which are required to stabilize the structure after a large earthquake, will allow them to deform to the extent given for a secondary component and maintain the structural integrity of the system. Analytically speaking, it is debatable if collapse prevention can be reliably achieved if a concentrated few SFRS components are deformed past the deformation associated with their peak strength and lose a considerable amount of strength and stiffness. Available literature has indicated the difficulty in solution convergence in analysis when component response is following a negative stiffness branch. Still, some liberties are provided, debatably, for existing buildings, but transferring this allowance to new buildings is also of debatable validity. Engineering judgment must be applied. Broadly speaking, the function that separating existing buildings and new buildings into bins plays in developing a resilient community must be clarified.
- Reliability issues arise when adopting secondary acceptance criteria for primary components. For example, the acceptance criterion of an RBS beam-to-column connection taken as a secondary component for the Life Safety SPL is beyond the peak deformation (“*a*” in Figure 3-2). In ASCE 41, primary acceptance criteria for the Collapse Prevention SPL generally matches the deformation associated with the peak strength of a component.
- There is little empirical evidence supporting the acceptance criteria for secondary steel components permitted in ASCE 41 §3.4.3.2, other than for beam-to-column connections studied in the SAC project (see FEMA 350 series (FEMA 2000a through 200d)). Experimental tests are rarely continued to achieve the peak deformations and the associated reserve strength of a component or subassembly after the required loading protocol is complete.

As a side note, ASCE 41-13 has removed all acceptance criteria for primary components for nonlinear assessment. Future research should be conducted to evaluate the systems by measuring demands against acceptance criteria for secondary components—which can be done by inspection with the analysis results presented in this study.

#### 3.1.4.2.1 Calculating Component Assessment Results

Component forces and deformations obtained by the NSP or NDP are referred to as design actions,  $Q_U$  (e.g., plastic rotation in a plastic hinge). Component design actions are computed as the action in the member or connection at the target displacement for the NSP and as the maximum value for a given earthquake for the NDP. Subsequently, a statistical average is computed from the maximum values from the suite of ground motions. In specific cases, the maximum value must be coupled with other actions in the component at the instant of computation of the maximum response.

Component design actions classified as *deformation-controlled*,  $Q_{UD}$ , are computed by

$$Q_{UD} = Q_G \pm Q_E \quad (\text{ASCE 41 §3.4.3.2.1}) \quad (3-8)$$

Component design actions classified as *force-controlled*,  $Q_{UF}$ , are computed by

$$Q_{UF} = Q_G \pm Q_E \quad (\text{ASCE 41 §3.4.3.2.3}) \quad (3-9)$$

where  $Q_G$  is the action due to gravity loads (or associated deformation) and  $Q_E$  is the action due to earthquake effects (or associated deformations). Superposition of forces or deformations is not applicable

in a nonlinear analysis; thus, gravity loads are directly applied in the analysis. The above equations are numerical interpretations of ASCE 41 §3.4.3.2. They are used in this study to maintain computational consistency over the various types of assessment procedures.

ASCE 41 §3.4.3.2 requires that deformation-controlled and force-controlled actions in primary and secondary components satisfy:

$$\text{Deformation-controlled: } \kappa Q_{CE} \geq Q_{UD} \quad (\text{ASCE 41 §3.4.2.2.1}) \quad (3-10)$$

$$\text{Force-controlled: } \kappa Q_{CL} \geq Q_{UF} \quad (\text{ASCE 41 §3.4.2.2.2}) \quad (3-11)$$

where  $Q_{CE}$  is the expected strength or deformation demand of a component,  $Q_{CL}$  is the lower-bound strength of a component, and  $\kappa$  is the knowledge factor (taken as unity in this study). ASCE 41 Chapter 5 does not explicitly provide a relationship between  $Q_{CE}$  (or  $Q_{CL}$ ) and  $Q_y$  on the force-deformation curve.

The results of the nonlinear assessment procedures are presented in this report as a normalized demand capacity ratio,  $DCR_N$ , where the plastic or total deformation demands are normalized with respect to the plastic or total acceptance criteria, modified by  $\kappa$  if required. The acceptance criteria verification then becomes a unity check similar to that done in modern component design standards (e.g., AISC 360). As such, a  $DCR_N$  value greater than unity indicates that the component does not satisfy the performance criteria for a given SPL. This approach is a consistent way to present results over the various types of assessment procedures used in this study.

$$\text{Deformation-controlled: } DCR_N = \frac{Q_{UD}}{\kappa Q_{CE}} = \begin{cases} \text{Total} & \frac{\theta_{plastic} + \theta_{elastic}}{\kappa(\theta_y + \theta_{pe} + \theta_{p,AC})} \\ \text{Plastic} & \frac{\theta_{plastic}}{\kappa\theta_{p,AC}} \end{cases} \quad (3-12)$$

$$\text{Force-controlled: } DCR_N = \frac{Q_{UF}}{\kappa Q_{CL}} \quad (3-13)$$

where  $\theta_{plastic}$  is the plastic deformation of a component,  $\theta_{elastic}$  is the elastic deformation of a component,  $\theta_y$  is the yield deformation of a component,  $\theta_{pe}$  is the post-yield elastic deformation of a component, and  $\theta_{p,AC}$  is the acceptance criteria of a component based on plastic deformation.

## 3.2 Concentrically Braced Frame

Seismic performance assessment of *steel concentrically braced frames* is performed in accordance with ASCE 41 §5.5.2. The concentrically braced frames in the archetype buildings are designed as an SCBF as identified in ASCE 7 §12.2 (item B.2 in Table 12.2-1) and AISC 341 §F2.

### 3.2.1 Assessment Methodology

There are three primary characteristics of each component (i.e., member, connection, etc.) forming the mathematical model of the structural system for each assessment method:

1. Stiffness, ASCE 41 §5.5.2.2
2. Strength, ASCE 41 §5.5.2.3
3. Acceptance Criteria, ASCE 41 §5.5.2.4, and whether or not the component *action* is force-controlled or deformation-controlled.

Each component characteristic is discussed in the appropriate linear and nonlinear assessment discussion.

The following component design actions are assessed:

- Brace axial force or deformation (compression and tension)<sup>17</sup>
- Beam and column flexural force or deformation at potential plastic hinge zones (section strength)
- Column axial-moment interaction strength (member strength)

#### 3.2.1.1 Linear Procedures

This section discusses the three primary component characteristics listed in Section 3.2.1 and computation of the demand in the component for the linear assessment procedures.

##### Stiffness

The stiffnesses of all members and connections for linear assessment follow ASCE 41 §5.5.2.2.1. To account for the increased stiffness provided by brace-to-beam and brace-to-column (gusset plate) connections, an 18-inch prismatic section with twice the flexural stiffness,  $EI$ , is used to connect the beam-to-column joint (outside the panel zone) to the beams and columns. Braces are modeled with a rigid end equal to  $0.05L_{wp}$ , and are ‘pinned’ out-of-plane and ‘fixed’ in-plane (see Chapter 2).

##### Strength

The strength of all members and connections for linear assessment follow ASCE 41 §5.5.2.3.2.

---

<sup>17</sup> Brace connections to adjacent members are force-controlled per ASCE 41 §5.5.2.4.1. Brace connections are not assessed in this study because they are designed to resist forces computed using the maximum strengths of the brace.

The expected compression strength of a *brace* member,  $Q_{CE} = P_{CE} (= Q_y)$ , is computed as  $P_n$  from AISC 360 Chapter E with  $\phi_c = 1.0$  and  $F_{ye}$  in lieu of  $F_y$ . For A992 steel,  $F_{ye} = 1.1 \times F_y$  (see ASCE 41 Table 5-3), which corresponds to  $R_y F_y$  in AISC 341. ASCE 41 allows the effective length factor,  $K$ , of the brace member to be taken as 0.8 for in-plane buckling and 1.0 for out-of-plane buckling, and  $L$  is the clear length of the brace plus the gusset plate (*total length* in ASCE 41 §5.5.2.3.2). For the archetype buildings in this study,  $KL$  is taken as  $1.0 \times 0.9 L_{wp}$  for both axes, where  $L_{wp}$  is the length between work points, which is a conservative estimate for in-plane buckling. This total length can underestimate  $P_{CE}$  when the rotation hinges developed in the brace connections for out-of-plane buckling occur within this total length. Research should investigate methods to include gusset plate effects in assessment provisions and develop acceptance criteria for brace connections. As a side note, ASCE 41 allows  $P_{CE}$  to be governed by local buckling (section strength) and does not enforce section compactness requirements similar to AISC 341—member slenderness is enforced through the acceptance criteria.

The expected flexural strength of a member,  $Q_{CE} = M_{CE} (= Q_y)$ , is computed as  $M_n$  from AISC 360 Chapter F<sup>18</sup> with  $\phi_b = 1.0$  and  $F_{ye}$  in lieu of  $F_y$ . For ASTM A992 steel,  $F_{ye} = 1.1 \times F_y$  (see ASCE 41 Table 5-3), which corresponds to  $R_y F_y$  in AISC 341. Composite action with the concrete slab is generally neglected in computing  $M_n$  for frame beams. In so doing, it is assumed that the plastic moment strength is achievable via adequate lateral bracing, thus  $M_n = M_p$ . If the flexural strength is less than  $M_p$ , then the available ductility of the member is significantly reduced because of member or cross-section instability (which also affects the acceptance criteria). ASCE 41 enforces section compactness requirements through the acceptance criteria—discussed subsequently.

The lower-bound flexural strength of a member,  $Q_{CL} = M_{CL}$ , is computed as  $M_n$  from AISC 360 Chapter F<sup>18</sup> with  $\phi_b = 1.0$  and  $F_{yLB}$  in lieu of  $F_y$ . For ASTM A992 steel,  $F_{yLB} = 1.0 \times F_y$  (see ASCE 41 Table 5-2).

Although not explicitly identified in ASCE 41 §5.4.2.3.2, the expected shear strength of a member,  $Q_{CE} = V_{CE} (= Q_y)$ , is identical to that computed as  $V_n$  from AISC 360 Chapter G with  $\phi_v = 1.0$  and  $F_{ye}$  in lieu of  $F_y$ . Web slenderness,  $h / t_w$ , is critical in developing a fully yielded cross-section. As such, there are cases when

$$\frac{418}{\sqrt{F_y}} = 2.45 \sqrt{\frac{E}{F_y}} < \frac{h}{t_w} \leq \frac{640}{\sqrt{F_y}} = 3.76 \sqrt{\frac{E}{F_y}} \quad (3-14)$$

and the web is still capable of achieving full yield strength in shear. However, if the web slenderness approaches the upper limit (taken as the ‘compact’ limit in AISC 360 Table B4.1) then the beam may have difficulty achieving its plastic moment strength,  $M_p$ . There is no lower-bound shear strength,  $V_{CL}$ , in ASCE 41 or shear-moment interaction.

The lower-bound compression strength of a member,  $Q_{CL} = P_{CL}$ , is computed as  $P_n$  from AISC 360 Chapter E<sup>18</sup> with  $\phi_c = 1.0$  and  $F_{yLB}$  in lieu of  $F_y$ . For ASTM A992 steel,  $F_{yLB} = 1.0 \times F_y$  (see ASCE 41 Table 5-2).

---

<sup>18</sup> ASCE 41 inadvertently states AISC 341.

Though identified in ASCE 41 §5.4.2.3.2-2, no guidance is provided for computing the expected flexural strength,  $M_{CE}$ , of a compression member if the axial load,  $P$ , exceeds 10 percent of the *axial strength*. This guidance would be useful for computing the flexural *DCR* at a given location, such as at the column base. The term *axial strength* of a compression member is also not well defined (i.e., is it  $P_{ye}$  or  $P_{CL}$ ?). Similarly, the axial load,  $P$ , is not defined except in an unrelated provision for the NSP. ASCE 41 §5.4.2.2.2 states that  $P$  for a linear analysis is  $P_{UF}$ . The flexural strength will also depend on the chosen  $P$ - $M$  interaction curve, which will use  $M_{CE}$  (or  $M_{CL}$ ) at  $P = 0$  as the anchor point. There is little need to have triggering language based on 10 percent axial load ratio because it delineates no physical phenomenon and does not also influence computing the yield chord rotation,  $\theta_y$ . In fact, it adds complexities, which will be discussed subsequently in the Acceptance Criteria section. ASCE 41 does not delineate between orthogonal buckling axes and non-flexural buckling limit states (e.g., torsional, local buckling) for its interaction verification. This can significantly affect the assessment of beam-column members where high in-plane moment is associated with a buckling limit state other than in-plane flexural buckling. Beam-columns can be further penalized in linear assessment methods where  $P_{UF}$  is highly affected by selecting a value for  $J$ .

The expected tension strength of a member,  $Q_{CE} = T_{CE} (= Q_y)$ , is computed as  $A_c \times F_{ye}$ , where  $A_c$  is the cross-sectional area of the member. ASCE 41 does not provide other tensile strengths, potentially brittle, similar to AISC 360 Chapter D, e.g., net section fracture.

The expected shear strength of a panel zone,  $Q_{CE} = V_{CE} (= Q_v)$ , is computed as  $0.55 F_{ye} \times d_b \times t_p$ . (ASCE 41 Equation 5-5<sup>19</sup>). This strength equates to  $0.92 \times V_y$  from AISC 360 Chapter J10.6 with  $\phi_v = 1.0$  and  $F_{ye}$  in lieu of  $F_y$ . ASCE 41 does not provide additional panel zone strength to account for column flange bending.

ASCE 41 does not provide explicit guidance on computing the strength of a beam-to-column connection in a CBF. The controlling mechanism for a beam-to-column connection is taken as the *lower-bound* flexural strength,  $Q_{CL}$ , measured at the face of the column. This flexural strength is determined using AISC 360 with  $\phi = 1.0$  and  $F_{yLB}$  in lieu of  $F_y$ . Similarly, the *lower-bound* strength of a brace-to-beam and brace-to-beam/column connection is determined from AISC 360 and is force-controlled for all design actions.

### Acceptance Criteria

The acceptance criteria of members and connections for linear assessment follow ASCE 41 §5.5.2.4.2.

### **Axial Force in Braces and Brace Connections**

The acceptance criteria for *axial* tension and compression actions in brace members are provided in ASCE 41 Table 5-5 and dependent on member slenderness parameter,  $KL / r$ , where  $K$  can be taken as 0.8 or 1.0, as discussed previously, and section configuration (wide-flange, HSS, pipe, etc.). While other provisions explicitly use  $F_{ye}$  for cross-section slenderness triggers, the member slenderness triggers use  $F_y$  to match test data. The “slender” brace trigger is nearly that used to delineate between inelastic and elastic flexural buckling (i.e.,  $1.414 \times \pi$ ) taken from AISC Seismic Provisions (1994) for an ordinary concentrically braced

---

<sup>19</sup> The reason the shear yield stress for a column web (assuming it can be designated as a beam) being defined as  $0.6 \times F_{ye}$  is not clear, but if the same column web is a panel zone, the shear yield stress is  $0.55 \times F_{ye}$ .

frame. The slenderness trigger for “stocky” braces is taken as one-half of that designating a slender brace, demarcating inelastic flexural buckling and plastic axial capacity of the brace—stocky braces will have  $P_{CE}$  close to  $P_{ye}$ . The allowable increase in  $KL / r$  applied to braces in an SCBF in AISC 341 is not applicable in ASCE 41. ASCE 41 does not provide variation in acceptance criteria when local buckling governs the expected compression strength,  $P_{CE}$ . ASCE 41 should expand the commentary to provide guidance and clarification regarding material properties and development of the acceptance criteria for braces in compression and tension.

Brace connections are considered force-controlled for axial actions in ASCE 41.

### **Flexure in Beams, Beam-to-Column Connections, and Brace Connections**

The acceptance criteria for *flexural* action at expected locations of plastic hinging in beams (members with axial load ratio less than or equal to 10 percent) are provided in ASCE 41 Table 5-5 and are dependent on web and flange slenderness. The range of flange limits match AISC 341 limits for *highly* and *moderately* ductile unstiffened compression elements. The range of web limits match AISC 341 limits for *highly* and *moderately* ductile stiffened compression elements taking at  $P = 0$ . The flange and web slenderness limits for moderately ductile sections are taken as a ‘compact’ compression element in AISC 360 (i.e.,  $\lambda_p$ ). The lower-bound web slenderness limit is taken as that capable of fully section yielding in shear. These web slenderness limits were introduced in FEMA 356 whereas flange limits were introduced in FEMA 273 and subsequently modified in FEMA 356 (upper-bound limit was changed from a pure axial compression limit to a compression from flexure limit).

Flexural actions in beams in chevron braced frames are considered force-controlled in ASCE 41—this component, however, should be evaluated as a *column* unless permitted otherwise because of the axial load ratio (see discussion below on connections). Force-controlled classification in these components is consistent with AISC 341 provisions for new buildings. Research on the performance of chevron frames that permit beam yielding in combination with brace buckling and yielding could support this as an effective assessment option.

In cases where the expected flexural strength of an unbraced segment is governed by instability (e.g., lateral-torsional buckling (LTB)) rather than full section yielding, the  $m$ -factors in ASCE 41 Table 5-5 shall be reduced accordingly. Again, ASCE 41 inadvertently references AISC 341 for these calculations as well as uses the notation,  $M_r$ , which is no longer used in AISC 360.

The acceptance criteria for beam-to-column connections (flexural hinge is located within the connection) are taken from Fully Restrained Moment Connections in ASCE 41 Table 5-5 and are dependent on connection detailing, panel zone strength in a balanced yield condition, and member and cross-section slenderness (see ASCE 41 §5.4.2.4.2, 4.1 to 4.4). It is assumed that the acceptance criteria for FR beam-to-column connections ( $m$ -factor) translated from results from the SAC project are applicable at the face of the column—see §3.2.1.2. Furthermore, the  $m$ -factors for beams are not applicable for flexural plastic hinges within the region<sup>20</sup> demarcating the beam-to-column connection when connection components

---

<sup>20</sup> This region is also used in AISC 341 to define the *protected zone*.

prevent the unobstructed spread of plasticity. ASCE 41 does not provide acceptance criteria for flexural actions for a beam-to-column connection that includes a brace connection (i.e., brace-to-beam/column) or a brace-to-beam connection. ASCE 41 requires that brace connections in a CBF be force-controlled for flexural actions. As such, using acceptance criteria applicable for beams to evaluate plastic hinges in beams adjacent to a brace connection could be unconservative. It is debatable that these hinges are within the connection and therefore should be classified as force-controlled.

### **Flexure in Columns and Column-to-Base Connections**

The acceptance criteria for *flexural* action at expected locations of plastic hinging in columns (members with axial load ratio greater than 10 percent) are provided in ASCE 41 Table 5-5 and are dependent on the axial load ratio,  $P_{UF}/P_{CL}$ , and web and flange slenderness. As discussed above, ASCE 41 does not delineate between orthogonal buckling axes and non-flexural buckling limit states (e.g., torsional, local buckling) for computing  $P_{CL}$ . Consequently, this can significantly affect the assessment of beam-column members where a high in-plane moment is associated with a buckling limit state other than in-plane flexural buckling. If the axial load ratio is greater than 0.5, then flexural action is considered force-controlled and the flexural demand and strength are taken as  $M_{UF}$  and  $M_{CL}$ , respectively. Otherwise, the  $m$ -factor is adjusted for  $P$ - $M$  interaction as shown in Figure 3-4 and the flexural demand and strength are taken as  $M_{UD}$  and  $M_{CE}$ , respectively.

The flange slenderness limits for columns are the same as those for beams and are *independent* of axial load. The lower-bound web slenderness range is essentially<sup>21</sup> 75 percent of the slenderness limits in AISC 341-02 (AISC 2002)—taken from FEMA (2000c)—at distinct axial force ratios (0.2 and 0.5). These ratios are at the upper range of axial force ratios in ASCE 41, albeit  $P_{UF}/P_{ye}$  and  $P_{UF}/P_{CL}$  represent two physically different phenomena in regards to plate buckling. The upper-bound web slenderness range is essentially the slenderness limits in AISC 341-02 at distinct axial force ratios (0.1 and 0.2). These ratios are at the lower range of axial force ratio in ASCE 41. Using fixed axial limits on slenderness can lead to excessive conservatism because of step function triggers, as illustrated in Figure 3-5 for the LS SPL—AISC 341 web compactness limits for highly (HD) and moderately (MD) ductile compression elements are included for comparison. The spherical icons shown in the figure represent the web slenderness ratios for all wide-flange sections currently available. Essentially, 35 percent of these sections do not satisfy the lower-bound criteria in ASCE 41 whereas this value reduces to 12 percent when using the AISC 341 criteria for highly ductile elements. Ultimately, the step functions created by both the axial load ratios and the section compactness requirements result in a highly complex formulation that is difficult to implement, as illustrated in Figure 3-6 for the LS SPL (plastic rotation is shown in lieu of  $m$ -factor). ASCE 41 could be simplified by combining the acceptance criteria for beams and columns into one set of criteria with no 10 percent axial load ratio trigger.

In addition to the effect of  $P$ - $M$  interaction on the  $m$ -factors (which is a section strength issue) for checking flexural actions in a column in accordance with ASCE 41 §3.4.2.2, member stability is also checked via global interaction equations in accordance with ASCE 41 §5.4.2.4, as shown in Figure 3-4—see projection of axial and moment ratios. The discontinuous curve is a result of variable  $P$ - $M$  interaction equations, with

---

<sup>21</sup> Work to develop FEMA 356 was conducted at the same time as the SAC project—see FEMA 350 series.

the discontinuity at  $P_{UF} / P_{CL} = 0.5$  being smallest when  $M_{CL}$  at  $P_{UF} = 0$  equals  $M_p$ , and gets larger as  $M_{UD} / M_{UF}$  increases. Future efforts should simplify the ASCE 41 interaction curves for consistency and applicability, including eliminating  $F_{y, LB}$  for a column that also uses  $F_{ye}$ .

Axial compression action in a column is always force-controlled due to significant reduction in ductility because of member and cross-sectional instability. Again, ASCE 41 is rather ambiguous when it comes to steel columns. First, there is no guidance on computing  $M_{CE}$  for a column. Although ASCE 41 §5.4.2.4.2-2 provides some information, it is not consistent with that required to define the expected flexural strength,  $M_{CE}$ . Second, the  $m$ -factor is reduced for beams to account for LTB. Since this failure mode is also applicable to columns, the  $m$ -factor should similarly be reduced. However, a column that fails in LTB should be avoided, and  $m = 1$  adopted since LTB is not a ductile phenomenon. Also,  $\kappa$  is not in the interaction equations similar to other verification procedures, and it is unclear if these equations have any physical meaning because member stability and section yielding effects are combined. Moreover, these equations can be conservative when weak-axis buckling is coupled with in-plane (strong-axis) bending.




Figure 3-4.  $P$ - $M$  Interaction on Section  $m$ -factor (in-plane) and Member Instability (Primary Component)

## Life Safety





Figure 3-5. Compactness Requirements as a Function of Axial Load Ratio, LS Acceptance Criteria

In terms of assessment, ASCE 41 does not explicitly address column hinges near the column-to-base connections of a frame (similar to a beam-to-column connection). Columns are designed in accordance with capacity design provisions in AISC 341. However, ASCE 41 does not similarly adopt a capacity design approach for the assessment of CBF columns and beams as is done for EBF columns and beams (see ASCE 41 §5.5.3.4.1).

### Shear in Panel Zones

The acceptance criteria for *shear* action in panel zones are provided in ASCE 41 Table 5-5. The acceptance criteria are not a function of the axial force demand in the panel zone.



**Figure 3-6. Acceptance Criteria as a Function of Axial Load Ratio and Section Compactness, LS Acceptance Criteria**

Demand

The axial demand,  $P_{UD}$ , for the brace is taken as the axial force at the mid-span of the brace. The flexural demand,  $M_{UD}$  or  $M_{UF}$ , and axial force,  $P_{UF}$ , for the columns are taken as the moment and axial force at the face of the each beam (top and bottom). The flexural demand,  $M_{UD}$  or  $M_{UF}$ , for the beams is taken as the moment at the face of the brace connection. The flexural demand,  $M_{UD}$  or  $M_{UF}$ , for the beam-to-column connections is taken as the moment at the face of the column or edge of the brace connection.

Table 3-10 summarizes the basic  $m$ -factors for the components of the SCBF for the linear procedures. Figure 3-7 through Figure 3-12 provide the load-independent  $m$ -factors—taking in to account force-controlled and deformation-controlled classifications (force-controlled components are assigned an  $m$ -factor of unity, see §3.1.4.1). These figures are referred to herein as “Frame Capacity Schematics.” The two

values given for a column represent the cases when  $P_{UF}/P_{CL} = 0.2$  and  $0.5$ , adjusted for section compactness requirements. At  $P_{UF}/P_{CL} = 0.2$  the interaction equation provides the same value when  $P_{UF}/P_{CL} < 0.2$ .

**Table 3-10. Basic  $m$ -factors for Linear Procedures, SCBF**

Component - Action	Performance Level	
	LS	CP
<b>Beam - Flexure</b>		
a) $\frac{b_f}{2t_f} \leq \frac{52}{\sqrt{F_{ye}}}$ and $\frac{h}{t_w} \leq \frac{418}{\sqrt{F_{ye}}}$	6	8
b) $\frac{b_f}{2t_f} \geq \frac{65}{\sqrt{F_{ye}}}$ or $\frac{h}{t_w} \geq \frac{640}{\sqrt{F_{ye}}}$	2	3
c) other	linear interpolation	
<b>Column - Flexure</b>		
for $P_{UF}/P_{CL} < 0.2$		
a) $\frac{b_f}{2t_f} \leq \frac{52}{\sqrt{F_{ye}}}$ and $\frac{h}{t_w} \leq \frac{300}{\sqrt{F_{ye}}}$	6	8
b) $\frac{b_f}{2t_f} \geq \frac{65}{\sqrt{F_{ye}}}$ or $\frac{h}{t_w} \geq \frac{460}{\sqrt{F_{ye}}}$	1.25	2
c) other	linear interpolation	
for $0.2 \leq P_{UF}/P_{CL} \leq 0.5$		
a) $\frac{b_f}{2t_f} \leq \frac{52}{\sqrt{F_{ye}}}$ and $\frac{h}{t_w} \leq \frac{260}{\sqrt{F_{ye}}}$	$9\left(1 - \frac{5}{3} \frac{P}{P_{CL}}\right)$	$12\left(1 - \frac{5}{3} \frac{P}{P_{CL}}\right)$
b) $\frac{b_f}{2t_f} \geq \frac{65}{\sqrt{F_{ye}}}$ or $\frac{h}{t_w} \geq \frac{400}{\sqrt{F_{ye}}}$	1.25	1.5
c) other	linear interpolation	
<b>Column Panel Zone - Shear</b>	8	11
<b>Braces - Compression (except EBF)</b>		
a) Slender $\frac{KL}{r} \geq 4.2 \sqrt{\frac{E}{F_y}}$		
1. W-shapes	6	8
2. HSS, pipes, tubes	5	7
b) Stocky $\frac{KL}{r} \leq 2.1 \sqrt{\frac{E}{F_y}}$		
1. W-shapes	5	7
2. HSS, pipes, tubes	4	6
c) intermediate	linear interpolation	
<b>Braces - Tension (except EBF)</b>	6	8




Figure 3-7. Frame Capacity Schematic (*m*-factor), LS and CP, 4-Story SCBF ELF




Figure 3-8. Frame Capacity Schematic (*m*-factor), LS and CP, 4-Story SCBF RSA




Figure 3-9. Frame Capacity Schematic (*m*-factor), LS and CP, 8-Story SCBF ELF




Figure 3-10. Frame Capacity Schematic (*m*-factor), LS and CP, 8-Story SCBF RSA




Figure 3-11. Frame Capacity Schematic (*m*-factor), LS and CP, 16-Story SCBF ELF




Figure 3-12. Frame Capacity Schematic (*m*-factor), LS and CP, 16-Story SCBF RSA

### 3.2.1.2 Nonlinear Procedures

This section discusses the three primary component characteristics listed in Section 3.2.1 and computation of the demand in the component for the nonlinear assessment procedures.

#### Stiffness, Strength, Acceptance Criteria, and Demand

Component characteristics follow that outlined previously for the linear procedures. Although component stiffness is the primary characteristic in linear procedures, component strength is of equal importance in nonlinear procedures.

The stiffnesses of all members and connections for nonlinear assessment follow ASCE 41 §5.5.2.2.2 for the NSP and ASCE 41 §5.5.2.2.3 for the NDP. The strength of all members and connections for nonlinear assessment follow ASCE 41 §5.5.2.3.3 for the NSP and ASCE 41 §5.5.2.3.4 for the NDP. The same analytical model is used for both the NSP and NDP—see §3.1.3.2.

Compound elements with elastic and inelastic components are used for constructing all members in PERFORM-3D. Elastic stiffness and strength characteristics for each component follow that outlined for the linear procedures. Nonlinear components include the column flexural hinge modeled with axial-moment ( $P$ - $M$ ) interaction and the panel zone modeled using the Krawinkler model (Krawinkler 1978). Gusset plate connections for braces are not explicitly modeled. The flexural rigidity,  $EI$ , of the portion of a member adjacent to a gusset plate is increased to approximate the effect of gusset plate rigidity in the plane of the frame. Figure 3-13 illustrates the analytical model of a brace-to-beam / column subassembly for nonlinear assessment procedures. In the figure, Default End Zones are modeled with a flexural rigidity factor of two; a higher end zone factor is potentially too rigid to capture flexural deformations within the joint region. Detailed information concerning all aspects of the analytical model for nonlinear analysis can be found in PERFORM-3D *Components and Elements* (CSI 2011c).

HSS braces are modeled as single-entity buckling elements (strut) in PERFORM-3D with rigid end zones and beam and column modifications to account for brace connection stiffness—discussed above. Axial strength and stiffness degradation are modeled based on calibrating the PERFORM-3D MODEL with experimental test data (see Figure 3-14—PERFORM-3D response is presented as “Analysis”). The tension and compression strength of the brace is taken as  $T_{CE}$  and  $P_{CE}$ , respectively. Inelastic strain parameters are taken from ASCE 41 Table 5-7 and interpolated where required. Brace fracture upon repeated inelastic cycles (low-cycle fatigue) is not captured in the hysteretic model or the nonlinear analysis.

Flexural plasticity in beams and beam-columns is represented by nonlinear *moment-curvature* (MC) relationships which in turn are based on *moment-chord rotation* (MR) relationships provided by ASCE 41 Table 5-6. This shift in basis highlights a discrepancy between ASCE 41 §5.4.2.2.2-2 and the prescribed acceptance criteria. Conversion between plastic rotation and plastic curvature is done using a defined plastic hinge length,  $l_p$ . An MC hinge is preferred in lieu of an MR hinge, as yield rotation,  $\theta_y$ , specified in ASCE 41 can lead to inconsistencies when beam models include rigid end offsets and when hinges are modeled away from the column faces. Further, ASCE 41 does not provide guidance on an appropriate beam length,  $l_b$  (ASCE 41 Equation 5-1). Theoretically, there is no difference between an MC hinge and an MR hinge model as long as the conversion procedure for all nonlinear model parameters between the two is

maintained.  $P$ - $M$  interaction effects on a moment-curvature hinge are included in the analytical model (discussed subsequently).




Figure 3-13. SCBF Brace-to-Beam / Column Subassembly Analytical Schematic




Figure 3-14. PERFORM-3D Brace Calibration

Where needed to model a flexural hinge within a beam span or a flexural hinge within (or adjacent to) a connection (e.g., next to the brace-to-beam connection in the chevron frame), an MC hinge is placed at the center of the hinge with a plastic hinge length equal to the depth of the beam,  $d$ . Plastic rotation parameters modeling the backbone curve of the beam or connection hinge are taken from ASCE 41 Table 5-6. These values are converted to plastic curvature and, if needed, adjusted from application at the column face to the center of the hinge (no adjustment is needed for a conventional beam hinge) and other connection adjustments discussed next. The residual strength ratio ( $c$  in ASCE 41 Table 5-6) is normalized to the yield strength,  $M_{CE}$ , not the ultimate strength as required in PERFORM-3D.

Where applicable, the acceptance criteria for beam-to-column connections (flexural hinge is located within the connection) are taken from Fully Restrained Moment Connections in ASCE 41 Table 5-6 and are dependent on connection detailing, panel zone strength in a balanced yield condition, and member and cross-section slenderness (see ASCE 41 §5.4.2.4.3, 4.1 to 4.4). These reduction factors are also applied to the plastic rotation values defining the backbone curve. This is done because the CP acceptance criteria for a primary FR connection was taken to match  $a$ —see Figure 3-2, and therefore any connection configuration that affects the value for  $a$  also affects the acceptance criteria. Similarly, the acceptance criteria are converted to plastic curvature and the application point is adjusted to the center of the hinge. Expanded commentary on beam-to-column connection versus beam hinge acceptance criteria is needed in ASCE 41, as well as a discussion clarifying the reductions to the plastic rotation values defining the backbone curve and acceptance criteria. ASCE 41 does not provide acceptance criteria for flexural actions for a beam-to-column connection that includes a brace connection (i.e., brace-to-beam/column) or a brace-to-beam connection. ASCE 41 requires that brace connections in a CBF be force-controlled for all actions. As such, using acceptance criteria applicable for beams to evaluate plastic hinges in beams adjacent to a brace connection could be unconservative. It is debatable that these hinges are within the connection and therefore should be classified as force-controlled.

Frame columns (i.e., beam-columns) are modeled similar to beams discussed previously, except that flexural  $PMM$  MC hinges that capture the combined effects of axial force and biaxial moments are placed near the joint region boundaries (see Figure 3-13). The plastic hinge length is assumed to be equal to the depth of the column,  $d_c$ . Out-of-plane moments are small relative to the in-plane moments in the SFRS members because each SFRS is an isolated planar frame in the direction of loading. Plastic rotation parameters of the flexural  $PMM$  hinges are taken from “columns” in ASCE 41 Table 5-6 and converted to plastic curvature (no adjustment for hinge location is needed). Criteria for flexural hinges based on member buckling strengths can be complex and problematic in capturing the in-plane nonlinear flexure behavior. For example, yield rotation,  $\theta_y$ , for a column is based on section strength,  $P_{ye}$ , while modeling parameters and acceptance criteria (function of  $\theta_y$ ) are based on member strength,  $P_{CL}$ , without regard to the plane of buckling. ASCE 41-13 took the first step in resolving some issues concerning steel columns by permitting the modeling parameters to be determined using  $P / P_{CL}$  in the plane of buckling. Still,  $P$ - $M$  interaction curves still require some clarification and guidance. In terms of assessment, ASCE 41 does not explicitly address column hinges near the column-to-base connections of a frame (similar to a beam-to-column connection).

In this study, modeling and acceptance criteria for the beam-column flexural hinges are taken as those provided for columns in ASCE 41 Table 5-6. The  $P$ - $M$  interaction effect on the in-plane flexural strength

of a column hinge,  $M_{CEx}$ , where  $x$  denotes the in-plane bending axis, is modeled by the *section* strength of the member (i.e., yield surface) using  $P / P_{ye}$  in ASCE 41 Equation 5-4 (repeated below as Equation (3-15)); see Figure 3-15, Figure 3-17, and Figure 3-18).  $P$ - $M$  interaction relationships provided in PERFORM-3D for the yield surfaces of MC hinges in beam-columns are calibrated to approximate this curve as illustrated in Figure 3-18.

$$M_{CEx} = 1.18M_{pe,x} \left( 1 - \frac{P}{P_{ye}} \right) \leq M_{pe,x} \quad (\text{ASCE 41 Equation 5-4}) \quad (3-15)$$

ASCE 41 Equation 5-4 is based on plastic design theory and applicable for the in-plane section strength (strong-axis bending) of a wide flange section. AISC 360 Equation H1-1 can also be applied for computing the in-plane section strength by using  $P / P_{ye}$  in lieu of  $P_r / P_c$  as defined in AISC 360. Plastic design theory also gives the out-of-plane section strength (weak-axis bending, with  $y$  denoting the out-of-plane bending axis) of a wide flange section as Equation (3-16).

$$M_{CEy} = 1.19M_{pe,y} \left( 1 - \left( \frac{P}{P_{ye}} \right)^2 \right) \leq M_{pe,y} \quad (3-16)$$


$P$ - $M$  interaction effect on the plastic rotation parameters and acceptance criteria of a column hinge is modeled by *member* strength using  $P_{CL}$ , computed for buckling about any axis or failure mode independent of the effect it may have on the in-plane flexure response of the column hinge (see Figure 3-15).

First, ASCE 41 requires a column (i.e., flexural hinge in the column) to be force-controlled for flexure when  $P / P_{CL} > 0.5$  for the nonlinear procedures and references the same equation used for linear assessment. This can be extremely problematic as separate strengths and interaction equations create discontinuities that cannot be effectively addressed in analysis software (see Figure 3-15). This elastic interaction equation is neglected in this study for nonlinear assessment and the hinge model obeys ASCE 41 Equation 5-4 independent of  $P_{CL}$ . ASCE 41 Equation 5-12 is more applicable for checking member stability than defining the section yield surface; Equation (3-17) rearranges ASCE 41 Equation 5-12 in terms of the moment strength.

$$M_{CE} = M_{CL} \left( 1 - \frac{P}{P_{CL}} \right) \quad (\text{from ASCE 41 Equation 5-12}) \quad (3-17)$$

Second, flexural hinge model parameters and associated acceptance criteria are a function of the axial load ratio  $P / P_{CL}$ . Provisions for this interaction in ASCE 41, however, create a discontinuity in the curve, as shown in Figure 3-16, which cannot be effectively addressed in analysis software. PERFORM-3D provides a simplified curve to model the variation in acceptance criteria with axial force, also shown in Figure 3-16. The adopted curves in this study are conservative for  $P / P_{CL} \leq 0.2$ . Further, because of constraints on  $P$ - $M$  hinge models in PERFORM-3D, the model parameters ( $a$  in ASCE 41 Table 5-6 plus the elastic component as shown in Figure 3-16,  $a$  plus elastic = DL in PERFORM-3D—see Figure 3-2 for  $a$  and DL) do not coincide for  $P / P_{CL} > 0.2$ . A column hinge with high axial load can reach its peak strength ( $a$  plus elastic =

CP in this case) in regards to the provisions of ASCE 41 yet still be able to maintain its flexural strength. In general, column hinges are not expected to be significantly strained; however, demands may affect the performance of base hinges, which can have detrimental effects on the system upon loss of strength. More detailed information can be found in the *PERFORM-3D User Guide* (CSI 2011d) and *PERFORM-3D Components and Elements* (CSI 2011c). Lastly, it is of questionable validity to allow a primary column component in a SFRS to have acceptance criteria based on a secondary component when based on a function of  $P / P_{CL}$  as was mentioned earlier.



**Figure 3-15. In-plane Flexural Hinge Yield Surface Model (Including Force-Controlled Response)**

The ultimate flexural strength of the MC hinge is taken as 1.1 times  $M_{CE}$  at  $P = 0$ . This flexural strength increase is held constant for all values of axial force in PERFORM-3D. The residual strength ratio ( $c$  in ASCE 41 Table 5-6) is normalized to the yield strength,  $M_{CE}$ , at distinct  $P / P_{CL}$  values (not  $P / P_{ye}$ , which is used to compute  $M_{CE}$ ) and not the ultimate strength as required in PERFORM-3D.

Stability of a beam-column needs to be addressed in addition to capturing flexural plasticity. However, ASCE 41 does not provide explicit provisions to check member stability when  $P / P_{CL} \leq 0.5$  for nonlinear procedures. When  $P / P_{CL} > 0.5$ , ASCE 41 Equation 5-12 (primarily used for the linear procedures) can be used, but is not recommended as discussed previously.

In this study, section strength flags are applied to the frame columns as an indicator of member instability. For in-plane buckling and strong axis bending, a  $PM$  strength flag is placed at the ends of the column using AISC 360 §H1.3(a) for the interaction curve using  $P_{n,x}$  as  $P_c$ . This approach closely aligns with ASCE 41 Equations 5-10, 5-11, and 5-12. The in-plane effective length of the column is taken as that computed for design (i.e., adjusted  $K$  factor—see Chapter 2). This is considered a conservative practice as the analysis adjusts the stiffness matrix (only for material nonlinearity) at every time step and the leaning column effect is explicitly included. However, geometric imperfections (system and member), residual stresses, and epistemic uncertainties (i.e.,  $\phi$  factor) are not included in the mathematical model. Consequently, member

strengths based on the actual unbraced length (i.e.,  $KL_x = L_x$ ) is of questionable validity, but so is using the design value based on a vertical load-only load combination. Research is needed concerning in-plane dynamic instability of inelastic members.





Figure 3-16. Variation in Acceptance Criteria and Hinge Model for Axial Force

For out-of-plane buckling and strong axis bending, a  $PM$  strength flag is placed at the ends of the column using AISC 360 §H1.3(b) for the interaction curve and the effective length is taken as the actual unbraced length (i.e.,  $KL_y = L_y$ ). Adopting ASCE 41 Equations 5-10, 5-11, and 5-12 as an indicator of weak-axis instability coupled with in-plane bending can be highly conservative. PERFORM-3D uses a single continuous interaction curve as shown in Figure 3-19 which illustrates several interaction curves together with the approximations from PERFORM-3D. Similar to beams, section strengths are modified as needed based on cross-section geometry, member strengths (commonly controls columns in compression), and design-assessment criteria prescribed in ASCE 41.

Figure 3-20 through Figure 3-23 provide the load-independent acceptance criteria—with consideration of force-controlled and deformation-controlled classifications. These figures are referred to herein as “Frame Capacity Schematics.” The two values given for a column represent the cases when  $P_{UF} / P_{CL} = 0.2$  and  $0.5$ , adjusted for section compactness requirements. At  $P_{UF} / P_{CL} = 0.2$ , the interaction equation does not provide the same value when  $P_{UF} / P_{CL} < 0.2$ , as seen for the linear procedures.

Primary Component  
Life Safety



**Figure 3-17. P-M Interaction on Plastic Rotation, LS Acceptance Criteria (Primary Component)**




Figure 3-18. *P-M* Interaction Curve (Section Yield Surface)




Figure 3-19. *P-M* Interaction Curve (Member Instability)




Figure 3-20. Frame Capacity Schematic (Inelastic), LS and CP, 4-Story SCBF ELF and RSA





Figure 3-21. Frame Capacity Schematic (Inelastic), LS and CP, 8-Story SCBF ELF and RSA



Braces = Total Strain  $\times 10^5$   
 Columns = Total Curvature  $\times 10^6$  (for  $P/P_{CL} = 0.2, 0.5$ )

CP = Collapse Prevention, LS = Life Safety, YD = Yield  
 T = Top Hinge, B = Bottom Hinge  
 All values are for Primary Components

**Figure 3-22. Frame Capacity Schematic (Inelastic), LS and CP, 16-Story SCBF ELF**




Figure 3-23. Frame Capacity Schematic (inelastic), LS and CP, 16-Story SCBF RSA

### 3.2.2 Seismic Assessment Results

The results for the SCBFs assessed using each of the four analysis procedures are presented in this section. The following section highlights any failure to satisfy the acceptance criteria.

For the LSP and LDP, force-controlled column compression demands,  $P_{UF}$ , are computed by taking  $J$  in ASCE 41 §3.4.2.1.2-2 as the minimum DCR—as defined in ASCE 41—of the component(s) (i.e., braces) delivering force to the member, but not less than 2.0. In this case, this method generally provides the least conservative axial force demand estimates than that determined from a *fully yielded* capacity design analysis per ASCE 41 §3.4.2.1.2-1. However, ASCE 41 does not provide explicit guidance on performing this capacity design analysis<sup>22</sup> for a concentrically braced frame, as is done for an eccentrically braced frame in ASCE 41 §5.5.3.4. The capacity design procedure in AISC 341 §F2.3 is adopted in this study to determine the maximum axial load demands to fulfill ASCE 41 §3.4.2.1.2-1. Further, axial force demand estimates from the capacity design procedure using the system overstrength factor,  $\Omega_o$ , in ASCE 7 are included with those determined from ASCE 41 in the respective analysis sections below. Force-controlled component actions are assigned an  $m$ -factor of unity, see §3.1.4.1.

Analysis results (e.g.,  $DCR_N$ ) for the NDP using the ground motion record set are statistically summarized by the median, mean, 84<sup>th</sup> percentile, and mean plus one standard deviation response for both the LS BPL (given the BSE-1 EHL) and the CP BPL (given the BSE-2 EHL). Mean and median response are presented because (1) ASCE 41 does not discuss how to process the results in the event of a structural collapse under a given record in the set, (2) new provisions under investigation for inclusion in the 2015 *NEHRP Provisions* are being debated as to how to process results from eleven records (an increase from seven in ASCE 7-10), and (3) the difference is small for well-performing systems that remain stable for all motions in a set. It is the goal here that showing the mean and median will assist in developing future code provisions.

For comparison purposes only, the  $DCR_N$  values obtained from the LSP, LDP, and NSP are superimposed on the figures showing the results obtained from the NDP. Results from the NSP and NDP can be directly compared because the basis of measurement is identical. However, caution should be used when comparing linear and nonlinear results by inspection because the nature of the analysis is fundamentally different; presenting them together here is not intended to imply they are equivalent. Results from the two are not always directly comparable as linear results would first need to be converted to total demand where applicable, and in certain cases not based on an interaction equation. Results from the linear assessment procedures are presented alongside results from the nonlinear assessment procedures primarily to highlight the distribution of performance predictions between the analytical methods.

For comparison purposes only, the base shears computed using the LSP and LDP are provided in §3.2.3.1.3.

---

<sup>22</sup> ASCE 41 §3.4.2.1.2-1 refers to this type of analysis as a “limit state” analysis.

### 3.2.2.1 Four-Story Concentrically Braced Frame

#### 3.2.2.1.1 Linear Static Procedure

##### 3.2.2.1.1.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-24 and Figure 3-25 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-26 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-24(b) and Figure 3-25(b) show that the frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5.




Figure 3-24. LSP Assessment Results, 4-Story SCBF ELF, BSE-1 LS





Figure 3-25. LSP Assessment Results, 4-Story SCBF RSA, BSE-1 LS



**Figure 3-26. LSP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-1**

### 3.2.2.1.1.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-27 and Figure 3-28 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, at the LSP at the BSE-2 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-29 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the CP BPL acceptance criteria. Figure 3-27(b) and Figure 3-28(b) show that the frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5.




Figure 3-27. LSP Assessment Results, 4-Story SCBF ELF, BSE-2 CP




Figure 3-28. LSP Assessment Results, 4-Story SCBF RSA, BSE-2 CP




Figure 3-29. LSP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-2

3.2.2.1.2 Linear Dynamic Procedure

3.2.2.1.2.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-30 and Figure 3-31 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LDP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-32 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-30(b) and Figure 3-31(b) show that the frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5.




Figure 3-30. LDP Assessment Results, 4-Story SCBF ELF, BSE-1 LS




Figure 3-31. LDP Assessment Results, 4-Story SCBF RSA, BSE-1 LS




Figure 3-32. LDP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-1

### 3.2.2.1.2.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-33 and Figure 3-34 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LDP at the BSE-2 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-35 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the CP BPL acceptance criteria. Figure 3-33(b) and Figure 3-34(b) show that the frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5.




Figure 3-33. LDP Assessment Results, 4-Story SCBF ELF, BSE-2 CP




Figure 3-34. LDP Assessment Results, 4-Story SCBF RSA, BSE-2 CP




Figure 3-35. LDP Assessment Results, Compression in Ext. Columns, 4-Story SCBF, BSE-2

### 3.2.2.1.3 Nonlinear Static Procedure

In this section, the following apply:

- Table 3-11 through Table 3-13 provide the computed NSP analysis and assessment parameters in accordance with ASCE 41 §3.3.3.
- Figure 3-36 and Figure 3-37 illustrate the monotonic pushover curves for the ELF- and RSA-designed frames, respectively, and the associated pushover parameters from ASCE 41 at the BSE-2 EHL. Roof displacement is measured at the Center of Mass (CoM). A significant change in base shear is due to component strength loss of components (e.g., braces), noted in the figures. Sharp points in the curves are a result of the hysteretic model used for the braces not capturing member out-of-straightness, which would gradually soften the curves as the buckling strengths are reached. First-order and second-order responses, shown in these figures, aids in computing a physically meaningful value for  $\alpha_{P-\Delta}$  used in ASCE 41 Equation 3-17.
- Figure 3-38 and Figure 3-39 illustrate the story drift ratios in terms of the roof drift ratio.

As discussed in §3.1.3.2.1, the NSP is permitted, but requires supplemental verification using the LDP—see §3.2.2.1.2. In this case, the displacement at the maximum base shear governs  $\Delta_d$  for both the ELF- and RSA-designed frames at the BSE-2 EHL whereas the target displacement governs  $\Delta_d$  for both the ELF- and RSA-designed frames at the BSE-1 EHL. The change in  $\Delta_d$  between BSE-1 and BSE-2 adds complexity to NSP process by changing the pushover variables. Axial compression force in the exterior columns at the target displacement are shown previously in the linear assessment sections.

**Table 3-11. NSP General Information, 4-Story SCBF (kip, inch)**

Design	$T_I$	$K_I$	$\Delta_y$	$V_y$	$K_e$	$T_e$	$h$	$\Delta_{peak}$	$V_{peak}$	$W$	$C_m$	$C_0$
ELF	0.67	710.5	1.6	1104	710.5	0.67	0.94	8.2	2093.5	5172	0.85	1.36
RSA	0.72	636.2	1.6	1022	636.2	0.72	0.95	6.2	1707.1	5136	0.85	1.36

**Table 3-12. CP NSP Analysis Parameters, 4-Story SCBF BSE-2 CP (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{P-\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	1.34	5.32	1.16	1.05	9.9	1986.8	8.2	0.21	-0.04	-0.01	-0.02	18.07	OK
RSA	1.25	5.31	1.14	1.00	9.9	1557.4	6.2	0.23	-0.04	-0.01	-0.02	16.50	OK

**Table 3-13. LS NSP Analysis Parameters, 4-Story SCBF BSE-1 LS (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{P-\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	0.90	3.55	1.09	1.02	6.0	1832.7	6.0	0.23	-0.03	-0.01	-0.01	17.97	OK
RSA	0.83	3.54	1.08	1.00	6.2	1700.3	6.2	0.23	-0.04	-0.01	-0.02	16.50	OK




Figure 3-36. 4-Story SCBF ELF Pushover, BSE-2




Figure 3-37. 4-Story SCBF RSA Pushover, BSE-2




Figure 3-38. 4-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2





Figure 3-39. 4-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2

Figure 3-40 illustrates which frame columns are force-controlled for flexure for both the NSP and NDP; red circles indicate anticipated plastic hinge locations that are force-controlled for flexure at the target displacement. Figure 3-41 through Figure 3-44 illustrate the  $DCR_N$  values if greater than unity for the ELF- and RSA-designed frames at the target displacement for the LS BPL at the BSE-1 EHL and CP BPL at the BSE-2 EHL. The figures illustrate demands when the system is loaded to the left. Nearly all brace axial compression actions do not satisfy the LS or CP BPL acceptance criteria. All brace axial tension actions satisfy the LS and CP BPL acceptance criteria. Nearly all columns remain essentially elastic at the BSE-2 EHL; therefore, satisfying the force-controlled lower-bound elastic acceptance criteria where required. The hinge that developed in the base column (compression side of the frame) in the ELF-designed frame fails the force-controlled criteria at the BSE-2 EHL.



All columns are *deformation-controlled* (DC) for flexure unless indicated as *force-controlled* (FC) in figure

Column is force-controlled for flexure if  $P > 0.5 \times P_{CL}$ , where  $P$  is computed at the target displacement for the NSP and as the maximum value for the NDP

**Figure 3-40. Schematic of Flexural Actions in Columns, 4-Story SCBF (NSP and NDP)**




Figure 3-41. NSP Assessment Results, 4-Story SCBF ELF, BSE-1 LS (+push to left)




Figure 3-42. NSP Assessment Results, 4-Story SCBF RSA, BSE-1 LS (+push to left)




Figure 3-43. NSP Assessment Results, 4-Story SCBF ELF, BSE-2 CP (+push to left)





Figure 3-44. NSP Assessment Results, 4-Story SCBF RSA, BSE-2 CP (+push to left)

### 3.2.2.1.4 Nonlinear Dynamic Procedure


The earthquake record set used to assess the N-S direction of MC4 is shown in Appendix A. For the ELF and RSA design, the analysis successfully completed for all 14 records at the BSE-1 and BSE-2 EHL. Maximum axial compression force in the exterior column lines from the record set are shown previously in the linear assessment sections.

Figure 3-45 through Figure 3-48 show the performance of the HSS braces at the BSE-1 (LS BPL) and BSE-2 (CP BPL) for the ELF- and RSA-designed frames, respectively. The results from the LSP, LDP, and NSP (loaded to the left) are included in the figures. Comparison discussions between the various procedures are addressed subsequently. As is evident from the figures, the ELF-designed frame does not perform significantly better than the RSA-designed frame—a corollary of the two frame designs being nearly the same. Both designs have braces that do not satisfy the LS or CP BPL acceptance criteria. All braces except those in the second story approach being classified as ‘slender’ by ASCE 41 Table 5-7.


The average ratio of secondary to primary component acceptance criteria for all HSS sections with the configuration in this frame is 1.25 for the CP SPL (1.43 for the LS SPL). The figures for the ELF- and RSA-designed frame illustrate that this value is exceeded in a number of stories at the BSE-1 EHL and BSE-2 EHL. This highlights the rapid analytical progression towards a collapse state when several components are strained past the deformation associated with their peak strength—see §3.1.4.2. However, brace fracture is not explicitly modeled in the analysis. Therefore, these frames would not solely rely upon the resulting moment frame after brace fracture for collapse resistance—see NIST GCR 10-917-8. ASCE 41 does not provide acceptance criteria for beam-to-column connections once a brace fractures.




**Figure 3-45. NDP Assessment Results, Brace Struts, 4-Story SCBF ELF, BSE-1 LS**



**Figure 3-46. NDP Assessment Results, Brace Struts, 4-Story SCBF RSA, BSE-1 LS**



**Figure 3-47. NDP Assessment Results, Brace Struts, 4-Story SCBF ELF, BSE-2 CP**



**Figure 3-48. NDP Assessment Results, Brace Struts, 4-Story SCBF RSA, BSE-2 CP**

Figure 3-40 (see NSP section) illustrates which flexural actions in the frame columns are force-controlled for both the NSP and NDP. Figure 3-49 and Figure 3-50 show the curvature ductility demand of the column hinges (i.e., section strength) at the BSE-2 EHL—see discussion on column hinge modeling in §3.2.1.2.

Figure 3-51 and Figure 3-52 show the elastic member strength interaction results at the BSE-2 EHL—see discussion on column strength modeling in §3.2.1.2. Column hinges at the base above the brace connection experience inelastic strain demands (yield corresponds to a  $DCR_N = 1$  in the figures). However, the deformation demands are considerably lower than the primary CP acceptance criteria for a ‘column’. This effect is a consequence of modeling rotationally restrained base connections, which more closely characterizes how the base connection is detailed in these buildings than assuming rotationally unrestrained connections as is commonly done in practice.

Still, the exterior base columns in both the ELF- and RSA-designed frames are force-controlled for flexure and therefore do not satisfy the lower-bound elastic acceptance criteria at the BSE-2. There is indication that other plastic hinges may develop in the columns below stories with highly strained braced. Whether or not this is an effect of the column-to-base connection model is not well understood. As illustrated in Figure 3-40, these columns would be force-controlled for flexure because of high axial load ratios. It does not seem justified that force-controlled response be triggered by  $P_{UF} / P_{CL}$  in lieu of  $P_{UF} / P_{ye}$ , more so when  $P_{CL}$  is governed by any buckling mode other than in-plane flexural buckling. First,  $P_{CL}$  can be controlled by flexural buckling about the weak-axis, which is a failure mode that should be treated separately from the formation of a plastic hinge from in-plane bending. Second,  $P_{CL}$  varies based on the length of a member whereas  $P_{ye}$  is constant. As a side note, if  $P_{UF} / P_{ye}$  were used as the axial force ratio trigger, as was done in FEMA 273, base column flexural action would not be classified as force-controlled. ASCE 41-13 took the first step in resolving this inconsistency by permitting  $P_{UF} / P_{CL}$  to be computed in the plane of bending.

The  $DCR_N$  results for the LSP and LDP are based on an interaction equation and not from  $M_{UD} / m \times M_{CE}$ , or  $M_{UF} / M_{CL}$ , which would be a more physically consistent metric for comparison against the results from the nonlinear assessment procedures. Nonetheless, the linear results are generally not applicable here because the columns are deformation-controlled for flexure in the linear assessment procedures. Though there is a fundamental difference in how the  $DCR_N$  is computed for the linear and nonlinear procedures, the linear assessment results show similar distributions of demands and location of potential performance concerns.




Figure 3-49. NDP Assessment Results, Column Hinges, 4-Story SCBF ELF, BSE-2 Yield




Figure 3-50. NDP Assessment Results, Column Hinges, 4-Story SCBF RSA, BSE-2 Yield





Figure 3-51. NDP Assessment Results, Column Members, 4-Story SCBF ELF, BSE-2



**Figure 3-52. NDP Assessment Results, Column Members, 4-Story SCBF RSA, BSE-2**

### 3.2.2.2 Eight-Story Concentrically Braced Frame

#### 3.2.2.2.1 Linear Static Procedure

##### 3.2.2.2.1.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-53 and Figure 3-54 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m\kappa$ .
- Figure 3-55 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-53(b) and Figure 3-54(b) show that some frame columns particularly in the lower stories of the frame are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces a lower-bound estimate for  $P_{UF}$  for the LS SPL as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-55.




Figure 3-53. LSP Assessment Results – 8-Story SCBF ELF – BSE-1 – LS





Figure 3-54. LSP Assessment Results, 8-Story SCBF RSA, BSE-1 LS



**Figure 3-55. LSP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-1**

### 3.2.2.2.1.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-56 and Figure 3-57 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-58 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All brace actions satisfy the CP BPL acceptance criteria. Figure 3-56(b) and Figure 3-57(b) show that most frame columns particularly in the lower stories of the frame are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5.

Base columns do not satisfy the CP BPL acceptance criteria using the interaction equation because they are designated as force-controlled for flexure because of  $P_{UF}$  exceeding  $0.5 \times P_{CL}$  (see discussion in §3.2.2.1.4). High flexural demand at the base of the frame is a consequence of modeling rotationally restrained base connections, which more closely characterizes how the base connection is detailed in these buildings than assuming rotationally unrestrained connections as is commonly done in practice. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces an upper-bound estimate for  $P_{UF}$  for the CP SPL as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-58. The axial load changes because  $J$  is essentially unchanged between the BSE-1 and BSE-2 analyses—contrary to the capacity design philosophy.




Figure 3-56. LSP Assessment Results, 8-Story SCBF ELF, BSE-2 CP





Figure 3-57. LSP Assessment Results, 8-Story SCBF RSA, BSE-2 CP



**Figure 3-58. LSP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-2**

3.2.2.2.2 Linear Dynamic Procedure

3.2.2.2.2.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-59 and Figure 3-60 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-2 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-61 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-59(b) and Figure 3-60(b) show that the frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces the least conservative  $P_{UF}$  as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-61.




Figure 3-59. LDP Assessment Results, 8-Story SCBF ELF, BSE-1 LS





Figure 3-60. LDP Assessment Results, 8-Story SCBF RSA, BSE-1 LS



**Figure 3-61. LDP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-1**

### 3.2.2.2.2.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-62 and Figure 3-63 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-64 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the CP BPL acceptance criteria. Figure 3-62(b) and Figure 3-63(b) show that most frame columns particularly in the lower stories of the frame are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces the least conservative  $P_{UF}$  as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-64.




Figure 3-62. LDP Assessment Results, 8-Story SCBF ELF, BSE-2 CP





Figure 3-63. LDP Assessment Results, 8-Story SCBF RSA, BSE-2 CP



**Figure 3-64. LDP Assessment Results, Compression in Ext. Columns, 8-Story SCBF, BSE-2**

### 3.2.2.2.3 Nonlinear Static Procedure

In this section, the following apply:

- Table 3-14 through Table 3-16 provide the computed NSP analysis and assessment parameters in accordance with ASCE 41 §3.3.3.
- Figure 3-65 and Figure 3-66 illustrate the monotonic pushover curves for the ELF- and RSA-designed frames, respectively, and the associated pushover parameters from ASCE 41 at the BSE-2 EHL. Roof displacement is measured at the Center of Mass (CoM). A significant change in base shear is due to component strength loss of components (e.g., braces), notated in the figures. Sharp points in the curves are a result of the hysteretic model used for the braces not capturing member out-of-straightness, which would gradually soften the curves as the buckling strengths are reached. First-order and second-order responses, shown in these figures, aids in computing a physically meaningful value for  $\alpha_{P-\Delta}$  used in ASCE 41 Equation 3-17.
- Figure 3-67 and Figure 3-68 illustrate the story drift ratios in terms of the roof drift ratio.

As discussed in §3.1.3.2.1, the NSP is permitted, but requires supplemental verification using the LDP—see §3.2.2.2.2. In this case, the displacement at the maximum base shear governs  $\Delta_d$  for the ELF-designed frame for both the BSE-1 and BSE-2 EHLs and the RSA-designed frame for the BSE-2 EHL, whereas the target displacement governs the RSA-designed frame for the BSE-1 EHL. The change in  $\Delta_d$  between BSE-1 and BSE-2 adds complexity to NSP process by changing the pushover variables. Further, when  $\Delta_d$  is governed by the target displacement, the system can have an increased  $R_{max}$ . Axial compression force in the exterior columns at the target displacement are shown previously in the linear assessment sections. Results indicate that the NSP generally results in a lower estimate of the axial force demands compared to the other methods used in this study. This is partly because the fundamental mode-based lateral force distribution

does not adequately capture higher mode effects. Also, the target displacement at the roof computed based on fundamental mode properties may underestimate the story demands in the upper stories.

**Table 3-14. NSP General Information, 8-Story SCBF (kips, inch)**


Design	$T_1$	$K_1$	$\Delta_y$	$V_y$	$K_e$	$T_e$	$h$	$\Delta_{peak}$	$V_{peak}$	$W$	$C_m$	$C_0$
ELF	1.40	278.8	7.5	2098	279.1	1.40	1.05	11.8	2527.0	10618	1.00	1.41
RSA	1.45	251.9	7.1	1758	249.1	1.46	1.06	13.0	2068.4	10527	1.00	1.40

**Table 3-15. CP NSP Analysis Parameters, 8-Story SCBF BSE-2 CP (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{p,\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	0.69	3.50	1.00	1.00	18.7	2214.9	11.8	0.36	-0.09	-0.03	-0.04	8.93	OK
RSA	0.64	3.85	1.00	1.00	18.8	1986.1	13.0	0.21	-0.10	-0.03	-0.04	8.61	OK

**Table 3-16. LS NSP Analysis Parameters, 8-Story SCBF BSE-1 LS (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{p,\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	0.46	2.34	1.00	1.00	12.5	2219.9	11.8	0.36	-0.09	-0.03	-0.04	8.93	OK
RSA	0.43	2.57	1.00	1.00	12.5	2054.8	12.5	0.22	-0.10	-0.03	-0.04	8.62	OK



**Figure 3-65. 8-Story SCBF ELF Pushover, BSE-2**




Figure 3-66. 8-Story SCBF RSA Pushover, BSE-2

Figure 3-69 illustrates which frame columns are force-controlled for flexure for both the NSP and NDP; red circles indicate anticipated plastic hinge locations that are force-controlled for flexure at the target displacement. Similar to results from the linear procedures, exterior columns below the mid-height of the frame are force-controlled for flexure.

Figure 3-70 through Figure 3-73 illustrate the  $DCR_N$  values if greater than unity for the ELF- and RSA-designed frames at the target displacement for the LS BPL at the BSE-1 EHL and CP BPL at the BSE-2 EHL. The figures illustrate demands when the system is loaded to the left. Nearly all brace axial compression actions satisfy the LS and CP BPL acceptance criteria. All brace axial tension actions satisfy the LS and CP BPL acceptance criteria. Nearly all columns remain essentially elastic at the BSE-2 EHL, therefore satisfying the force-controlled lower-bound elastic acceptance criteria where required. The hinge that developed in the base column (compression side of the frame) in the ELF-designed frame barely fails the force-controlled criteria in compression at the BSE-2 EHL.




Figure 3-67. 8-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2





Figure 3-68. 8-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2



All columns are *deformation-controlled* (DC) for flexure unless indicated as *force-controlled* (FC) in figure

Column is force-controlled for flexure if  $P > 0.5 \times P_{CL}$ , where  $P$  is computed at the target displacement for the NSP and as the maximum value for the NDP

**Figure 3-69. Schematic of flexural actions in columns, 08-Story SCBF (NSP and NDP)**




Figure 3-70. NSP Assessment Results, 8-Story SCBF ELF, BSE-1 LS (+push to left)




Figure 3-71. NSP Assessment Results, 8-Story SCBF RSA, BSE-1 LS (+push to left)




Figure 3-72. NSP Assessment Results, 8-Story SCBF ELF, BSE-2 CP (+push to left)




Figure 3-73. NSP Assessment Results, 8-Story SCBF RSA, BSE-2 CP (+push to left)

3.2.2.2.4 Nonlinear Dynamic Procedure

The earthquake record set used to assess the N-S direction of MC8 is shown in Appendix A. For the ELF and RSA design, the analysis successfully completed for all 14 records at the BSE-1 and BSE-2 EHL. Maximum axial compression force in the exterior column lines from the record set are shown previously in the linear assessment sections.

Figure 3-74 through Figure 3-77 show the performance of the HSS braces at the BSE-1 (LS BPL) and BSE-2 (CP BPL) for the ELF- and RSA-designed frames, respectively. The results from the LSP, LDP, and NSP (loaded to the left) are included in the figures. Comparison discussions between the various procedures are addressed subsequently. As is evident from the figures, the ELF-designed frame does not perform significantly better than the RSA-designed frame—a corollary of the two frame designs being nearly the same. Both designs have braces (lower story of the two-story X bracing) that do not satisfy the LS or CP BPL acceptance criteria. All braces except those in the second story approach being classified as ‘slender’ by ASCE 41 Table 5-7.

The average ratio of secondary to primary component acceptance criteria for all HSS sections with the configuration in this frame is 1.25 for the CP SPL (1.43 for the LS SPL). The figures for the ELF- and RSA-designed frame illustrate that this value is exceeded in a number of stories at the BSE-1 EHL and BSE-2 EHL. This highlights the rapid analytical progression towards a collapsed state when several components are strained past the deformation associated with their peak strength—see §3.1.4.2. However, brace fracture is not explicitly modeled in the analysis—see §3.2.2.1.3 for more information.




Figure 3-74. NDP Assessment Results, Brace Struts, 8-Story SCBF ELF, BSE-1 LS




Figure 3-75. NDP Assessment Results, Brace Struts, 8-Story SCBF RSA, BSE-1 LS





Figure 3-76. NDP Assessment Results, Brace Struts, 8-Story SCBF ELF, BSE-2 CP



**Figure 3-77. NDP Assessment Results, Brace Struts, 8-Story SCBF RSA, BSE-2 CP**

Figure 3-69 (see NSP section) illustrates which flexural actions in the frame columns are force-controlled for both the NSP and NDP. Figure 3-78 and Figure 3-79 show the curvature ductility demand on the column hinges (i.e., section strength) at the BSE-2 EHL—see discussion on column hinge modeling in §3.2.1.2. Figure 3-80 and Figure 3-81 show the elastic member strength interaction results at the BSE-2 EHL—see discussion on column strength modeling in §3.2.1.2.

Column hinges at the base above the brace connection experience inelastic strain demands (yield corresponds to a  $DCR_N = 1$  in the figures) using the mean response. In contrast to the mean response, the median response indicates better performance because it is less influenced by large deformations resulting from component strength loss potentially resulting in collapse of the system. Consequently, the median is potentially a more stable performance metric when analyzing a large number of ground motion records, but should be restrained relative to a mean value. However, the deformation demands are considerably lower than the primary CP acceptance criteria for a ‘column’. This effect is a consequence of modeling rotationally restrained base connections, which more closely characterizes how the base connection is detailed in these buildings than assuming rotationally unrestrained connections as is commonly done in practice.

Still, the exterior base columns in both the ELF- and RSA-designed frames are force-controlled for flexure and therefore do not satisfy the lower-bound elastic acceptance criteria at the BSE-2—see §3.2.2.1.4 for additional information and discussion.

The  $DCR_N$  results for the LSP and LDP are based on an interaction equation and not from  $M_{UD} / m \times M_{CE}$ , or  $M_{UF} / M_{CL}$ , which would be a more physically consistent metric for comparison against the results from the nonlinear assessment procedures. Nonetheless, the linear results are generally applicable here because most of the exterior frame columns are force-controlled for flexure in the linear assessment procedures. Though there is a fundamental difference in how the  $DCR_N$  is computed for the linear and nonlinear procedures, the

linear assessment results show similar distributions of demands and location of potential performance concerns.




Figure 3-78. NDP Assessment Results, Column Hinges, 8-Story SCBF ELF, BSE-2 Yield






Figure 3-79. NDP Assessment Results, Column Hinges, 8-Story SCBF RSA, BSE-2 Yield



**Figure 3-80. NDP Assessment Results, Column Members, 8-Story SCBF ELF, BSE-2**



**Figure 3-81. NDP Assessment Results, Column Members, 8-Story SCBF RSA, BSE-2**

### 3.2.2.3 Sixteen-Story Concentrically Braced Frame

#### 3.2.2.3.1 Linear Static Procedure

##### 3.2.2.3.1.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-82 and Figure 3-83 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-84 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-82(b) and Figure 3-83(b) show that nearly all exterior frame columns are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces a lower-bound estimate for  $P_{UF}$  for the LS SPL as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-84.




Figure 3-82. LSP Assessment Results, 16-Story SCBF ELF, BSE-1 LS





Figure 3-83. LSP Assessment Results, 16-Story SCBF RSA, BSE-1 LS



**Figure 3-84. LSP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-1**

### 3.2.2.3.1.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-85 and Figure 3-86 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LSP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-87 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All brace actions satisfy the CP BPL acceptance criteria. Figure 3-85(b) and Figure 3-86(b) show that nearly all exterior frame columns are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces an upper-bound estimate for  $P_{UF}$  for the LS SPL as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-87. The axial load,  $P_{UF}$ , in Figure 3-84 and Figure 3-87 changes because  $J$  is essentially unchanged between the BSE-1 and BSE-2 analyses—contrary to the capacity design philosophy (compare  $P_{UF}$  to  $P_{u, Capacity Design}$  from AISC 341).

Several exterior frame columns in the ELF- and RSA-designed frames do not satisfy the CP BPL acceptance criteria using the interaction equation because they are designated as force-controlled for flexure since  $P_{UF}$  exceeds  $0.5 \times P_{CL}$ —see §3.2.2.1.4 for additional information and discussion. High flexural demand at the base of the frame is a consequence of modeling rotationally restrained base connections, which more closely characterizes how the base connection is detailed in these buildings than assuming rotationally unrestrained connections as is commonly done in practice.




Figure 3-85. LSP Assessment Results, 16-Story SCBF ELF, BSE-2 CP




Figure 3-86. LSP Assessment Results, 16-Story SCBF RSA, BSE-2 CP




Figure 3-87. LSP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-2

### 3.2.2.3.2 Linear Dynamic Procedure

#### 3.2.2.3.2.1 BSE-1 Earthquake Hazard Level (LS BPL)

In this section, the following apply:

- Figure 3-88 and Figure 3-89 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LDP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-90 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the LS BPL acceptance criteria. Figure 3-88(b) and Figure 3-89 (b) show that nearly all frame columns are deformation-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces the least conservative  $P_{UF}$  as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-90.




Figure 3-88. LDP Assessment Results, 16-Story SCBF ELF, BSE-1 LS




Figure 3-89. LDP Assessment Results, 16-Story SCBF RSA, BSE-1 LS




Figure 3-90. LDP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-1

### 3.2.2.3.2.2 BSE-2 Earthquake Hazard Level (CP BPL)

In this section, the following apply:

- Figure 3-91 and Figure 3-92 provide the  $DCR_N$  and load-dependent  $m$ -factor values for the ELF and RSA designs, respectively, for the LDP at the BSE-1 EHL. In these figures,  $DCR_N$  values greater than unity are highlighted in red and underlined.  $DCR$  values, as defined by ASCE 41, can be obtained by multiplying  $DCR_N$  by  $m$  and  $\kappa$ , see Eq. 3-6.
- Figure 3-93 provides the maximum axial compression demands,  $P_{UF}$ , in the exterior column lines for various analysis methods and the column capacity,  $P_{CL}$ .

All component actions satisfy the CP BPL acceptance criteria. Figure 3-91(b) and Figure 3-92 (b) show that nearly all exterior frame columns are force-controlled for flexure and the braces tend toward a ‘slender’ classification in ASCE 41 Table 5-5. As discussed previously in §3.2.2,  $P_{UF}$  is determined by taking  $J$  (ASCE 41 §3.4.2.1.2-2) as the minimum  $DCR$  of the component(s) delivering force to the column, but not less than 2.0. This approach produces the least conservative  $P_{UF}$  as compared to AISC 341 SCBF column design requirements, as shown in Figure 3-93.




Figure 3-91. LDP Assessment Results, 16-Story SCBF ELF, BSE-2 CP




Figure 3-92. LDP Assessment Results, 16-Story SCBF RSA, BSE-2 CP




Figure 3-93. LDP Assessment Results, Compression in Ext. Columns, 16-Story SCBF, BSE-2

### 3.2.2.3.3 Nonlinear Static Procedure

In this section, the following apply:

- Table 3-17 through Table 3-19 provide the computed NSP analysis and assessment parameters in accordance with ASCE 41 §3.3.3.
- Figure 3-94 and Figure 3-95 illustrate the monotonic pushover curves for the ELF- and RSA-designed frames, respectively, and the associated pushover parameters from ASCE 41 at the BSE-2 EHL. Roof displacement is measured at the Center of Mass (CoM). A significant change in base shear is due to component strength loss (e.g., braces), notated in the figures. Sharp points in the curves are a result of the hysteretic model used for the braces not capturing member out-of-straightness, which would gradually soften the curves as the buckling strengths are reached. First-order and second-order responses, shown in these figures, aids in computing a physically meaningful value for  $\alpha_{P-\Delta}$  used in ASCE 41 Equation 3-17.
- Figure 3-96 and Figure 3-97 illustrate the story drift ratios in terms of the roof drift ratio.

As discussed in §3.1.3.2.1, the NSP is permitted, but requires supplemental verification using the LDP—see §3.2.2.3.2. In this case, the displacement at the maximum base shear governs  $\Delta_d$  for the ELF-designed frame for both the BSE-1 and BSE-2 EHLs and the RSA-designed frame for BSE-2 EHL, whereas the target displacement governs the RSA-designed frame for BSE-1 EHL. The change in  $\Delta_d$  between BSE-1 and BSE-2 adds complexity to NSP process by changing the pushover variables. Further, when  $\Delta_d$  is governed by the target displacement, the system can have an increased  $R_{max}$ . Axial compression force in the exterior columns at the target displacement are shown previously in the linear assessment sections. Results indicate that the NSP generally results in a lower estimate of the axial force demands compared to the other methods used in this study. This is partly because the fundamental mode-based lateral force distribution

does not adequately capture higher mode effects. Also, the target displacement at the roof computed based on fundamental mode properties may underestimate the story demands in the upper stories.

**Table 3-17. NSP General Information, 16-Story SCBF (kip, inch)**


Design	$T_1$	$K_1$	$\Delta_y$	$V_y$	$K_e$	$T_e$	$h$	$\Delta_{peak}$	$V_{peak}$	$W$	$C_m$	$C_0$
ELF	2.03	258.5	9.3	2401	258.6	2.02	1.11	16.8	3363.0	21782	1.00	1.44
RSA	2.08	243.2	9.4	2292	243.5	2.08	1.11	21.5	2494.9	21649	1.00	1.28

**Table 3-18. CP NSP Analysis Parameters, 16-Story SCBF BSE-2 CP (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{p,\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	0.45	4.08	1.00	1.00	26.0	2858.7	16.8	0.50	-0.22	-0.03	-0.07	6.59	OK
RSA	0.45	4.25	1.00	1.00	24.2	2490.7	21.5	0.07	-0.14	-0.03	-0.05	8.62	OK

**Table 3-19. LS NSP Analysis Parameters, 16-Story SCBF BSE-1 LS (kip, inch)**

Design	$S_a$	$R$	$C_1$	$C_2$	$\Delta_t$	$V_t$	$\Delta_d$	$\alpha_1$	$\alpha_2$	$\alpha_{p,\Delta}$	$\alpha_e$	$R_{max}$	$R \leq R_{max}$
ELF	0.30	2.72	1.00	1.00	17.4	3054.8	16.8	0.50	-0.22	-0.03	-0.07	6.59	OK
RSA	0.30	2.83	1.00	1.00	16.2	2466.9	16.2	0.11	-0.12	-0.03	-0.05	8.71	OK



**Figure 3-94. 16-Story SCBF ELF Pushover, BSE-2**




Figure 3-95. 16-Story SCBF RSA Pushover, BSE-2




Figure 3-96. 16-Story SCBF ELF Pushover – Story Drift Ratios – BSE-2





Figure 3-97. 16-Story SCBF RSA Pushover – Story Drift Ratios – BSE-2

Figure 3-98 illustrates which frame columns are force-controlled for flexure for both the NSP and NDP; red circles indicate anticipated plastic hinge locations that are force-controlled for flexure at the target displacement. Similar to results from the linear procedures, most exterior frame columns are force-controlled for flexure.

Figure 3-99 through Figure 3-102 illustrate the  $DCR_N$  values if greater than unity for the ELF- and RSA-designed frames at the target displacement for the LS BPL at the BSE-1 EHL and CP BPL at the BSE-2 EHL. The figures illustrate demands when the system is loaded to the left. Nearly all brace axial compression actions satisfy the LS and CP BPL acceptance criteria. All brace axial tension actions satisfy the LS and CP BPL acceptance criteria. All columns remain essentially elastic at the BSE-2 EHL, therefore satisfying the force-controlled lower-bound elastic acceptance criteria where required.



All columns are *deformation-controlled* (DC) for flexure unless indicated as *force-controlled* (FC) in figure

Column is force-controlled for flexure if  $P > 0.5 \times P_{CL}$ , where  $P$  is computed at the target displacement for the NSP and as the maximum value for the NDP

Figure 3-98. Schematic of flexural actions in columns, 16-Story SCBF (NSP and NDP)




Figure 3-99. NSP Assessment Results, 16-Story SCBF ELF, BSE-1 LS (+push to left)




Figure 3-100. NSP Assessment Results, 16-Story SCBF RSA, BSE-1 LS (+push to left)




Figure 3-101. NSP Assessment Results, 16-Story SCBF ELF, BSE-2 CP (+push to left)





Figure 3-102. NSP Assessment Results, 16-Story SCBF RSA, BSE-2 CP (+push to left)

### 3.2.2.3.4 Nonlinear Dynamic Procedure


The earthquake record set used to assess the N-S direction of MC16 is shown in Appendix A. For the ELF and RSA design, the analysis successfully completed for all 14 records at the BSE-1 and BSE-2 EHL. Maximum axial compression force in the exterior column lines from the record set are shown previously in the linear assessment sections.

Figure 3-103 through Figure 3-106 show the performance of the HSS braces at the BSE-1 (LS BPL) and BSE-2 (CP BPL) for the ELF- and RSA-designed frames, respectively. The results from the LSP, LDP, and NSP (loaded to the left) are included in the figures. Comparison discussions between the various procedures are addressed subsequently. As is evident from the figures, the ELF-designed frame does not perform significantly better than the RSA-designed frame—a corollary of the two frame designs being nearly the same. Both designs have braces (lower story of the two-story X bracing) that do not satisfy the LS or CP BPL acceptance criteria. All braces except those in the second story approach being classified as ‘slender’ by ASCE 41 Table 5-7.


The average ratio of secondary to primary component acceptance criteria for all HSS sections with the configuration in this frame is 1.25 for the CP SPL (1.43 for the LS SPL). The figures for the ELF- and RSA-designed frame illustrate that this value is exceeded in a number of stories at the BSE-1 EHL and BSE-2 EHL. This highlights the rapid analytical progression towards a collapsed state when several components are strained past the deformation associated with their peak strength—see §3.1.4.2. However, brace fracture is not explicitly modeled in the analysis—see §3.2.2.1.3 for more information.




**Figure 3-103. NDP Assessment Results, Brace Struts, 16-Story SCBF ELF, BSE-1 LS**



**Figure 3-104. NDP Assessment Results, Brace Struts, 16-Story SCBF RSA, BSE-1 LS**



**Figure 3-105. NDP Assessment Results, Brace Struts, 16-Story SCBF ELF, BSE-2 CP**



**Figure 3-106. NDP Assessment Results, Brace Struts, 16-Story SCBF RSA, BSE-2 CP**

Figure 3-98 (see NSP section) illustrates which flexural actions in the frame columns are force-controlled for both the NSP and NDP. Figure 3-107 and Figure 3-108 show the curvature ductility demand on the column hinges (i.e., section strength) at the BSE-2 EHL—see discussion on column hinge modeling in §3.2.1.2. Figure 3-109 and Figure 3-110 show the elastic member strength interaction results at the BSE-2 EHL—see discussion on column strength modeling in §3.2.1.2. These figures illustrate that linear analysis has difficulty assessing columns that support components that experience significant strength loss quickly as common for a brace in compression.

Column hinges at the base above the brace connection experience inelastic strain demands (yield corresponds to a  $DCR_N = 1$  in the figures) using the mean response. In contrast to the mean response, the median response indicates better performance because it is less influenced by large deformations resulting from component strength loss potentially resulting in collapse of the system. Consequently, the median is potentially a more stable performance metric when analyzing a large number of ground motion records, but should be restrained relative to a mean value. However, the deformation demands are considerably lower than the primary CP acceptance criteria for a ‘column’. This effect is a consequence of modeling rotationally restrained base connections, which more closely characterizes how the base connection is detailed in these buildings than assuming rotationally unrestrained connections as is commonly done in practice.

Still, the exterior base columns in both the ELF- and RSA-designed frames are force-controlled for flexure and therefore do not satisfy the lower-bound elastic acceptance criteria at the BSE-2—see §3.2.2.1.4 for additional information and discussion.

The  $DCR_N$  results for the LSP and LDP are based on an interaction equation and not from  $M_{UD} / m \times M_{CE}$ , or  $M_{UF} / M_{CL}$ , which would be a more physically consistent metric for comparison against the results from the nonlinear assessment procedures. Nonetheless, the linear results are generally not applicable here because most of the exterior frame columns are force-controlled for flexure in the linear assessment procedures.

Though there is a fundamental difference in how the  $DCR_N$  is computed for the linear and nonlinear procedures, the linear assessment results show similar distributions of demands and location of potential performance concerns.




Figure 3-107. NDP Assessment Results, Column Hinges, 16-Story SCBF ELF, BSE-2 Yield






Figure 3-108. NDP Assessment Results, Column Hinges, 16-Story SCBF RSA, BSE-2 Yield



(NDP = max of either axis, LSP / LDP = equations from ASCE 41)

**Figure 3-109. NDP Assessment Results, Column Members, 16-Story SCBF ELF, BSE-2**



(NDP = max of either axis, LSP / LDP = equations from ASCE 41)

**Figure 3-110. NDP Assessment Results, Column Members, 16-Story SCBF RSA, BSE-2**

### 3.2.3 Seismic Assessment Discussion

The discussion in this section focuses on the following component design actions:

- Brace axial force (compression and tension)<sup>23</sup>
- Beam and column flexure within anticipated plastic hinge zones (section strength)
- Column axial-moment interaction strength (e.g., member strength)

ASCE 41 requires all frame components that do not satisfy the acceptance criteria to be retrofitted or replaced, even if only a small percentage of the total components fail the criteria (see ASCE 41 §5.5.2.5). Therefore, a building can only satisfy a selected BPL when all structural components satisfy the corresponding SPL. Building behavior is rarely governed by the response of a single component, with the one notable exception being collapse resulting from failure of a column. It can be argued that a shortcoming of ASCE 41 is the focus on component performance to ensure that all elements pass the evaluation, when failures of individual elements may not lead to catastrophic failure. Further, ASCE 41 requires that all brace connections are force-controlled and does not provide generalized modeling parameters of a brace connection for nonlinear analysis as done for a “ductile” beam-to-column connection in a moment frame. As such, the assessment does not allow the analysis to account for post-yield strength and deformation capacity of a gusset-type connection or for its influence on the performance of adjacent members once a brace fractures.

Design choices, constructability considerations, code requirements, nonseismic loads, analytical modeling assumptions, and other project specific requirements may add strength to critical components in a frame. Further, allocation of component strengths within the frame because of the lateral force distribution adopted in design can cause deviations of the component strengths from one story to another. Thus, capturing all possible permutations, in essence, would create an infinitely large design space. Nonetheless, the change in component strengths can significantly influence the  $DCR_N$  values obtained from the ASCE 41 assessments.

#### 3.2.3.1 Linear Assessment Procedures

The following discusses the analytical results for the noted components from the linear procedures for each archetype building.

##### 3.2.3.1.1 Brace Members

Table 3-20 provides a summary of the performance of the brace members for each linear assessment procedure and each BPL. Brace members consistently satisfy the performance criteria for the LS and CP BPL for both linear procedures.

---

<sup>23</sup> Brace connections to adjacent members are force-controlled per ASCE 41 §5.5.2.4.1.

**Table 3-20. Performance Summary of Brace Members (BM) per Frame, Linear Procedures**

Archetype	Design	LSP		LDP	
		LS	CP	LS	CP
4-Story	ELF	All BM Pass	All BM Pass	All BM Pass	All BM Pass
	RSA	All BM Pass	All BM Pass	All BM Pass	All BM Pass
8-Story	ELF	All BM Pass	All BM Pass	All BM Pass	All BM Pass
	RSA	All BM Pass	All BM Pass	All BM Pass	All BM Pass
16-Story	ELF	All BM Pass	All BM Pass	All BM Pass	All BM Pass
	RSA	All BM Pass	All BM Pass	All BM Pass	All BM Pass

As a side note, Table 3-21 summarizes the effects of design (AISC 360) and assessment (ASCE 41) provisions on the  $DCR_N$  for a brace member at  $\frac{2}{3} \times MCE_R$  for the LS BPL. On the component capacity side, the axial compression strength prescribed in ASCE 41,  $P_{CE}$ , and AISC 360,  $P_n$ , have the same underlying equation; differences arise when using nominal versus expected material properties and a strength reduction factor,  $\phi_c = 0.9$ , resulting in a capacity ratio (ASCE 41 / AISC 360) ranging from 1.2 to 1.4 depending on  $KL / r$  for the axis of buckling. On the component demand side, assuming an eigenvalue analysis is conducted, ASCE 41 allows the use of the period determined from analysis,  $T_{analysis}$ , whereas ASCE 7 will limit this period to  $C_u T_a$  when greater than. If this limit is triggered, the demand in the braces will generally increase for design resulting in a demand ratio (ASCE 41 / ASCE 7) less than unity. Additionally, ASCE 41 effectively divides the demand by  $m$  while ASCE 7 divides the elastic demand by  $R (= 6$  for an SCBF). The  $m$ -factor ranges from 4.26 to 4.88 (see ASCE 41 Table 5-5) because HSS braces with slenderness values in the “inelastic” buckling range were considered in this discussion. Thus, for a brace member designed per ASCE 7 and its referenced standards whose nominal strength exactly equals the demand from ASCE 7, the corresponding  $DCR_N$  for the linear assessment will be less than or equal to 1.03, as illustrated in Figure 3-111. This value increases to 1.09 for the CP SPL at the BSE-2.

**Table 3-21. Effect of Design and Assessment Provisions on  $DCR_N$  of a Brace – LS SPL at the BSE-1 EHL**

	Demand		Capacity	Effect on $DCR_N$
a) ASCE 41	$S_a$ at $T = T_{analysis}$	$1/m = 1/(4.26 \text{ to } 4.88)$	$P_{CE} = \left[ 0.658^{(F_y/F_c)} \right] F_y A_g$	$DCR_N = \frac{(\# \leq 1.0)(1.23 \text{ to } 1.41)}{(1.19 \text{ to } 1.38)}$
b) ASCE 7 and AISC 341	$S_a$ at $T = \min(T_{analysis}, C_u T_a)$	$1/R = 1/6$	$\phi_c P_n = 0.9 \left[ 0.658^{(F_y/F_c)} \right] F_y A_g$	
Ratio (a / b)	$a / b \leq 1.0$	$a / b \leq 1.23 \text{ to } 1.41$	Given: $KL/r \leq 4.71 \sqrt{E/F_y}$ $a / b \leq 1.19 \text{ to } 1.38$	$\therefore DCR_N \leq 1.03$

Assuming  $C_u T_a$  and  $T_{analysis}$  are both on the descending branch of the response spectrum (but less the  $T_L$  defined in ASCE 7), the following can be observed:

$$\frac{S_{a,ASCE\ 41}}{S_{a,ASCE\ 7}} = \frac{(S_{D1}/T_{analysis})}{(S_{D1}/C_u T_a)} = \frac{C_u T_a}{T_{analysis}} \quad (3-18)$$

As an example, the ELF-designed MC8 shows a reduction in the demand of 34 percent ( $0.99 / 1.5 = 0.66$  from Table 2-5) from that using  $C_u T_a$ . This reduction aligns well with the  $DCR_N$  values observed in the LSP results, see Figure 3-53. Inversely, if the brace exactly satisfied the ASCE 41 assessment criteria, the design demand would be equal to approximately 1.5 times the nominal design strength—clearly larger than what would be comfortably accepted in practice.




Figure 3-111. Effect of Design and Assessment Provisions on the  $DCR_N$

3.2.3.1.2 Member Cross-section Strength (flexural hinge) and Global Strength (member stability)

Table 3-22 provides a summary of the performance of the *column* members for each linear assessment procedure and each BPL. The number listed in parentheses denotes the number of failed components in the frame—shown as bolded text. Also shown in the table is the percentage of failed components compared to the total number of similar components. Recall that section strength and member strength of a column is combined into a single  $P$ - $M$  interaction equation for linear assessment procedures in ASCE 41 (see ASCE 41 Equations 5-10, 5-11, and 5-12.) Consequently, identifying an efficient retrofit option for a column can be challenging because understanding and isolating the failure mechanism of the column can be difficult.

Table 3-22. Performance Summary of Columns Members (CM) per Frame, Linear Procedures

Archetype	Design	LSP		LDP	
		LS	CP	LS	CP
4-Story	ELF	All CM Pass	All CM Pass	All CM Pass	All CM Pass
	RSA	All CM Pass	All CM Pass	All CM Pass	All CM Pass
8-Story	ELF	All CM Pass	<b>Ext CM Fail (2)</b> 13%	All CM Pass	All CM Pass
	RSA	All CM Pass	<b>Ext CM Fail (2)</b> 13%	All CM Pass	All CM Pass
16-Story	ELF	All BC Pass	<b>Ext CM Fail (6)</b> 19%	All CM Pass	All CM Pass
	RSA	All BC Pass	<b>Ext CM Fail (10)</b> 31%	All CM Pass	All CM Pass

Several columns do not satisfy the assessment criteria using the interaction equation because of high axial force and moment in the 8-story and 16-story archetype buildings, principally for the CP BPL using the

LSP. These members are all force-controlled for both axial force and flexure because  $P_{UF}$  exceeds  $0.5 \times P_{CL}$ —generally associated with weak-axis flexural buckling. As such,  $M_{UF}$  and  $M_{CL}$  are used in the interaction equation (ASCE 41 Equation 5-12). Determination of  $M_{UF}$  is subject to the same limitations as  $P_{UF}$  (see sections on assessment results). As noted previously, the force distribution used in the LSP directly contributes to the increased column forces. However, generally speaking, the estimated axial load demands in the columns are the least conservative approximations, as compared to more rigorous analysis procedures (see the axial load figures (e.g., Figure 3-64)). Nonetheless, there are many columns that pass the force-controlled assessment criteria. It is unclear whether certain upper story columns fail by member instability or section hinging because of the adopted interaction equation in ASCE 41. Additionally, it is difficult to assess column failures with interaction results slightly over 1.0 due to the uncertainties in the analysis procedures and conservatism in the assessment provisions. However, the axial load demands computed using ASCE 41 §3.4.2.1.2-2 are generally less than those determined using a capacity design approach (e.g., AISC 341 §F2.3) or the NDP.

The first floor columns consistently have the most difficulty satisfying the assessment criteria because of high axial load combined with significant flexural demand because of the fixity assigned to the column-to-base connection. ASCE 41 does not provide guidance on how to assess column-to-base connections similar to beam-to-column connections in a moment frame. In reality, it is likely that the flexural demand will not be as great (as that computed in the analysis) at large deformations because some of the fixity would be relieved because of bolt elongation, weld fracture, and/or gusset plate damage. This relief would effectively reduce some of the moment demand, reducing the likelihood of a flexural hinge being formed. However, the alternative is to model the base connection as pinned, which would not capture the rigidity of the column-to-base connection assumed in design. In this study the base connections are maintained as fixed throughout the analysis, thus being conservative on the treatment of the flexural demand.

As discussed previously, it is of debatable validity that force-controlled response be triggered with  $P_{UF} / P_{CL}$  in lieu of  $P_{UF} / P_{ye}$ , as was done in FEMA 273. The interaction equation in ASCE 41 used for the case of out-of-plane instability and in-plane flexure is also debatable; ASCE 41 would benefit from following AISC 360 in this regard (see AISC 360 §H1.3). ASCE 41 would also benefit from decoupling the single interaction curve for member stability and section strength into two separate interaction equations as done in AISC ASD Chapter N, Plastic Design (AISC 1989). Decoupling the stability and strength would provide a clearer picture of potential retrofit schemes for frame columns. Nonetheless, some member stability equations were derived from beam-columns test results where column ends did not translate relative to each other. Future research is required to justify updated interaction equations for assessment of beam-columns with ASCE 41, as well as a critical examination of the acceptance criteria in regard to experimental test results.

In addition to the above performance observations, the effects of additional strengthening of columns in design should be recognized. The columns in the 4-story frames are somewhat oversized from that required from analysis to satisfy section compactness requirements in AISC 341, and therefore, the columns efficiently satisfy the acceptance criteria, regardless of estimation of  $P_{CL}$ . All the frame columns in the 4-story frames are deformation-controlled for flexure. As a side note, there is also considerably less scatter in the axial load demands in the columns from the various approximation methods.

### 3.2.3.1.3 Summary

Table 3-23 summarizes the performance of the archetype buildings in reference to the BSO for both linear procedures. Table 3-24 provides the base shears computed with the linear assessment procedures. All frames satisfy the seismic performance objective using the LDP, but only the 4-story frames satisfy the criteria using the LSP. Column performance (primarily at the base) controls the overall assessment of the SCBF frames for the LSP. However, in this analytical context, base column failure due to flexural action (plastic hinge) in an SCBF is not necessarily detrimental to the overall structural performance unless total strength loss of adjacent braces occurs. As noted above, additional research is needed on assessment criteria for columns.

**Table 3-23. BSO Performance Summary of Archetype Buildings, Linear Procedures**

Archetype	Design	LSP			Design	LDP		
		BM	CM	Conn.		BM	CM	Conn.
4-Story	ELF	Pass	Pass	NA	ELF	Pass	Pass	NA
	RSA	Pass	Pass	NA	RSA	Pass	Pass	NA
8-Story	ELF	Pass	<b>Fail</b>	NA	ELF	Pass	Pass	NA
	RSA	Pass	<b>Fail</b>	NA	RSA	Pass	Pass	NA
16-Story	ELF	Pass	<b>Fail</b>	NA	ELF	Pass	Pass	NA
	RSA	Pass	<b>Fail</b>	NA	RSA	Pass	Pass	NA

The assessment results from the LSP and LDP illustrate that, on average, the ELF-designed SCBF performs only slightly better than the RSA-designed SCBF for all archetype buildings—a corollary of the two frame designs being nearly the same. This can be attributed to the slight increase in strength and stiffness provided to the ELF-designed frames (see Table 2-5) by differences in the ELF and RSA procedures, including associated scaling provisions, in ASCE 7. Further, section compactness requirements in AISC 341 resulted in minor variations in member sizes during design.

**Table 3-24. Summary of Base Shears, Linear Procedures (kips)**

EHL	Routine	MC4		MC8		MC16	
		ELF	RSA	ELF	RSA	ELF	RSA
BSE-1	LSP	4409	4044	4403	4196	6283	6070
	LDP	3999	3760	3654	3998	5778	5666
	Ratio	0.91	0.93	0.83	0.95	0.92	0.93
BSE-2	LSP	6614	6067	6604	6293	9425	9105
	LDP	5999	5640	5848	5697	8667	8499
	Ratio	0.91	0.93	0.89	0.91	0.92	0.93

The LDP consistently results in lower  $DCR_N$  values than the LSP for both the ELF- and RSA-designed frames for all archetype buildings, an indication that a more accurate distribution of seismic demands (based on elastic modes) is better captured in taller frames. However, assessment of the RSA-designed frame consistently illustrates inferior performance using the LSP compared to the LDP because of the variation between the distribution of seismic demands and the allocation of component strengths within the frame. This variation is not as substantial when assessing the ELF-designed frame with the LDP. Moreover, the lateral force distribution in the LSP does not capture higher modes well, leading to conservative estimates of column forces in the taller frames. This can be problematic for beam-columns due to the lower-bound estimate of compressive strength,  $P_{CL}$ .

Analytical results based on component-level performances obtained from the LDP suggest that special concentrically braced frames designed in accordance with ASCE 7 and its referenced standards can achieve the selected seismic performance objective of an existing building intended to be equivalent to a new building. Conversely, results from the LSP provide a contrary inference based on the performance of the columns, a result that can be enhanced by more mechanistically consistent column provisions and analytical modeling parameters.

### 3.2.3.2 Nonlinear Assessment Procedures

The following discusses the analytical results for the noted components from the nonlinear procedures for each archetype building.

As noted previously, the NSP is permitted for the frames but requires supplemental verification using the LDP. The following summaries for the NSP reflect results only from the NSP (see previous for the linear verification using the LDP). For the NDP, results are mainly discussed in reference to the *mean* response from the set of records except where noted otherwise.

#### 3.2.3.2.1 Brace Members

Table 3-25 provides a summary of the performance of the brace members for each nonlinear assessment procedure and each BPL. The number listed in parentheses denotes the number of failed components in the frame—shown as bolded text. Also shown in the table is the percentage of failed components compared to the total number of similar components. Contrary to the results from the linear procedures, the braces consistently do not satisfy the performance criteria for the LS and CP BPL for both nonlinear procedures. Although the median response is biased less by a collapsed state of a given frame than the mean response, the results are, in general, marginally improved for the NDP. Additionally, the NDP consistently indicates poorer performance of the braces than that given by the NSP.

**Table 3-25. Performance Summary of Brace Members (BM) per frame, Nonlinear Procedures**

Archetype	Design	NSP		NDP (based on mean response of record set)	
		LS	CP	LS	CP
4-Story	ELF	<b>BM Fail (2)</b> 25%	<b>BM Fail (3)</b> 38%	<b>BM Fail (6)</b> 75%	<b>BM Fail (7)</b> 88%
	RSA	<b>BM Fail (1)</b> 13%	<b>BM Fail (3)</b> 38%	<b>BM Fail (8)</b> 100%	<b>BM Fail (8)</b> 100%
8-Story	ELF	<b>BM Fail (1)</b> 6%	<b>BM Fail (2)</b> 13%	<b>BM Fail (4)</b> 25%	<b>BM Fail (6)</b> 38%
	RSA	<b>BM Fail (1)</b> 6%	<b>BM Fail (2)</b> 13%	<b>BM Fail (6)</b> 38%	<b>BM Fail (8)</b> 50%
16-Story	ELF	<b>BM Fail (4)</b> 6%	<b>BM Fail (8)</b> 13%	<b>BM Fail (14)</b> 22%	<b>BM Fail (17)</b> 27%
	RSA	<b>BM Fail (4)</b> 6%	<b>BM Fail (6)</b> 9%	<b>BM Fail (12)</b> 19%	<b>BM Fail (16)</b> 25%

The distribution of brace failures identified by the nonlinear procedures illustrates the effect that design choices can have on frame performance. For example, the variation in failures between alternating stories is due to maintaining the brace size over two stories. Similarly, the location of the failures indicated by the

NSP highlights variations between the force distributions used in assessment and that used for design. In reference to design, the design force distribution in the ELF and RSA procedure is potentially inadequate when frames exhibit increased higher mode participation and a high level of nonlinearity. Additional discussion regarding the NSP and NDP is provided subsequently in the summary section.

### 3.2.3.2.2 Member Cross-section Strength (flexural hinge) and Global Strength (member stability)

Table 3-26 provides a summary of the performance of the *column* hinges for each nonlinear assessment procedure for the CP BPL. The number listed in parentheses denotes the number of failed components in the frame—shown as bolded text. Also shown in the table is the percentage of failed components compared to the total number of similar components. In general, column hinges satisfy the performance criteria for the LS and CP BPL for both procedures. However, base column hinges at the exterior of the frames consistently fail the performance criteria. These failures are a corollary of the column-to-base connection assumptions adopted for analysis and the modeling parameters for *P-M* hinges in ASCE 41 (see linear discussion above for information). However, while the mean response of the record set indicates column hinging at the base, the median response does not (recall that all analyses completed).

**Table 3-26. Performance Summary of Columns Hinges (CH) per frame, Nonlinear Procedures**

Archetype	Design	NSP		NDP (based on mean response of record set)	
		LS	CP	LS	CP
4-Story	ELF	---	<b>CH Fail (2)</b> 13%	---	<b>CH Fail (2)</b> 13%
	RSA	---	All CH Pass	---	<b>CH Fail (2)</b> 13%
8-Story	ELF	---	<b>CH Fail (2)</b> 6%	---	<b>CH Fail (2)</b> 6%
	RSA	---	All CH Pass	---	<b>CH Fail (2)</b> 6%
16-Story	ELF	---	All CH Pass	---	<b>CH Fail (3)</b> 3%
	RSA	---	All CH Pass	---	<b>CH Fail (3)</b> 3%

These exterior column members that fail the criteria are force-controlled for both axial force and flexure due to  $P$  exceeding  $0.5 \times P_{CL}$  for the NSP and NDP. Still, the axial force demand,  $P_{max}$ , is from an individual record and is, therefore, biased by the behavior of the frame to that record. As such, it is difficult to capture record-to-record variability on force- and deformation-controlled response directly in the analysis for a set of ground motion records. Recall that the linear procedures also identified concerns with these columns.

Establishing the in-plane column hinge model and performance metrics as a function of the out-of-plane flexural buckling strength, when governs  $P_{CL}$ , can be problematic for wide-flange columns. More so, when the gravity load alone produces an axial force greater than  $0.2 \times P_{CL}$ . Consequently, modeling the section flexural strength of a column hinge using the section axial strength of that section would not result in a force-controlled condition. This was the approach taken in FEMA 273, the predecessor of ASCE 41. It is theoretically inconsistent to model the component strengths within the same column as a function of both  $P_{ye}$  and  $P_{CL}$ .

Table 3-27 summarizes the performance of the *column* member strength for each nonlinear assessment procedure for the CP BPL. ASCE 41 does not provide guidance on checking column member stability when using the nonlinear procedures unless the column is designated as force-controlled. It is mechanistically inconsistent to adjust material properties between section strength and member stability for a given column (i.e., hinge uses  $P_{ye}$  and member uses  $P_{CL}$ ). Analytical results of the member strength interaction curves indicate that column members satisfy the performance criteria. Nonetheless, the in-plane stability of a column with plastic hinges from in-plane flexure is highly complex and is a topic that is not well understood in the literature or implicitly or explicitly addressed in ASCE 41 for the nonlinear procedures. Experimental testing on shallow wide-flanged steel beam-columns has illustrated that the weak-axis buckling strength of a wide-flange is not affected by plastic hinges from in-plane flexure.

**Table 3-27. Performance Summary of Column Members (CM) per frame, Nonlinear Procedures**

Archetype	Design	NSP		NDP (based on mean response of record set)	
		LS	CP	LS	CP
4-Story	ELF	---	All CM Pass	---	All CM Pass
	RSA	---	All CM Pass	---	All CM Pass
8-Story	ELF	---	All CM Pass	---	All CM Pass
	RSA	---	All CM Pass	---	All CM Pass
16-Story	ELF	---	All CM Pass	---	All CM Pass
	RSA	---	All CM Pass	---	All CM Pass

The SCBF columns (most are force-controlled) except at the base consistently satisfy the performance objective indicating that the capacity design provisions in AISC 341 result in adequate column sizes. These results are somewhat contrary to that suggested by the analytical results using the linear procedures. Still, the linear procedures have limitations in capturing a realistic force demands in the base columns and braces, thus contributing to the cause of this unanticipated discrepancy.

### 3.2.3.2.3 Summary

Table 3-28 summarizes the performance of the archetype buildings in reference to the BSO for both nonlinear procedures. Brace member performance from both assessment procedures controls the overall assessment of the frames. Similar to the linear assessments, column-to-base connection assumptions led to performance issues for the force-controlled base columns. As noted above, additional research is needed on assessment criteria for brace connections and columns. In the end, none of the designed frames satisfy the seismic performance objective using the NSP (not considering results from the LDP where required) or the NDP.

**Table 3-28. BSO Performance Summary of Archetype Buildings, Nonlinear Procedures**

Archetype	Design	NSP			Design	NDP (based on mean response of record set)		
		BM	CH	CM		BM	CH	CM
4-Story	ELF	Fail	Fail	Pass	ELF	Fail	Fail	Pass
	RSA	Fail	Pass	Pass	RSA	Fail	Fail	Pass
8-Story	ELF	Fail	Fail	Pass	ELF	Fail	Fail	Pass
	RSA	Fail	Pass	Pass	RSA	Fail	Fail	Pass
16-Story	ELF	Fail	Pass	Pass	ELF	Fail	Fail	Pass
	RSA	Fail	Pass	Pass	RSA	Fail	Fail	Pass

The assessment results from the NSP and NDP illustrate that, on average, the ELF-designed SCBF does not perform significantly better than the RSA-designed SCBF for all archetype buildings—a corollary of the two frame designs being nearly the same. This result can be attributed to the slight increase in strength and stiffness provided to the ELF-designed frames (see Table 2-5) by differences in the ELF and RSA procedures, including associated scaling provisions, in ASCE 7. Further, section compactness requirements in AISC 341 resulted in minor variations in member sizes during design.

The NSP (without supplemental verification) consistently results in lower  $DCR_N$  values than the NDP for both the ELF- and RSA-designed frames for all archetype buildings, an indication that a more accurate distribution of seismic demands is not well captured in taller frames using the NSP (LDP results are consistently greater than NSP, albeit a direct comparison is problematic as discussed previously). Nonlinear results indicate that the NSP has a tendency to underestimate the demands in the upper stories. This occurs primarily because of the differences in the distribution of seismic demands and the lack of modal representation other than the fundamental mode in the NSP. This effect was also noticed in NIST GCR 10-917-9: *Applicability of Nonlinear Multi-Degree-of-Freedom Modeling for Design* (NIST 2010c).

The results from the NDP are sensitive to excitation input, analysis parameters, and component modeling. In this study, generalized component models were incorporated with degradation effects calibrated to an experimental test. Future research should critically examine the applicability of the generalized modeling parameters for steel components in ASCE 41. Experimental research has shown that subassembly tests can have large scatter in acceptable performance given the stochastic variations in the type of loading, that being cyclical, near-fault, random, etc. Future research should investigate the influence of the loading protocol adopted to establish the deterministic acceptance criteria for strut-type brace members.

Analytical results based on component-level performances obtained from the NSP and NDP suggest that special concentrically braced frames designed in accordance with ASCE 7 and its referenced standards have difficulty achieving the selected seismic performance objective of an existing building intended to be equivalent to a new building. This notion is driven by the performance of the braces and, to a lesser extent, the columns. The results for the columns can be enhanced by more mechanistically consistent column provisions and analytical modeling parameters. The results for the braces provide a contrary inference to that provided for the linear procedures. However, brace performance is based on high fidelity analytical modeling parameters (except for brace fracture) thus room for brace model enhancement is limited, although alternative modeling practices could be investigated.

### **3.2.3.3 Comparison between Linear and Nonlinear Assessment Results**

Table 3-29 summarizes the performance of the archetype buildings for each analysis procedure. The results indicate that the linear procedures do not consistently provide  $DCR_N$  values greater than that given by the nonlinear procedures. As discussed previously, direct comparison of results between linear and nonlinear procedures can be problematic, except for direct comparison of the distribution of results. No tangible consistency is evident in the global performance rating of the frames among the various assessment procedures. However, not all component performance failures align between the procedures, as discussed previously (e.g., brace members). The conservatism of the linear procedures is also apparent, as expected.

The nonlinear procedures provide a more rigorous assessment approach as compared to the linear procedures. However, the results from the nonlinear procedures indicate more performance failures in the brace members than identified using the linear procedures, which is contrary to the assumption that the linear procedures are more conservative. Several factors contribute to this outcome, but it is difficult to narrow down any single primary contributor. Certainly for the NDP, the effects of ground motion selection and scaling can be significant, including the number of records adopted to achieve a reasonable level of statistical confidence and the method by which the records were chosen with a bias to achieve an unfairly beneficial binary outcome. Moreover, some of the higher mode periods fall directly in localized high energy regions of the response spectrum resulting in increased axial demands that cannot be captured efficiently in a linear analysis using a smooth generalized spectrum. Furthermore for the NSP, the force distribution is potentially inadequate for frames that exhibit increased higher mode participation, either elastically or triggered by nonlinearity.

**Table 3-29. BSO Performance Summary of Archetype Buildings**

Archetype	Design	LSP	LDP	NSP	NDP (based on mean response of record set)
4-Story	ELF	Pass	Pass	<b>Fail</b>	<b>Fail</b>
	RSA	Pass	Pass	<b>Fail</b>	<b>Fail</b>
8-Story	ELF	<b>Fail</b>	Pass	<b>Fail</b>	<b>Fail</b>
	RSA	<b>Fail</b>	Pass	<b>Fail</b>	<b>Fail</b>
16-Story	ELF	<b>Fail</b>	Pass	<b>Fail</b>	<b>Fail</b>
	RSA	<b>Fail</b>	Pass	<b>Fail</b>	<b>Fail</b>

The nonlinear procedures provide a more rigorous assessment approach as compared to the linear procedures. However, the results from the nonlinear procedures indicate more performance failures in the brace members than identified using the linear procedures, which is contrary to the assumption that the linear procedures are more conservative. Several factors contribute to this outcome, but it is difficult to narrow down any single primary contributor. Certainly for the NDP, the effects of ground motion selection and scaling can be significant, including the number of records adopted to achieve a reasonable level of statistical confidence and the method by which the records were chosen with a bias to achieve an unfairly beneficial binary outcome. Moreover, some of the higher mode periods fall directly in localized high energy regions of the response spectrum resulting in increased axial demands that cannot be captured efficiently in a linear analysis using a smooth generalized spectrum. Furthermore for the NSP, the force distribution is potentially inadequate for frames that exhibit increased higher mode participation, either elastically or triggered by nonlinearity.

In contrast to the nonlinear procedures, the linear analysis model and assessment is implied to be less rigorous and more conservative. As already discussed, the linear procedures yielded less conservative results for the deformation-controlled diagonal braces. The linear procedures can also illustrate the trend in demands but may fail to highlight critical performance zones within a given frame. A case in point is the acceptable  $DCR_N$  values of the brace members while the nonlinear procedures illustrate that the braces fail the acceptance criteria.

For observation purposes only, Figure 3-112 illustrates the story drift ratios (normalized to two percent) for the RSA-designed frame at the BSE-2 EHL from the NDP. Evaluating drift ratios against Figure 3-77 shows that some braces are failing the CP criteria prior to achieving a two percent story drift ratio.




Figure 3-112. NDP Assessment Results, Story Drift Ratios, 8-Story SCBF RSA, BSE-2 CP

The columns that failed the acceptance criteria are typically force-controlled due to high axial loads, a result of using  $P / P_{CL}$  in lieu of  $P / P_{ye}$  to model flexural hinge strength and trigger force-controlled response. In comparison to the results from the NDP, the linear procedures produced conservative estimates of poor performance. On average, the linear procedures slightly overestimate the axial force demand in the exterior columns. Although there is general agreement between the procedures on which members may pose a risk, the results from the NDP illustrate that the column hinges can satisfy the performance criteria if the hinges were not force-controlled using  $P_{CL}$ , which is generally governed by out-of-plane flexural buckling. Enhancements to the assessment of beam-columns could consider using a dual assessment criterion that evaluates stability and flexural hinging separately (as is done for the NDP in this study). Noting the number of force-controlled columns (assuming  $P_{CL}$  is appropriate), ASCE 41 could impose a capacity design philosophy for a CBF similar to that prescribed for an EBF to simplify and clarify the process. As such, an SCBF designed in accordance with AISC 341 would pass the assessment criteria in ASCE 41 by default.

The failure of the SCBF using the NDP exposes the need for more sophisticated assessment guidance. A building with seemingly reasonable strength distribution and ductility is seen to be prone to high concentration of demands, which went undetected during the (linear) design process and the ensuing linear performance assessment.



## Chapter 4 Summary, Conclusions, and Recommendations

This report presents the results of a study investigating the correlation between the seismic performance of an ASCE 7 code-compliant building and its performance as quantified using ASCE 41 analysis procedures and structural performance metrics. This investigation is performed by evaluating a suite of structural steel buildings in a high seismicity region that are designed using ASCE 7 and evaluated using ASCE 41. *The basic question is whether the standards for designing new steel buildings and assessing existing steel buildings provide consistent levels of performance.* An additional outcome of this research is to advance the state-of-knowledge in PBSD and assessment of buildings using ASCE 41. Further, results provide the technical background for provisions that target equivalent seismic performance between a new building and an existing building that is required to meet the seismic performance objective of a new building.

This chapter highlights significant observations and conclusions from the seismic assessment of the archetype buildings using four assessment procedures in ASCE 41. General findings and recommendations are based on the collective results for the seismic force-resisting system. More in-depth findings specific to the system are in the relevant subsections in this chapter, as well as in relevant sections of the assessment discussion in Chapter 3. Although the primary emphasis of this study is on benchmarking ASCE 41 assessment procedures, questions arise that may be more applicable to the design criteria used rather than to the assessment results—these items are identified in the section about future research.

### 4.1 Summary of Project Work

This report presents the results of a structural seismic performance assessment using ASCE 41 procedures and performance measures of buildings utilizing steel special concentrically braced frames (SCBF) as the lateral force-resisting system (LFRS).

A suite of archetype buildings that incorporate SCBFs along one principal direction of the buildings is designed in accordance with ASCE 7. The suite consists of 4-, 8-, and 16-story buildings designed using both the Equivalent Lateral Force (ELF) Procedure and Modal Response Spectrum Analysis (RSA). Both analysis procedures are used to provide a generally applicable range of LFRS strength within the selected seismic intensity region. As such, an LFRS may include significant overstrength to resist nonseismic loads or to satisfy other design criteria. A design space is created to investigate the effects of design methodology, building height and other LFRS-specific geometric modifications on seismic performance. In reality, the design space is infinitely large and many design choices made in this study can also have different configurations to evaluate the variation in performance specific to a design choice.

The seismic performance assessment of the building suite is conducted using both linear and nonlinear analysis procedures prescribed in ASCE 41:

- Linear Static Procedure (LSP)
- Linear Dynamic Procedure (Response Spectrum) (LDP)
- Nonlinear Static Procedure (NSP)
- Nonlinear Dynamic Procedure (NDP)

For this study, the performance assessment targets the Basic Safety Objective (BSO) prescribed in ASCE 41. This objective includes the interrelated goals of Life Safety (LS) Building Performance Level (BPL) at the Basic Safety Earthquake-1 (BSE-1) earthquake hazard level (EHL) and Collapse Prevention (CP) BPL at the BSE-2 EHL. This performance objective is chosen to align with the intended structural performance objective of an ordinary building in ASCE 7, which is qualitatively defined here as “life safety” provided by collapse prevention of the building, given a maximum considered earthquake (MCE) event.

To evaluate seismic assessment criteria, each component of the SCBFs is designated as a *primary* member (or component) in accordance with ASCE 41 §2.2.5 (and ASCE 41 §2.4.4.2). Similarly, quantitative performance measures (i.e., acceptance criteria) for *primary* components are used for all assessment procedures, although performance measures for *secondary* components are permitted by ASCE 41 for some primary components. The consistent use of primary acceptance criteria keeps all components and associated assessment results correlated among the assessment procedures for this study.

The goals of this research are as follows:

- Assess *new* structural steel buildings utilizing SCBFs designed per ASCE 7 requirements and, in turn, evaluated using ASCE 41,
- Develop a qualitative link between the performance implied in ASCE 7 in light of the performance identified by ASCE 41 procedures and performance measures,
- Provide guidance or technical support for improved or new provisions in ASCE 41 (and to a lesser extent, ASCE 7),
- Reduce uncertainty in first-generation PBSD procedures for performance-based seismic assessment, and
- Identify any inconsistencies, ambiguities, and confusing provisions in ASCE 41.

In reference to developing a link between ASCE 7 and ASCE 41, the primary difficulty in equating the two standards is rooted in their disjointed performance objectives. That is, acceptance criteria for a component in ASCE 41 are not directly calibrated to the seismic performance objective of ASCE 7, which is a 10 percent probability of partial or total collapse given an MCE event—that is  $MCE_R$  (or one percent probability of partial or total collapse in 50 years). Equating the two objectives of the standards would imply that only one structural performance level with an associated earthquake hazard level can be coupled: that being, CP at the  $MCE_R$ . However, this would be difficult based on a member-level binary performance solution. Consequently, the question becomes what percentage of components needs to fail the associated CP SPL to achieve a 10 percent probability of total or partial collapse given an  $MCE_R$  event? Future research should assess the archetype buildings in FEMA P695 analysis to ascertain the collapse probability in relation to the ASCE 7 performance objective. Results from that study can be used to probabilistically relate the *R*-factor in ASCE 7 to the *m*-factors and inelastic deformations using story drift. Clearly, the study presented in this report presumes that the *R*-factor used for design has been derived to provide the intended

collapse performance objective. As such, the analysis results do not necessarily reflect satisfactory or unsatisfactory performance in relation to the seismic performance objective of ASCE 7.

A consequence of a deterministic-type component evaluation (i.e., pass or fail) is that analytical results, depending on the accuracy of the model and analysis algorithms, can be independent of the behavior of the system. Individual member performance and the potential need to retrofit or replace it are therefore based on an analysis output rather than the influence of the component performance on the system performance. This is a challenging issue to overcome, and only recently has there been *some* progress made (e.g., FEMA P695 and FEMA P-58 (FEMA 2012)) toward having the ability to probabilistically correlate member performance to system performance. However, these efforts are not without their limitations and debatable performance metrics. It is still yet to be determined whether practitioners will accept these developing methods because of the time and resources needed to successfully apply their recommendations. However, ASCE 41 is available and being used for performance-based seismic engineering of building systems and components. In many cases, the acceptance criteria in ASCE 41 are being used to justify computed seismic performance to buildings officials as being satisfactory. The question is what seismic performance is being justified: the objective defined in ASCE 41 or that intended in ASCE 7? If satisfying ASCE 7, then this would infer that the CP SPL associated with the  $MCE_R$  (taken as the BSE-2) defined in ASCE 41 matches the intended collapse performance of ASCE 7. A significant effort is still needed to bring ASCE 41 to the state-of-the-art and equivalent to ASCE 7. In this regard, assessment provisions are meaningless without the technical support provided by experimental research and subsequent case studies that evaluate how the research findings affect component and system performance.

## 4.2 Assumptions and Limitations of this Study

The following discussion summarizes notable assumptions employed in this study and other limitations of the work that could impact the results, which form the basis for the conclusions and observations.

### Building System and Component Characteristics for Design and Assessment

- The archetype buildings are representative of a specific type of building, which uses a seismically designed system to resist lateral loads and deformations. The selected system in this study represents one design option out of the many available for steel framed buildings. In designing the SFRS, there are many specific design assumptions made that play an important role in resisting lateral loads and deformations. Different selections for frame configuration, plan layout, bay spacing, height, connection details, and magnitude of non-seismic loads all could affect the assessment results.
- The buildings are *regular* in layout and configuration as defined in both ASCE 7 and ASCE 41. Irregular building configurations can affect seismic performance and are not addressed in this study, as they could complicate the comparisons that are being made.
- The archetype buildings are simple in concept and do not contain stairwells, elevator cores, architectural setbacks, atriums or other features found in typical buildings. The goal here is to study the basic performance of the SFRS in resisting lateral loads and deformations without the complexity posed by other attributes found in buildings today.

- Strength and stiffness of specific *secondary* components, as defined in ASCE 41, were not fully represented in the mathematical model for linear and nonlinear analyses (e.g., shear tab connection for gravity framing, façade, stairs, etc.). This assumption, while reasonable from an analysis standpoint, highlights a difference in requirements between ASCE 7 provisions for design and ASCE 41 provisions for assessment (ASCE 7 §12.7 and ASCE 41 §3.2.2).
- Composite action developed between primary and secondary structural components and the portion of slab they support was not included in the mathematical model for seismic design or assessment. This approach is consistent with that used by many practitioners and provides presumably conservative results because floor slabs are not active in providing composite action and added moment capacity. Composite action was included for the moment frame beams for verifying elastic story drifts under service-level wind loading.
- The column-to-base connections of the SFRS and the seismic base of the buildings were assumed to be horizontally, vertically, and rotationally restrained, resulting in a “fixed” connection to the ground. The base of non-SFRS columns were rotationally unrestrained. Soil-structure interaction effects, modeling the flexibility of the soil and / or the foundation components, and modelling partially-restrained column-to-base connections were not included in this study. Inclusion of these effects would likely affect the assessment results. However, inclusion of the effects of the soil-foundation flexibility into the analysis is complex and not well established at the present time. Moreover, current design practice commonly does not include soil-foundation effects; column-to-base connections to the building foundations are often idealized models, as is done in this study.
- No formal investigation was included in this study to evaluate the accuracy of the quantitative modeling parameters for nonlinear analysis or acceptance criteria for linear and nonlinear analysis provided in ASCE 41 for primary or secondary component models. There is a project currently ongoing with ATC (ATC-114: *Development of Accurate Models and Efficient Simulation Capabilities for Collapse Analysis to Support Implementation of Performance Based Seismic Engineering*) that will examine the component modelling parameters and acceptance criteria for specific components.

### **Structural Analysis**

- No formal investigation was included in this study to evaluate the accuracy of the analysis algorithms in the software packages used for structural analysis. These software packages are the same as those used by practitioners. The stability of solution algorithms when the stiffness and strength of the component models have significantly degraded can vary between software packages. Therefore, any software accuracy limitations encountered in this study are consistent with those present in design offices.
- The methodology used in this study for ground motion selection and scaling resulted in a set of earthquake records that may not be applicable or suitable for a specific site. A different record set—selected by engineering judgment, selected by revising the parameters of the methodology, or developed from an alternative methodology—could affect the assessment results. However, the process employed here is consistent with that used in practice, representing a typical building site in an area with a high level of seismicity.

No formal investigation was included in this study to evaluate all potential sources of uncertainty or error, or whether multiple sources of error are correlated. The question of uncertainties in the analytical models, solution algorithms, material properties and even potential as-built final dimensions and positions of members are all beyond the scope of this study. The load and resistance factor design (LRFD) philosophy in use for structural design today are based on pioneering work on uncertainties in material and load characterizations performed starting in the 1950's. Whether a new similar large national effort to that conducted for LRFD is required today is not clear. Quantifying the effect of any source of uncertainty or error, as it relates to the design or assessment of buildings to resist earthquake motions, is a significant issue and would require its own research program to study all of the aspects.

## 4.3 Conclusions and Observations

This section highlights significant observations and conclusions from the seismic assessment of the archetype buildings. Topics are categorized as general or system specific. Additionally, more in-depth discussions of the observations and conclusions specific to the SFRS are in the relevant subsections in this chapter as well as in relevant summary sections of the assessment discussion.

### 4.3.1 ASCE 41

The following observations and conclusions can be drawn from this study. Topics are grouped by either general applicability to ASCE 41 assessment procedures or specific to the structural system.

#### 4.3.1.1 General

The following general topics focus on observations identified by the assessment provisions for the selected assessment methods:

- The LSP generally results in more conservative normalized demand to capacity ratios,  $DCR_N$ , values than that of the LDP, because of the differences in the distribution of seismic demands and the lack of modal representation other than the fundamental mode in the LSP.
- The NSP generally results in less conservative  $DCR_N$  values than that of the NDP, contrary to what would be expected with increasing the analytical complexity, because of the differences in the distribution of seismic demands and the lack of modal representation other than the fundamental mode in the NSP.
- The nonlinear procedures provide a more rigorous assessment approach as compared to the linear procedures. The results from the LSP, and to a lesser extent the LDP, indicate more performance failures in force-controlled components than identified using the nonlinear procedures. The results presented emphasize the inherent conservatism in the linear procedures. However, this conservatism is accompanied by a reduction in required analytical resources and proficiency of the analyst.
- The linear procedures can illustrate the trend in demands but may fail to highlight critical performance zones within a given frame.

- No clear consistency exists between linear assessment results and nonlinear assessment results for brace members. Contrary performance results indicate acceptance criteria that need further calibration.

#### 4.3.1.2 Special Concentrically Braced Frame

The following significant observations and conclusions are based on the collective results obtained from the assessment of the SCBFs. More details about the specific items are in the relevant sections of the assessment discussion in Chapter 3.

- Analytical results based on component-level performances indicate, dependent on the assessment procedure used, that new SCBFs designed in accordance with ASCE 7, and its referenced standards, have difficulty achieving the ASCE 41 BSO for an existing building intended to be equivalent to a new building. This observation is driven by the performance of the braces and, to a lesser extent, the columns. Assessment results for brace members from the nonlinear procedures provide a conclusion opposite to that provided for the linear procedures in that nonlinear assessment reveals higher  $DCR_N$  values than the linear assessment.
- *Assuming* the archetype buildings meet the collapse performance objective of ASCE 7, the results of the assessment procedures indicate that ASCE 41 is generally conservative for SCBFs. ASCE 41 analysis would require retrofit or replacement of specific components of a code-compliant SFRS to satisfy the CP BPL, given an MCE event. The results highlight that columns (i.e., beam-columns) with high axial and flexural demands and brace members have difficulty in satisfying the performance criteria in ASCE 41. Future research is needed to couple the collapse performance objectives of the two standards, as well as other performance objectives associated with a seismic hazard with a lower return period.
- Analysis results indicate that the linear procedures generally give smaller  $DCR_N$  values than that obtained from nonlinear procedures, contrary to what would be expected from increasing the analytical complexity. Given a properly designed new brace member, the linear procedures will result in a maximum  $DCR_N$  value for a primary component of approximately the ratio of  $C_u T_a / T_1$ , which is less than or equal to unity.
- A significant number of brace members did not satisfy the acceptance criteria for the nonlinear procedures. Brace performance is based on high fidelity analytical modeling parameters (except for brace fracture); thus, room for brace modeling enhancement is limited, although alternative modeling practices could be investigated. Research should investigate the influence of the loading protocol adopted to establish the deterministic acceptance criteria for brace members.
- A significant number of columns, primarily at the base of the frames, did not satisfy the ASCE 41 acceptance criteria. The results for columns can be enhanced by more mechanistically consistent assessment provisions and analytical modeling parameters for columns (e.g., column/brace-to-base connection modeling). Refinement of the relevant interaction equations to evaluate specific failure mechanisms could assist by allowing what would be a force-controlled column to be classified as “deformation-controlled”.
- Components of the SCBFs that do not satisfy the CP acceptance criteria would need to be strengthened to achieve the performance required by ASCE 41. However, the results from the various assessment procedures were seen to be inconsistent in some cases for a given design routine

(i.e., LSP vs. NDP) or the same assessment procedure was inconsistent between design routines (i.e., ELF and RSA). This makes it difficult to definitively suggest that using ASCE 41 to design a new SCBF would produce a system capable of achieving the seismic performance objective of ASCE 7. Future research is needed to evaluate the collapse probability of a new system strengthened by ASCE 41 relative to the seismic performance objective of ASCE 7. The same is required for a new system that has component strengths reduced from that required by ASCE 7 to meet an ASCE 41 performance objective. Further, the adequacy of the components of the enhanced frame (those required to satisfy ASCE 41) would be dependent upon which analysis procedure is used to iterate between design and assessment, and therefore the fidelity of the analytical model and analysis parameters.

- Results from this study indicate that for ASCE 41 to be used as a seismic design procedure for new steel buildings, as a performance-based alternative to ASCE 7 (see ASCE 7 §1.3.1.3), acceptance criteria for the various analysis methods must be calibrated to each other to consistently result in a uniform collapse risk. Additionally, ASCE 41 would need to reference material-specific design standards (e.g., AISC 341) for their seismic design requirements, as well as consistent requirements for defining acceptance criteria for a component (e.g., plastic rotation).

## **4.4 Recommendations for Future Research**

The following sections identify items for future research. The recommendations are grouped by the applicable standard: ASCE 41, ASCE 7, and AISC 341 / 360 / 358.

### **4.4.1 ASCE 41**

#### **4.4.1.1 General**

The following items are general considerations for future studies to enhance ASCE 41 assessment provisions:

- The archetype buildings should be analyzed using the methodology formulated in FEMA P695. This will provide the requisite data to identify the collapse probability of the systems (or frames) in relation to the intended collapse objective of ASCE 7. However, the same seismic performance factors as used in design should be used in the analysis. Results from this study can be used to probabilistically relate the  $R$ -factor in ASCE 7 to  $m$ -factors and inelastic deformations using story drift.
- Research should investigate the implementation of risk-targeted collapse assessment criteria into ASCE 41 similar to the design philosophy introduced in ASCE 7-10. As such, comparison of system fragility curves should be done to correlate the risk-target of ASCE 7 and the risk-target of an existing building intended to be equivalent to a new building.
- Research should evaluate the influence of gravity framing (e.g., partially restrained shear tab connections) on assessment results of the primary components of the SFRS.
- Research should investigate alternative lateral force distributions for taller systems for the NSP, including comparison between adaptive and non-adaptive loading.

- Research should be conducted to determine the number of components that do not need to satisfy the ASCE 41 component acceptance criteria while still permit the building to be classified as meeting a performance objective.
- Research should evaluate the systems used in this study by measuring demands against acceptance criteria for secondary components to quantify variations in performance results; for example, the diagonal brace members in the MC8 buildings. Even if secondary component criteria were implemented, the  $DCR_N$  values still indicate unsatisfactory performance in the several floors. The primary acceptance criteria for the nonlinear procedures has been removed in ASCE 41-13. Based on some trends seen in this study, this should be done only if the acceptance criteria for linear and nonlinear procedures have been correlated and calibrated.
- Enhanced commentary is needed in ASCE 41, similar to the effort used to develop FEMA 274. Commentary can be used to explain differences in component strengths between ASCE 41 and ASCE 7 and its reference standards (e.g., AISC 341 and AISC 360). This effort would include cleaning up incorrect references (e.g., AISC 341 or AISC 360, FEMA 355F or FEMA 355D). Similarly, the commentary can detail the experimental tests used to derive the acceptance criteria.
- Consideration should be given to reorganize Chapter 5 (Chapter 9 in ASCE 41-13) to remove system-to-system references, most notably when they are not applicable. For example, a force-controlled column in an EBF cannot reference provisions for a column in a moment frame. This chapter would benefit with an outline similar to AISC 341, where the section on member strength is outlined similar to AISC 360. Therefore, the individual systems would reference a member strength in lieu of another system that may or may not be applicable.

#### 4.4.1.2 Concentrically Braced Frames

The following items are considerations for future studies to enhance ASCE 41 assessment provisions for concentrically braced frames:

- Research should critically examine the applicability of the generalized modeling parameters for strut-type braces for use in the nonlinear procedures.
- Research should investigate the correlation between acceptance criteria for the linear and nonlinear procedures. This effort can include alternative modeling strategies for brace members.
- Research should investigate the influence of the loading protocol adopted to establish the deterministic acceptance criteria for strut-type brace members. Similarly, the influence of total brace fracture on the acceptance criteria can be included. ASCE 41-13 partly addressed this issue in revised acceptance criteria for braces in tension. However, acceptance criteria for braces in compression always governed the assessment in this study. A supplementary analysis performed on the RSA-designed MC8 using the revised ASCE 41-13 criteria indicated no change in the governing  $DCR_N$  value.
- Research should investigate the use of acceptance criteria and modeling parameters for brace connections. Guidance is needed concerning modeling parameters for beam-to-column connections strengths and acceptance criteria once the adjacent brace(s) experience total strength loss from fracture.
- Research is needed to develop acceptance criteria and modeling parameters for column / brace-to-base connections, including embedded connections.

- Research is required to justify updated interaction equations for assessment of beam-columns using ASCE 41, as well as a critical examination of the acceptance criteria in regard to experimental test results. Decoupling interaction equations into specific failure mechanisms and referencing highly vetted design standards should be considered. Removing  $P_{CL}$  as the basis for force-controlled response and acceptance criteria for a column hinges (i.e., revert back to FEMA 273) and using  $P_{CE}$  when  $F_{ye}$  is used to assess a flexure hinge in the same column should also be considered.

#### **4.4.2 ASCE 7**

The following items are considerations for future studies to enhance ASCE 7 provisions:

- The assessment results illustrate that on average the ELF-designed frames perform better than the RSA-designed frames for all archetype buildings. However, the ELF procedure is not permitted in some cases. Research should investigate the applicability of the analysis limitations in terms of the intended collapse objective of ASCE 7.
- Research should investigate the lateral design force distributions in ASCE 7 and modal scaling provisions, and their influence on the allocation of component strengths within a frame. Research has indicated that higher modal base shear scaling may be warranted (NIST 2010b and NIST 2012). Potential modifications to the MRSA procedure could also include scaling provisions to additionally account for higher mode effects resulting from nonlinear response. Provisions can be directly transferred to the linear procedures in ASCE 41.
- Research efforts should evaluate incorporating other performance levels for design into ASCE 7 (NIST 2012).

#### **4.4.3 AISC 341 / 360 / 358**

##### **4.4.3.1 Special Concentrically Braced Frames**

The following items are considerations for future studies to enhance AISC 341 provisions of special concentrically braced frames:

- The design adopted for the archetype buildings indicate that there is minor variation in member sizes when using either the ELF procedure or the RSA to determine required member strengths. This is primarily due to section compactness requirements.
- The axial load demands on the columns determined from the NDP are consistently greater than that determined using the system overstrength factor (i.e., ASCE 7) and less than that determined from the capacity analysis prescribed in AISC 341 §F2.3. As such, results indicate that the capacity design procedure in AISC 341 does well in setting the required member strength. Research should investigate whether a 0.88 factor, as allowed for an EBF—see AISC 341 §F3.3, or similar concept is applicable for an SCBF. Similarly, the use of the overstrength factor to compute required axial strengths should be disregarded since it can be highly unconservative. AISC 341 can provide more guidance on how to perform this analysis as well as how to incorporate the flexural demand that can exist in beams and columns after brace fracture.



# Appendix A Ground Motions for Response History Analysis

## A.1 Ground Motion Record Set

The far-field record set (22 records, each with two horizontal components) from FEMA P695 (FEMA 2009a) is selected as the input motion database for the NDP; 14 of the 44 horizontal component records are selected as the ground motion set for each archetype building, with no two records coming from the same station. The records are normalized for magnitude, distance, and source conditions as discussed in FEMA P695.

The *scaled* record set (see Ground Motion Selection and Scaling section below) for each archetype building is taken directly as the Basic Safety Earthquake-2 (BSE-2) earthquake hazard level (EHL). Although this EHL is not strictly the same as having a two percent probability of exceedance in 50 years, it is comparable, and anticipated future changes in ASCE 41-13 will likely match the seismic hazard defined in ASCE 7-10 (see Chapter 3). The scaled record set is factored by two-thirds to represent the BSE-1 EHL in lieu of explicitly determining the ground motion parameters with a ten percent probability of exceedance in 50 years. No spectral shape modifier,  $\varepsilon$ , is used to adjust the seismic demands for either BSEs (FEMA 2009a; Haselton et al. 2009), this is a topic of needed research.

As a side note, the goal initially was to analyze the archetype buildings using seven scaled pairs of ground motion records along each principal axis of the structure (14 records in each direction). However, because of complications in scaling orthogonal pairs for the maximum direction of response when a structure has significantly different periods along the principal axes, it was decided to analyze 14 unique records independently along each principal axis—see above. This is permitted by ASCE 41 since requirements for considering multidirectional seismic effects are not triggered in this study—see ASCE 41 §3.2.7. Further, there is no guidance regarding the application of scaled ground motion pairs for the maximum direction of response when a structure has significantly different periods along the principal axes. Future research is needed to provide provisions on scaling and application of ground motion pairs.

## A.2 Ground Motion Selection and Scaling

The ground motion selection and scaling procedure for each archetype building is described below. This procedure was developed in consultation with select members of the peer review team. Each set of records (14 total) is used for both the equivalent lateral force (ELF) and response spectrum analysis (RSA) designs to gauge performance between the two. The process is as follows:

1. Determine the fundamental *lateral* mode period,  $T_1$ , of the building in the direction being considered not including gravity load effects (i.e., first-order period) for both the ELF and RSA

designs. Second-order periods may also be computed with *expected point-in-time* gravity loads rather than *factored* loads. Determine the average (arithmetic mean) of the periods for the ELF and RSA designs,  $T_{1,avg}$ . This will keep the scaling of the two designs consistent.

2. For each of the 44 far-field component records (not the records computed from the square root of the sum of the squares (SRSS) of the two horizontal components of an event), compute the error between  $S_a$  from the recorded spectrum and  $S_a$  from the maximum considered earthquake (MCE<sub>R</sub>) design spectrum at each period between  $0.2 \times T_{1,avg}$  and  $1.5 \times T_{1,avg}$ . The period step used here is 0.01 second. The error at each period ranges from 0 to 1, with 0 being an identical match.
3. Sum the error values over the periods between  $0.2 \times T_{1,avg}$  and  $1.5 \times T_{1,avg}$  to get a single composite error value for each record.
4. Scale each record to minimize the total error from step 3.
5. Select the 14 records with least total error. If both horizontal components of a specific station are in the set, then remove the record with the larger error of the pair and select the next unique record from the remaining record set. This step is repeated as needed until all records selected are from different stations.
6. Compute the average spectrum from the record set (14 total) from step 5.
7. Scale the average spectrum from step 6 so that no value between  $0.2 \times T_{1,avg}$  and  $1.5 \times T_{1,avg}$  is less than the MCE<sub>R</sub> spectrum. The 1.3 factor in ASCE 41 §1.6.2 is not included here, so as to address the change of spectrum parameters from geomean to maximum direction response in ASCE 7 (this factor will be removed in ASCE 41-13).
8. Scale the record set from step 5 by the value computed in step 7. Therefore, there are two scaling factors: step 4 and step 7.
9. Apply the total scaling factor (step 4 times step 7) to each component record in the set from step 5 and perform analysis.

For comparison purposes, the process in ASCE 41 §1.6.2.2 is summarized as follows:

1. Select a minimum of three recorded events (each event is a data set), each with two horizontal components.
2. Take the SRSS of the two horizontal components of each selected data set from step 1.
3. Select a *scaling factor* for each SRSS from step 2. Note that application of a scaling factor to the unscaled SRSS is equivalent to taking the SRSS of the similarly scaled components.
4. Compute the average of the scaled SRSS spectra from step 3 for all selected events.
5. Scale the average spectrum from step 4 so that no value between  $0.2 \times T_{1,avg}$  and  $1.5 \times T_{1,avg}$  is less than 1.3 times the *design* spectrum.
6. Apply the total scaling factor (step 3 times step 5) to each component record in an event and perform analysis.

The selection and scaling procedure in this study differs slightly from that found in ASCE 41. Because this study investigates a generalized SDC  $D_{max}$  analysis without a specific location, it is difficult to select a site and apply common selection and scaling processes typically performed by a geotechnical engineer. In lieu of taking the SRSS of the two horizontal components of an event and having 22 SRSS spectra and in turn computing the error of the SRSS records and associated scaling factor for the event, the error and scaling factor were computed for each component (44 spectra). 14 unique records were selected per principal

direction and the average of this set scaled to meet the target spectrum. In summary, steps 1 to 5 in the process identify the “best fit” to the ASCE 41 code spectrum (which matches ASCE 7). The average of this set is computed and scaled similarly to that in ASCE 41—without the 1.3 factor.

Other ground motion selection and scaling methods are discussed in NIST GCR 11-917-15: *Selecting and Scaling Earthquake Ground Motions for Performing Response-History Analyses* (NIST 2011d).

## A.3 Four-Story Archetype Building

### A.3.1 4-Story Special Concentrically Braced Frame

Table A-1 summarizes the 14 strong motion records used for the nonlinear dynamic procedure (NDP) for the N-S direction of MC4 special concentrically braced frame (SCBF). Figure A-1 illustrates the set of acceleration response spectra, original and scaled, and the scaled average spectrum. Figure A-2 illustrates the acceleration response spectra, original and scaled, for each select record. For comparison, the ASCE 41 code spectrum is shown in the figures. All analyses completed for the BSE-1 and BSE-2 for the ELF and RSA design.

**Table A-1. Ground Motion Records for N-S Direction of MC4**

ID	EQ No.	Event Name	Station	Comp. <sup>1</sup>	Error <sup>2</sup>	BSE-2 Scaling <sup>3</sup>	BSE-1 Scaling <sup>3</sup>	Step <sup>4</sup>	Time <sup>5</sup>
1	40	Chi-Chi, Taiwan	TCU045	2	6	1.853	1.236	0.005	90
2	35	Cape Mendocino	Rio Dell Overpass	1	9	2.005	1.337	0.020	36
3	9	Imperial Valley	Delta	1	9	2.543	1.695	0.010	100
4	31	Superstition Hills	El Centro Imp. Co.	1	9	2.301	1.534	0.005	40
5	4	Northridge	Canyon Country-WLC	2	11	1.469	0.980	0.010	20
6	17	Kocaeli, Turkey	Duzce	1	11	2.256	1.504	0.005	28
7	7	Hector Mine	Hector	1	13	3.719	2.479	0.010	46
8	34	Superstition Hills	Poe Road (temp)	2	14	2.807	1.871	0.010	23
9	21	Landers	Yermo Fire Station	1	15	3.024	2.016	0.020	44
10	15	Kobe, Japan	Shin-Osaka	1	15	2.811	1.874	0.010	41
11	20	Kocaeli, Turkey	Arcelik	2	15	6.796	4.531	0.005	30
12	6	Duzce, Turkey	Bolu	2	15	1.172	0.781	0.010	56
13	28	Loma Prieta	Gilroy Array #3	2	16	2.689	1.793	0.005	40
14	44	Friuli, Italy	Tolmezzo	2	16	1.878	1.252	0.005	37

Notes:

1. Component Number. See FEMA P-695 Appendix A for additional parameters associated to each component of an event.
2. Single composite error value computed in Step 3.
3. Scaling factor for the component for the BSE-2 or BSE-1 EHL (BSE-1 =  $\frac{2}{3}$  × BSE-2).
4. Time step in seconds.
5. Total time of record in seconds.





Figure A-1. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC4



**Figure A-2. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC4**

## A.4 Eight-Story Archetype Building

### A.4.1 8-Story Special Concentrically Braced Frame

Table A-2 summarizes the 14 strong motion records used for the NDP for the N-S direction of MC8 (SCBF). Figure A-3 illustrates the set of acceleration response spectra, original and scaled, and the scaled average spectrum. Figure A-4 illustrates the acceleration response spectra, original and scaled, for each select record. For comparison, the ASCE 41 code spectrum is shown in the figures. All analyses completed for the BSE-1 and BSE-2 for the ELF and RSA design.

**Table A-2. Ground Motion Records for N-S Direction of MC84**

I D	EQ No.	Event Name	Station	Comp. <sup>1</sup>	Error <sup>2</sup>	BSE-2 Scaling <sup>3</sup>	BSE-1 Scaling <sup>3</sup>	Step <sup>4</sup>	Time <sup>5</sup>
1	34	Superstition Hills	Poe Road (temp)	2	20	3.023	2.015	0.010	23
2	31	Superstition Hills	El Centro Imp. Co.	1	24	2.504	1.669	0.005	40
3	37	Chi-Chi, Taiwan	CHY101	1	25	2.223	1.482	0.005	90
4	10	Imperial Valley	Delta	2	25	2.165	1.443	0.010	100
5	20	Kocaeli, Turkey	Arcelik	2	29	6.379	4.253	0.005	30
6	17	Kocaeli, Turkey	Duzce	1	29	2.385	1.590	0.005	28
7	16	Kobe, Japan	Shin-Osaka	2	33	2.799	1.866	0.010	41
8	5	Duzce, Turkey	Bolu	1	33	1.714	1.143	0.010	56
9	12	Imperial Valley	El Centro Array #11	2	35	3.678	2.452	0.005	40
10	35	Cape Mendocino	Rio Dell Overpass	1	35	2.049	1.366	0.020	36
11	28	Loma Prieta	Gilroy Array #3	2	35	1.831	1.221	0.005	40
12	22	Landers	Yermo Fire Station	2	38	3.808	2.539	0.020	44
13	3	Northridge	Canyon Country-WLC	1	38	1.774	1.183	0.010	20
14	2	Northridge	Beverly Hills - Mulhol	2	38	1.102	0.735	0.010	30

Notes:

1. Component Number. See FEMA P-695 Appendix A for additional parameters associated to each component of an event.
2. Single composite error value computed in Step 3.
3. Scaling factor for the component for the BSE-2 or BSE-1 EHL ( $BSE-1 = \frac{1}{3} \times BSE-2$ ).
4. Time step in seconds.
5. Total time of record in seconds.





Figure A-3. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC8



**Figure A-4. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC8**

## A.5 Sixteen-Story Archetype Building

### A.5.1 16-Story Special Concentrically Braced Frame

Table A-3 summarizes the 14 strong motion records used for the NDP for the N-S direction of MC16 (SCBF). Figure A-5 illustrates the set of acceleration response spectra, original and scaled, and the scaled average spectrum. Figure A-6 illustrates the acceleration response spectra, original and scaled, for each select record. For comparison, the ASCE 41 code spectrum is shown in the figures. All analyses completed for the BSE-1 and BSE-2 for the ELF and RSA design.

**Table A-3. Ground Motion Records for N-S Direction of MC16**

ID	EQ No.	Event Name	Station	Comp. 1	Error <sup>2</sup>	BSE-2 Scaling <sup>3</sup>	BSE-1 Scaling <sup>3</sup>	Step <sup>4</sup>	Time <sup>5</sup>
1	34	Superstition Hills	Poe Road (temp)	2	28	2.987	1.991	0.010	23
2	12	Imperial Valley	El Centro Array #11	2	28	4.059	2.706	0.005	40
3	5	Duzce, Turkey	Bolu	1	35	2.005	1.337	0.010	56
4	31	Superstition Hills	El Centro Imp. Co.	1	38	2.805	1.870	0.005	40
5	10	Imperial Valley	Delta	2	38	2.410	1.606	0.010	100
6	20	Kocaeli, Turkey	Arcelik	2	41	5.844	3.896	0.005	30
7	15	Kobe, Japan	Shin-Osaka	1	43	3.023	2.015	0.010	41
8	17	Kocaeli, Turkey	Duzce	1	43	2.480	1.653	0.005	28
9	28	Loma Prieta	Gilroy Array #3	2	44	2.036	1.358	0.005	40
10	22	Landers	Yermo Fire Station	2	47	4.553	3.035	0.020	44
11	3	Northridge	Canyon Country-WLC	1	51	2.163	1.442	0.010	20
12	38	Chi-Chi, Taiwan	CHY101	2	52	1.183	0.789	0.005	90
13	39	Chi-Chi, Taiwan	TCU045	1	53	4.848	3.232	0.005	90
14	30	Manjil, Iran	Abbar	2	54	1.316	0.877	0.020	54

Notes:

1. Component Number. See FEMA P-695 Appendix A for additional parameters associated to each component of an event.
2. Single composite error value computed in Step 3.
3. Scaling factor for the component for the BSE-2 or BSE-1 EHL ( $BSE-1 = \frac{1}{2} \times BSE-2$ ).
4. Time step in seconds.
5. Total time of record in seconds.





Figure A-5. Acceleration Response Spectra: Original, Scaled, and Scaled Average Spectrum for N-S Direction of MC16



**Figure A-6. Acceleration Response Spectra: Original and Scaled for Each Selected Record for N-S Direction of MC16**

## A.6 FEMA P-695 Far-Field Record Set

Figure A-7 through Figure A-50 illustrate the recorded ground motion, Fourier amplitude (frequency and period), and the five percent damped response spectra (displacement, velocity, acceleration) for each component.




Figure A-7. 1994 Northridge Earthquake at Beverly Hills, Mulholland Drive Station, Comp. 009







Figure A-8. 1994 Northridge Earthquake at Beverly Hills, Mulholland Drive Station, Comp. 279




**Figure A-9. 1994 Northridge Earthquake at Canyon Country WLC Station, Comp. 000**




**Figure A-10. 1994 Northridge Earthquake at Canyon Country WLC Station, Comp. 270**




**Figure A-11. 1999 Duzce, Turkey Earthquake at Bolu Station, Comp. 000**




**Figure A-12. 1999 Duzce, Turkey Earthquake at Bolu Station, Comp. 090**




**Figure A-13. 1999 Hector Mine Earthquake at Hector Station, Comp. 000**




**Figure A-14. 1999 Hector Mine Earthquake at Hector Station, Comp. 090**




**Figure A-15. 1979 Imperial Valley Earthquake at Delta Station, Comp. 262**




**Figure A-16. 1979 Imperial Valley Earthquake at Delta Station, Comp. 352**




**Figure A-17. 1979 Imperial Valley Earthquake at El Centro Array Station #11, Comp. 140**




**Figure A-18. 1979 Imperial Valley Earthquake at El Centro Array Station #11, Comp. 230**




**Figure A-19. 1995 Kobe, Japan Earthquake at Nishi-Akashi Station, Comp. 000**




**Figure A-20. 1995 Kobe, Japan Earthquake at Nishi-Akashi Station, Comp. 090**




**Figure A-21. 1995 Kobe, Japan Earthquake at Shin-Osaka Station, Comp. 000**




**Figure A-22. 1995 Kobe, Japan Earthquake at Shin-Osaka Station, Comp. 090**




**Figure A-23. 1999 Kocaeli, Turkey Earthquake at Duzce Station, Comp. 180**




**Figure A-24. 1999 Kocaeli, Turkey Earthquake at Duzce Station, Comp. 270**




**Figure A-25. 1999 Kocaeli, Turkey Earthquake at Arcelik Station, Comp. 000**




**Figure A-26. 1999 Kocaeli, Turkey Earthquake at Arcelik Station, Comp. 090**




**Figure A-27. 1992 Landers Earthquake at Yermo Fire Station, Comp. 270**




**Figure A-28. 1992 Landers Earthquake at Yermo Fire Station, Comp. 360**




**Figure A-29. 1992 Landers Earthquake at Coolwater Station, Longitudinal Direction**



**Figure A-30. 1992 Landers Earthquake at Coolwater Station, Transverse Direction**



**Figure A-31. 1989 Loma Prieta Earthquake at Capitola Station, Comp. 000**



**Figure A-32. 1989 Loma Prieta Earthquake at Capitola Station, Comp. 090**




Figure A-33. 1989 Loma Prieta Earthquake at Gilroy Array Station #3, Comp. 000







Figure A-34. 1989 Loma Prieta Earthquake at Gilroy Array Station #3, Comp. 090




**Figure A-35. 1990 Manjil, Iran Earthquake at Abbar Station, Longitudinal Direction**




**Figure A-36. 1990 Manjil, Iran Earthquake at Abbar Station, Transverse Direction**




**Figure A-37. 1987 Superstition Hills Earthquake at El Centro, Imperial County, Comp. 000**




**Figure A-38. 1987 Superstition Hills Earthquake at El Centro, Imperial County, Comp. 090**




**Figure A-39. 1987 Superstition Hills Earthquake at Poe Road, Comp. 270**




**Figure A-40. 1987 Superstition Hills Earthquake at Poe Road, Comp. 360**




**Figure A-41. 1992 Cape Mendocino Earthquake at Rio Dell Overpass, Comp. 270**




**Figure A-42. 1992 Cape Mendocino Earthquake at Rio Dell Overpass, Comp. 360**




**Figure A-43. 1999 Chi-Chi, Taiwan Earthquake at CHY101 Station, E-W Component**




**Figure A-44. 1999 Chi-Chi, Taiwan Earthquake at CHY101 Station, N-S Component**




**Figure A-45. 1999 Chi-Chi, Taiwan Earthquake at TCU045 Station, E-W Component**




**Figure A-46. 1999 Chi-Chi, Taiwan Earthquake at TCU045 Station, N-S Component**




**Figure A-47. 1971 San Fernando Earthquake at Los Angeles Hollywood Store Station, Comp. 090**



**Figure A-48. 1971 San Fernando Earthquake at Los Angeles Hollywood Store Station, Comp. 180**



**Figure A-49. 1976 Friuli, Italy Earthquake at Tolmezzo Station, Comp. 000**



**Figure A-50. 1976 Friuli, Italy Earthquake at Tolmezzo Station, Comp. 270**



# Appendix B Supplemental Design Information and Design Examples

This appendix presents supplemental information and details on the design of each archetype building.

Section B.1 provides information about the following:

- Wind forces both for strength and drift analyses
- Effective seismic weights and story gravity forces
- Seismic forces both for strength and drift analyses
- Lateral story drifts and displacements (ASCE 7 §2.8.6)
- ASCE 7 stability verification (ASCE 7 §12.8.7)

Section B.2 provides information regarding horizontal and vertical irregularities of the SFRS.

Section B.3 provides information regarding the AISC 360 frame stability calculation ( $B_2$  for the effective length method) for the moment frame designs.

Section B.4 provides example calculations for the strength design of a few specific members and components:

- SCBF brace
- SCBF column

## B.1 Horizontal Design Forces

### B.1.1 Wind Forces

Table B-1 through Table B-3 provide the horizontal wind forces for the 700-year wind for strength design of the members and components of the MWFRS and wind forces for the 10-year wind for verification of serviceability criteria for each archetype building. In these tables,  $F_x$  represents wind forces in the E-W direction and  $F_y$  represents wind in the N-S direction. Slight differences in applied wind forces are due to stiffness variations between the ELF and RSA designs.

**Table B-1. Wind Forces on MC4 (kips)**

Level	Elevation (ft)	Diaphragm Forces (kips), Applied at Geometric Center							
		700-Year Wind (Design)				10-Year Wind (Drift)			
		RSA		ELF		RSA		ELF	
		$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$
Roof	60	36.09	52.43	35.30	52.43	14.82	22.46	14.67	22.46
4	46	35.48	50.50	33.98	50.50	13.99	21.63	13.69	21.63
3	32	33.21	47.53	31.81	47.53	13.09	20.36	12.82	20.36
2	18	34.36	49.60	32.91	49.60	13.55	21.25	13.26	21.25
Base	0	139.14	200.06	134.01	200.06	55.46	85.71	54.44	85.71

**Table B-2. Wind Forces on MC8 (kips)**

Level	Elevation (ft)	Diaphragm Forces (kips), Applied at Geometric Center							
		700-Year Wind (Design)				10-Year Wind (Drift)			
		RSA		ELF		RSA		ELF	
		$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$
Roof	116	46.18	63.44	44.19	63.33	18.47	27.03	18.00	27.03
8	102	49.32	63.10	45.43	62.89	18.55	26.74	17.64	26.74
7	88	47.98	61.52	44.20	61.31	18.05	26.07	17.16	26.07
6	74	46.48	59.75	42.81	59.54	17.49	25.32	16.62	25.32
5	60	44.76	57.72	41.23	57.52	16.84	24.46	16.00	24.46
4	46	42.72	55.31	39.35	55.12	16.07	23.44	15.28	23.44
3	32	40.18	52.31	37.01	52.13	15.12	22.17	14.37	22.17
2	18	41.88	55.02	38.58	54.83	15.76	23.32	14.98	23.32
Base	0	359.49	468.19	332.81	466.67	136.35	198.54	130.04	198.54

**Table B-3. Wind Forces on MC 16 (kips)**

Level	Elevation (ft)	Diaphragm Forces (kips), Applied at Geometric Center							
		700-Year Wind (Design)				10-Year Wind (Drift)			
		RSA		ELF		RSA		ELF	
		$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$	$F_x$	$F_y$
Roof	228	56.78	77.60	55.35	77.48	22.58	32.73	22.22	32.73
16	214	62.23	78.96	59.41	78.72	23.22	32.81	22.50	32.81
15	200	61.44	78.03	58.66	77.80	22.93	32.42	22.22	32.42
14	186	60.61	77.06	57.86	76.83	22.62	32.02	21.92	32.02
13	172	59.74	76.04	57.03	75.81	22.29	31.59	21.60	31.59
12	158	58.81	74.95	56.14	74.73	21.95	31.14	21.27	31.14
11	144	57.82	73.79	55.20	73.58	21.58	30.66	20.91	30.66
10	130	56.76	72.55	54.19	72.34	21.18	30.15	20.53	30.15
9	116	55.62	71.21	53.10	71.00	20.76	29.59	20.11	29.59
8	102	54.37	69.75	51.91	69.54	20.29	28.98	19.66	28.98
7	88	53.00	68.14	50.60	67.94	19.78	28.31	19.16	28.31
6	74	51.46	66.33	49.12	66.13	19.20	27.56	18.61	27.56
5	60	49.69	64.26	47.44	64.07	18.54	26.70	17.97	26.70
4	46	47.60	61.81	45.44	61.62	17.76	25.68	17.21	25.68
3	32	44.98	58.74	42.94	58.57	16.79	24.41	16.26	24.41
2	18	47.26	62.28	45.12	62.09	17.64	25.88	17.09	25.88
Base	0	878.18	1131.51	839.50	1128.26	329.11	470.62	319.23	470.62

## B.1.2 Seismic Forces

### B.1.2.1 Effective Seismic Weights and Story Gravity Forces

Table B-4 through Table B-6 provide the effective seismic weights lumped at each story as well as the lumped gravity force acting on each story for each building design. The gravity force is computed using the two load combinations as discussed in Chapter 2.

**Table B-4. Effect Seismic Weights and Story Gravity Forces, MC4 (kips)**

Level, $x$	RSA			ELF		
	$w_x^1$	$P_{story}^2$	$P_x^3$	$w_x^1$	$P_{story}^2$	$P_x^3$
Roof	1091	1309	1091	1095	1314	1095
4	1339	2925	2470	1345	2936	2479
3	1346	4547	3854	1359	4574	3877
2	1364	6192	5257	1377	6235	5293
Total	5140	-	-	5176	-	-

1. Inertial weight computed from Dead + Superimposed Dead + 0.2×Floor Live
2. Computed from 1.2×Dead + 1.2×Superimposed Dead + 0.25×Floor Live gravity load
3. Computed from Dead + Superimposed Dead + 0.25×Floor Live gravity load

**Table B-5. Effect Seismic Weights and Story Gravity Forces, MC8 (kips)**

Level, $x$	RSA			ELF		
	$w_x^1$	$P_{story}^2$	$P_x^3$	$w_x^1$	$P_{story}^2$	$P_x^3$
Roof	1081	1297	1081	1084	1300	1083
8	1324	2893	2443	1328	2901	2450
7	1333	4501	3815	1346	4525	3835
6	1338	6114	5192	1355	6158	5229
5	1349	7741	6580	1364	7803	6631
4	1353	9373	7973	1368	9452	8038
3	1367	11021	9378	1380	11115	9457
2	1390	12697	10807	1402	12806	10898
Total	10536	-	-	10627	-	-

1. Inertial weight computed from Dead + Superimposed Dead + 0.2×Floor Live
2. Computed from 1.2×Dead + 1.2×Superimposed Dead + 0.25×Floor Live gravity load
3. Computed from Dead + Superimposed Dead + 0.25×Floor Live gravity load

**Table B-6. Effect Seismic Weights and Story Gravity Forces, MC16 (kips)**

Level, $x$	RSA			ELF		
	$w_x^1$	$P_{story}^2$	$P_x^3$	$w_x^1$	$P_{story}^2$	$P_x^3$
Roof	1083	1296	1080	1083	1297	1081
16	1327	2893	2444	1327	2895	2444
15	1332	4496	3812	1342	4509	3822
14	1337	6105	5184	1349	6133	5208
13	1349	7728	6570	1357	7766	6601
12	1354	9358	7960	1360	9403	7997
11	1359	10993	9355	1366	11046	9399
10	1363	12634	10754	1370	12695	10806
9	1370	14282	12160	1379	14355	12221
8	1374	15936	13570	1384	16020	13641
7	1379	17595	14986	1389	17691	15066
6	1384	19260	16406	1394	19369	16496
5	1395	20939	17837	1402	21056	17935
4	1403	22627	19276	1410	22754	19381
3	1414	24328	20726	1425	24469	20843
2	1445	26067	22207	1462	26227	22341
Total	21667	-	-	21800	-	-

1. Inertial weight computed from Dead + Superimposed Dead + 0.2×Floor Live
2. Computed from 1.2×Dead + 1.2×Superimposed Dead + 0.25×Floor Live gravity load
3. Computed from Dead + Superimposed Dead + 0.25×Floor Live gravity load

### B.1.2.2 Horizontal Seismic Forces, E-W Direction

#### B.1.2.2.1 MC4 (Special Moment Frame)

Table B-7 and Table B-8 provide the horizontal seismic forces and story shears for each building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-1 through Figure B-3. In these tables,  $F_x$  represents the seismic forces acting in the E-W direction only.. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-7. Seismic Strength Design Forces, E-W MC4**

Level, $x$	RSA		ELF			Wind (700-Year)	
	$F_x$ (kips)	$V_i$ (kips)	$F_x$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_x$ (kips)	$V_i$ (kips)
Roof	145	145	138	138	1.05	36	36
4	68	213	121	259	0.82	35	72
3	46	259	77	336	0.77	33	105
2	56	316	38	374	0.84	34	139




Figure B-1. Strength Design Lateral Forces and Story Shears

Table B-8. Seismic Drift Forces, E-W MC4

Level, $x$	$F_x$ (kips)	$V_i$ (kips)	RSA			ELF			Wind (10-Year)			
			$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)
Roof	76	76	11.82	1.88	0.011	89	89	12.13	2.28	0.014	15	15
4	36	112	9.94	2.73	0.016	70	159	9.85	3.00	0.018	14	29
3	24	136	7.21	3.39	0.020	39	198	6.85	3.33	0.020	13	42
2	30	166	3.82	3.82	0.018	15	213	3.51	3.51	0.016	14	55





Figure B-2. Drift Design Lateral Forces and Story Shears



**Figure B-3. Story Drift Ratios and Deflected Shape**

Table B-9 and Table B-10 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and ASCE §12.8.7 for each archetype building design. The following formulas were used in these calculations—see ASCE 7, where  $\delta$  is the story drift and  $\Delta$  is the story drift ratio as defined in ASCE 7.

$$\delta_x = \frac{C_d \delta_{xe}}{I_e} \quad (\text{B-1})$$

$$\Delta_i = \delta_x - \delta_{x-1} = \frac{C_d}{I_e} (\delta_{xe} - \delta_{(x-1)e}) \quad (\text{B-2})$$

$$\theta_{2i} = \frac{P_x \Delta_i I_e}{V_i h_{sx} C_d} = \frac{P_x (\delta_{xe} - \delta_{(x-1)e})}{V_i h_{sx}} \quad (\text{B-3})$$

$$\theta_{1i} = \frac{\theta_{2i}}{1 + \theta_{2i}} \quad (\text{B-4})$$

**Table B-9. ASCE 7 Allowable Drift and Stability Verification, E-W MC4 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	418	1091	1.88	168	0.011	0.029	0.028	0.39	0.232
4	615	2470	2.73	168	0.016	0.065	0.061	0.54	0.168
3	749	3854	3.39	168	0.020	0.104	0.094	0.63	0.143
2	911	5257	3.82	216	0.018	0.102	0.093	0.70	0.129

**Table B-10. ASCE 7 Allowable Drift and Stability Verification, E-W MC4 ELF**


Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	488	1095	2.28	168	0.014	0.030	0.030	0.39	0.231
4	874	2479	3.00	168	0.018	0.051	0.048	0.44	0.208
3	1088	3877	3.33	168	0.020	0.071	0.066	0.50	0.183
2	1171	5293	3.51	216	0.016	0.074	0.069	0.53	0.172

B.1.2.2.2 MC8 (Special Moment Frame)

Table B-11 and Table B-12 provide the horizontal seismic forces and story shears for each archetype building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-4 through Figure B-6. In these tables,  $F_x$  represents the seismic forces acting in the E-W direction only. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-11. Seismic Strength Design Forces, E-W MC8**


Level, $x$	RSA		ELF			Wind (700-Year)	
	$F_x$ (kips)	$V_i$ (kips)	$F_x$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_x$ (kips)	$V_i$ (kips)
Roof	135	135	108	108	1.25	46	46
8	57	192	108	216	0.89	49	96
7	39	231	86	302	0.77	48	143
6	37	268	65	367	0.73	46	190
5	31	299	47	413	0.72	45	235
4	26	326	30	444	0.73	43	277
3	31	357	17	460	0.77	40	318
2	37	394	7	467	0.84	42	359




**Figure B-4. Strength Design Lateral Forces and Story Shears**

**Table B-12. Seismic Drift Forces, E-W MC8**

Level, $x$	$F_x$ (kips)	$V_i$ (kips)	RSA			ELF					Wind (10-Year)	
			$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)
Roof	66	66	21.48	1.84	0.011	71	71	22.95	2.25	0.013	18	18
8	28	93	19.64	2.38	0.014	68	139	20.70	2.83	0.017	19	37
7	19	112	17.26	2.75	0.016	51	190	17.87	2.81	0.017	18	55
6	18	131	14.52	2.92	0.017	36	226	15.06	3.00	0.018	17	73
5	15	146	11.59	2.90	0.017	24	250	12.06	3.06	0.018	17	89
4	13	159	8.69	2.99	0.018	14	264	9.00	3.11	0.019	16	105
3	15	174	5.70	2.86	0.017	7	271	5.89	2.96	0.018	15	121
2	18	192	2.84	2.84	0.013	2	273	2.93	2.93	0.014	16	136




(a) Lateral forces




(b) Story Shears

**Figure B-5. Drift Design Lateral Forces and Story Shears**



(a) Story Drift ratios at Center of Mass



(b) Floor Displacements at Center of Mass

**Figure B-6. Story Drift Ratios and Deflected Shape**

Table B-13 and Table B-14 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and §12.8.7 for each archetype building design.

**Table B-13. ASCE 7 Allowable Drift and Stability Verification, E-W MC8 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_i$	$\beta_i$	$\theta_{max,i}$
ROOF	361	1081	1.84	168	0.011	0.033	0.032	0.53	0.172
8	513	2443	2.38	168	0.014	0.067	0.063	0.68	0.134
7	619	3815	2.75	168	0.016	0.101	0.092	0.67	0.136
6	718	5192	2.92	168	0.017	0.126	0.112	0.71	0.128
5	801	6580	2.90	168	0.017	0.142	0.124	0.62	0.147
4	872	7973	2.99	168	0.018	0.163	0.140	0.63	0.145
3	956	9378	2.86	168	0.017	0.167	0.143	0.60	0.151
2	1055	10807	2.84	216	0.013	0.135	0.119	0.60	0.152

**Table B-14. ASCE 7 Allowable Drift and Stability Verification, E-W MC8 ELF**


Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_i$	$\beta_i$	$\theta_{max,i}$
ROOF	392	1083	2.25	168	0.013	0.037	0.036	0.37	0.246
8	763	2450	2.83	168	0.017	0.054	0.051	0.51	0.180
7	1043	3835	2.81	168	0.017	0.062	0.058	0.43	0.210
6	1243	5229	3.00	168	0.018	0.075	0.070	0.48	0.190
5	1375	6631	3.06	168	0.018	0.088	0.081	0.46	0.199
4	1453	8038	3.11	168	0.019	0.102	0.093	0.48	0.190
3	1491	9457	2.96	168	0.018	0.112	0.101	0.47	0.192
2	1503	10898	2.93	216	0.014	0.098	0.089	0.45	0.200

B.1.2.2.3 MC16 (Special Moment Frame)

Table B-15 and Table B-16 provide the horizontal seismic forces and story shears for each archetype building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-7 through Figure B-9. In these tables,  $F_x$  represents the seismic forces acting in the E-W direction only. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-15. Summary of Seismic Strength Design Forces, E-W MC16**


Level, x	RSA		ELF			Wind (700-Year)	
	$F_x$ (kips)	$V_i$ (kips)	$F_x$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_x$ (kips)	$V_i$ (kips)
Roof	196	196	133	133	1.47	57	57
16	95	292	144	278	1.05	62	119
15	54	346	127	405	0.85	61	180
14	46	391	111	515	0.76	61	241
13	45	436	95	611	0.71	60	301
12	41	477	80	691	0.69	59	360
11	33	510	67	758	0.67	58	417
10	31	541	55	813	0.67	57	474
9	33	573	44	857	0.67	56	530
8	33	607	34	891	0.68	54	584
7	29	636	26	917	0.69	53	637
6	26	662	18	935	0.71	51	689
5	29	691	12	947	0.73	50	738
4	38	729	7	954	0.76	48	786
3	44	773	3	957	0.81	45	831
2	37	810	1	958	0.85	47	878




**Figure B-7. Strength Design Lateral Forces and Story Shears**

**Table B-16. Summary of Seismic Drift Forces, E-W MC16**

Level, x	RSA					ELF					Wind (10-Year)	
	$F_x$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_x$ (kips)	$V_i$ (kips)
Roof	71	71	29.39	1.28	0.008	52	52	38.12	1.76	0.010	23	23
16	35	106	28.11	1.69	0.010	56	109	36.36	2.16	0.013	23	46
15	20	126	26.42	2.00	0.012	50	158	34.20	2.30	0.014	23	69
14	17	142	24.42	2.02	0.012	43	202	31.89	2.51	0.015	23	91
13	16	159	22.41	1.89	0.011	37	239	29.39	2.62	0.016	22	114
12	15	174	20.51	1.99	0.012	31	270	26.77	2.81	0.017	22	136
11	12	186	18.52	2.09	0.012	26	296	23.96	2.92	0.017	22	157
10	11	197	16.43	2.10	0.012	21	318	21.05	2.84	0.017	21	178
9	12	209	14.33	2.04	0.012	17	335	18.21	2.64	0.016	21	199
8	12	221	12.29	2.07	0.012	13	348	15.57	2.60	0.015	20	219
7	11	232	10.22	2.07	0.012	10	358	12.97	2.57	0.015	20	239
6	9	241	8.15	1.94	0.012	7	365	10.40	2.51	0.015	19	258
5	11	252	6.21	1.75	0.010	5	370	7.89	2.37	0.014	19	277
4	14	266	4.47	1.67	0.010	3	373	5.52	2.20	0.013	18	295
3	16	282	2.80	1.49	0.009	1	374	3.32	1.83	0.011	17	311
2	13	295	1.31	1.31	0.006	0	375	1.49	1.49	0.007	18	329




(a) Lateral forces



(b) Story Shears

**Figure B-8. Drift Design Lateral Forces and Story Shears**



**Figure B-9. Story Drift Ratios and Deflected Shape**

Table B-17 and Table B-18 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and ASCE 7 §12.8.7 for each building design.

**Table B-17. ASCE 7 Allowable Drift and Stability Verification, E-W MC16 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_i$	$\beta_i$	$\theta_{max,i}$
ROOF	392	1080	1.28	168	0.008	0.021	0.021	0.52	0.173
16	583	2444	1.69	168	0.010	0.042	0.040	0.68	0.133
15	692	3812	2.00	168	0.012	0.066	0.062	0.78	0.116
14	783	5184	2.02	168	0.012	0.079	0.074	0.81	0.112
13	874	6570	1.89	168	0.011	0.085	0.078	0.65	0.139
12	956	7960	1.99	168	0.012	0.099	0.090	0.67	0.137
11	1022	9355	2.09	168	0.012	0.114	0.102	0.68	0.134
10	1084	10754	2.10	168	0.012	0.124	0.110	0.68	0.134
9	1149	12160	2.04	168	0.012	0.129	0.114	0.67	0.135
8	1216	13570	2.07	168	0.012	0.138	0.121	0.67	0.135
7	1275	14986	2.07	168	0.012	0.145	0.126	0.68	0.133
6	1327	16406	1.94	168	0.012	0.143	0.125	0.68	0.134
5	1386	17837	1.75	168	0.010	0.134	0.118	0.63	0.143
4	1462	19276	1.67	168	0.010	0.131	0.116	0.61	0.149
3	1549	20726	1.49	168	0.009	0.118	0.106	0.60	0.150
2	1622	22207	1.31	216	0.006	0.083	0.077	0.54	0.169

**Table B-18. ASCE 7 Allowable Drift and Stability Verification, E-W MC16 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	287	1081	1.76	168	0.010	0.040	0.038	0.47	0.194
16	597	2444	2.16	168	0.013	0.053	0.050	0.61	0.150
15	870	3822	2.30	168	0.014	0.060	0.057	0.58	0.157
14	1108	5208	2.51	168	0.015	0.070	0.065	0.64	0.142
13	1313	6601	2.62	168	0.016	0.078	0.073	0.69	0.131
12	1486	7997	2.81	168	0.017	0.090	0.082	0.74	0.123
11	1630	9399	2.92	168	0.017	0.100	0.091	0.78	0.117
10	1748	10806	2.84	168	0.017	0.104	0.095	0.78	0.116
9	1843	12221	2.64	168	0.016	0.104	0.094	0.71	0.128
8	1916	13641	2.60	168	0.015	0.110	0.099	0.69	0.131
7	1971	15066	2.57	168	0.015	0.117	0.105	0.71	0.127
6	2010	16496	2.51	168	0.015	0.123	0.109	0.72	0.126
5	2036	17935	2.37	168	0.014	0.124	0.110	0.75	0.121
4	2051	19381	2.20	168	0.013	0.124	0.110	0.73	0.125
3	2058	20843	1.83	168	0.011	0.110	0.099	0.71	0.128
2	2061	22341	1.49	216	0.007	0.075	0.069	0.59	0.154

### B.1.2.3 Horizontal Seismic Forces, N-S Direction

#### B.1.2.3.1 MC4 (Special Concentrically Braced Frame)

Table B-19 and Table B-20 provide the horizontal seismic forces and story shears for each archetype building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-10 through Figure B-12. In these tables,  $F_y$  represents the seismic forces acting in the N-S direction only. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-19. Summary of Seismic Strength Design Forces, N-S MC4**

Level, $x$	RSA		ELF			Wind (700-Year)	
	$F_y$ (kips)	$V_i$ (kips)	$F_y$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_y$ (kips)	$V_i$ (kips)
Roof	261	261	293	293	0.89	36	36
4	219	480	272	565	0.85	35	72
3	153	633	188	753	0.84	33	105
2	91	723	104	857	0.84	34	139




Figure B-10. Strength Design Lateral Forces and Story Shears

Table B-20. Summary of Seismic Drift Forces, N-S MC4

Level, x	$F_y$ (kips)	$V_i$ (kips)	RSA			ELF			Wind (10-Year)			
			$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)
Roof	226	226	4.88	1.02	0.006	270	270	5.41	1.20	0.007	15	15
4	190	416	3.85	1.22	0.007	249	519	4.21	1.51	0.009	14	29
3	132	549	2.63	1.28	0.008	170	689	2.70	1.31	0.008	13	42
2	78	627	1.35	1.35	0.006	93	782	1.39	1.39	0.006	14	55





Figure B-11. Drift Design Lateral Forces and Story Shears



**Figure B-12. Story Drift Ratios and Deflected Shape**

Table B-21 and Table B-22 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and ASCE §12.8.7 for each archetype building design.

**Table B-21. ASCE 7 Allowable Drift and Stability Verification, N-S MC4 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	1130	1091	1.02	168	0.006	0.006	0.006	1.00	0.100
4	2082	2470	1.22	168	0.007	0.009	0.009	1.00	0.100
3	2743	3854	1.28	168	0.008	0.011	0.011	1.00	0.100
2	3135	5257	1.35	216	0.006	0.010	0.010	1.00	0.100

**Table B-22. ASCE 7 Allowable Drift and Stability Verification, N-S MC4 ELF**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	1351	1095	1.20	168	0.007	0.006	0.006	1.00	0.100
4	2597	2479	1.51	168	0.009	0.009	0.008	1.00	0.100
3	3446	3877	1.31	168	0.008	0.009	0.009	1.00	0.100
2	3909	5293	1.39	216	0.006	0.009	0.009	1.00	0.100


### B.1.2.3.2 MC8 (Special Concentrically Braced Frame)

Table B-23 and Table B-24 provide the horizontal seismic forces and story shears for each archetype building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-13 through Figure B-15. In these tables,  $F_y$  represents the seismic forces acting in

the N-S direction only. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-23. Summary of Seismic Strength Design Forces, N-S MC8**

Level, $x$	RSA		ELF			Wind (700-Year)	
	$F_y$ (kips)	$V_i$ (kips)	$F_y$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_y$ (kips)	$V_i$ (kips)
Roof	239	239	216	216	1.11	46	46
8	174	414	225	441	0.94	49	96
7	94	508	190	631	0.80	48	143
6	59	566	154	785	0.72	46	190
5	70	636	119	904	0.70	45	235
4	93	729	86	990	0.74	43	277
3	100	829	55	1045	0.79	40	318
2	76	904	27	1073	0.84	42	359



**Figure B-13. Strength Design Lateral Forces and Story Shears**

**Table B-24. Summary of Seismic Drift Forces, N-S MC8**

Level, $x$	$F_y$ (kips)	$V_i$ (kips)	RSA			ELF					Wind (10-Year)	
			$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)
Roof	168	168	10.93	1.51	0.009	161	161	14.59	2.03	0.012	18	18
8	122	290	9.42	1.62	0.010	163	324	12.56	2.23	0.013	19	37
7	66	356	7.79	1.68	0.010	133	458	10.33	2.17	0.013	18	55
6	41	397	6.12	1.54	0.009	104	562	8.16	1.99	0.012	17	73
5	49	446	4.58	1.37	0.008	77	638	6.17	2.00	0.012	17	89
4	65	511	3.20	1.10	0.007	52	690	4.17	1.57	0.009	16	105
3	70	581	2.11	1.04	0.006	31	721	2.60	1.39	0.008	15	121
2	53	633	1.06	1.06	0.005	13	735	1.22	1.22	0.006	16	136




Figure B-14. Drift Design Lateral Forces and Story Shears




Figure B-15. Story Drift Ratios and Deflected Shape

Table B-25 and Table B-26 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and ASCE §12.8.7 for each archetype building design.

**Table B-25. ASCE 7 Allowable Drift and Stability Verification, N-S MC8 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	838	1081	1.51	168	0.009	0.012	0.011	1.00	0.100
8	1449	2443	1.62	168	0.010	0.016	0.016	1.00	0.100
7	1778	3815	1.68	168	0.010	0.021	0.021	1.00	0.100
6	1985	5192	1.54	168	0.009	0.024	0.023	1.00	0.100
5	2229	6580	1.37	168	0.008	0.024	0.024	1.00	0.100
4	2555	7973	1.10	168	0.007	0.020	0.020	1.00	0.100
3	2903	9378	1.04	168	0.006	0.020	0.020	1.00	0.100
2	3167	10807	1.06	216	0.005	0.017	0.017	1.00	0.100

**Table B-26. ASCE 7 Allowable Drift and Stability Verification, N-S MC8 ELF**


Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	805	1083	2.03	168	0.012	0.016	0.016	1.00	0.100
8	1622	2450	2.23	168	0.013	0.020	0.020	1.00	0.100
7	2288	3835	2.17	168	0.013	0.022	0.021	1.00	0.100
6	2808	5229	1.99	168	0.012	0.022	0.022	1.00	0.100
5	3192	6631	2.00	168	0.012	0.025	0.024	1.00	0.100
4	3452	8038	1.57	168	0.009	0.022	0.021	1.00	0.100
3	3606	9457	1.39	168	0.008	0.022	0.021	1.00	0.100
2	3673	10898	1.22	216	0.006	0.017	0.016	1.00	0.100

B.1.2.3.3 MC16 (Special Concentrically Braced Frame)


Table B-27 and Table B-28 provide the horizontal seismic forces and story shears for each archetype building design for the seismic strength analysis and the drift analysis. The data are also graphically illustrated in Figure B-16 through Figure B-18. In these tables,  $F_y$  represents the seismic forces acting in the N-S direction only. The equivalent story forces for the RSA design are backed out from the story shears computed via a modal combination procedure. Although not theoretically correct, the forces provide a comparison basis for evaluating variations in the vertical distribution.

**Table B-27. Summary of Seismic Strength Design Forces, N-S MC16**

Level, $x$	RSA		ELF			Wind (700-Year)	
	$F_y$ (kips)	$V_i$ (kips)	$F_y$ (kips)	$V_i$ (kips)	$V_{ELF} / V_{RSA}$	$F_y$ (kips)	$V_i$ (kips)
Roof	190	190	159	159	1.19	57	57
16	172	362	177	336	1.08	62	119
15	115	477	161	497	0.96	61	180
14	73	550	144	641	0.86	61	241
13	45	595	128	769	0.77	60	301
12	33	628	112	881	0.71	59	360
11	31	658	98	979	0.67	58	417
10	33	692	83	1062	0.65	57	474
9	41	733	70	1132	0.65	56	530
8	50	783	57	1190	0.66	54	584
7	58	841	46	1235	0.68	53	637
6	66	907	35	1270	0.71	51	689
5	68	975	25	1296	0.75	50	738
4	62	1037	17	1312	0.79	48	786
3	50	1087	10	1322	0.82	45	831
2	33	1120	4	1326	0.84	47	878



(a) Lateral forces




(b) Story Shears


Figure B-16. Strength Design Lateral Forces and Story Shears

Table B-28. Summary of Seismic Drift Forces, N-S MC16

Level, x	RSA					ELF					Wind (10-Year)	
	$F_y$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)	$\delta_x$ (inch)	$\Delta_i$ (inch)	$\Delta_i / h_{sx}$	$F_y$ (kips)	$V_i$ (kips)
Roof	160	160	16.00	1.01	0.006	142	142	24.43	1.53	0.009	23	23
16	145	305	15.00	1.15	0.007	155	296	22.90	1.78	0.011	23	46
15	97	402	13.84	1.21	0.007	139	435	21.12	1.91	0.011	23	69
14	62	464	12.63	1.23	0.007	122	557	19.20	1.99	0.012	23	91
13	38	502	11.41	1.12	0.007	107	664	17.21	1.89	0.011	22	114
12	28	530	10.29	1.08	0.006	92	757	15.32	1.82	0.011	22	136
11	26	555	9.21	1.08	0.006	78	835	13.50	1.74	0.010	22	157
10	28	584	8.13	1.05	0.006	65	900	11.76	1.65	0.010	21	178
9	35	619	7.08	1.05	0.006	54	954	10.11	1.63	0.010	21	199
8	42	661	6.03	1.01	0.006	43	997	8.48	1.53	0.009	20	219
7	49	710	5.02	0.93	0.006	33	1030	6.95	1.48	0.009	20	239
6	55	766	4.09	0.89	0.005	24	1054	5.47	1.36	0.008	19	258
5	57	823	3.20	0.91	0.005	17	1071	4.11	1.29	0.008	19	277
4	53	875	2.29	0.84	0.005	10	1082	2.82	1.11	0.007	18	295
3	42	917	1.45	0.69	0.004	6	1087	1.71	0.86	0.005	17	311
2	28	945	0.76	0.76	0.004	2	1089	0.84	0.84	0.004	18	329




(a) Lateral forces




(b) Story Shears

**Figure B-17. Drift Design Lateral Forces and Story Shears**



(a) Story Drift ratios at Center of Mass



(b) Floor Displacements at Center of Mass

**Figure B-18. Story Drift Ratios and Deflected Shape**

Table B-29 and Table B-30 provide the tabulated data for verifying the allowable story drifts and the seismic stability coefficient per ASCE 7 §12.8.6 and §12.8.7 for each archetype building design.

**Table B-29. ASCE 7 Allowable Drift and Stability Verification, N-S MC16 RSA**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	800	1080	1.01	168	0.006	0.008	0.008	1.00	0.100
16	1524	2444	1.15	168	0.007	0.011	0.011	1.00	0.100
15	2010	3812	1.21	168	0.007	0.014	0.013	1.00	0.100
14	2320	5184	1.23	168	0.007	0.016	0.016	1.00	0.100
13	2508	6570	1.12	168	0.007	0.017	0.017	1.00	0.100
12	2646	7960	1.08	168	0.006	0.019	0.019	1.00	0.100
11	2775	9355	1.08	168	0.006	0.022	0.021	1.00	0.100
10	2916	10754	1.05	168	0.006	0.023	0.022	1.00	0.100
9	3090	12160	1.05	168	0.006	0.025	0.024	1.00	0.100
8	3302	13570	1.01	168	0.006	0.025	0.024	1.00	0.100
7	3548	14986	0.93	168	0.006	0.023	0.023	1.00	0.100
6	3824	16406	0.89	168	0.005	0.023	0.022	1.00	0.100
5	4109	17837	0.91	168	0.005	0.023	0.023	1.00	0.100
4	4372	19276	0.84	168	0.005	0.022	0.021	1.00	0.100
3	4581	20726	0.69	168	0.004	0.019	0.018	1.00	0.100
2	4721	22207	0.76	216	0.004	0.017	0.016	1.00	0.100

**Table B-30. ASCE 7 Allowable Drift and Stability Verification, N-S MC16 ELF**

Level, $x$	$V_i \times C_d$ (kips)	$P_x$ (kips)	$\Delta_i$ (inch)	$h_{sx}$ (inch)	$\Delta_i / h_{sx}$	$\theta_{2i}$	$\theta_{1i}$	$\beta_i$	$\theta_{max,i}$
ROOF	706	1080	1.52	168	0.009	0.014	0.014	1.00	0.100
16	1479	2444	1.78	168	0.011	0.017	0.017	1.00	0.100
15	2170	3821	1.91	168	0.011	0.020	0.020	1.00	0.100
14	2782	5206	1.99	168	0.012	0.022	0.022	1.00	0.100
13	3316	6598	1.88	168	0.011	0.022	0.022	1.00	0.100
12	3775	7994	1.82	168	0.011	0.023	0.022	1.00	0.100
11	4167	9396	1.74	168	0.010	0.023	0.023	1.00	0.100
10	4493	10802	1.65	168	0.010	0.024	0.023	1.00	0.100
9	4762	12217	1.63	168	0.010	0.025	0.024	1.00	0.100
8	4975	13636	1.53	168	0.009	0.025	0.024	1.00	0.100
7	5140	15061	1.47	168	0.009	0.026	0.025	1.00	0.100
6	5261	16491	1.36	168	0.008	0.025	0.025	1.00	0.100
5	5345	17929	1.29	168	0.008	0.026	0.025	1.00	0.100
4	5398	19375	1.11	168	0.007	0.024	0.023	1.00	0.100
3	5425	20836	0.86	168	0.005	0.020	0.019	1.00	0.100
2	5435	22334	0.84	216	0.004	0.016	0.016	1.00	0.100

## B.2 Horizontal and Vertical Irregularities

### B.2.1 Special Moment Frame

Table B-31 through Table B-34 provide the results for the horizontal (type 1) and vertical (type 1 and 5) irregularity verifications.

**Table B-31. Horizontal Irregularity Type 1 (a and b) Verification**

Floor (x)	$\Delta_{max} / \Delta_{avg}^{-1}$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof	-	-	-	-	1.015	1.012
16	-	-	-	-	1.011	1.009
15	-	-	-	-	1.012	1.008
14	-	-	-	-	1.011	1.007
13	-	-	-	-	1.010	1.008
12	-	-	-	-	1.010	1.007
11	-	-	-	-	1.009	1.007
10	-	-	-	-	1.009	1.007
9	-	-	1.016	1.011	1.008	1.007
8	-	-	1.013	1.009	1.009	1.007
7	-	-	1.012	1.008	1.008	1.006
6	-	-	1.011	1.007	1.008	1.007
5	1.007	1.006	1.009	1.006	1.007	1.006
4	1.006	1.004	1.008	1.005	1.007	1.007
3	1.005	1.004	1.008	1.006	1.011	1.009
2	1.004	1.003	1.006	1.004	1.004	1.005

1. Values include accidental torsion with  $A_T = 1.0$ .

**Table B-32. Vertical Irregularity Type 1 (a and b) Verification (Exception 1)**

Floor (x)	$(\Delta / h_{sx})_x / (\Delta / h_{sx})_{x+1}^{-1}$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof	-	-	-	-	-	-
16	-	-	-	-	1.22	1.27
15	-	-	-	-	1.07	1.13
14	-	-	-	-	1.09	0.97
13	-	-	-	-	1.04	0.89
12	-	-	-	-	1.07	1.02
11	-	-	-	-	1.04	1.02
10	-	-	-	-	0.97	0.98
9	-	-	-	-	0.93	0.95
8	-	-	1.26	1.20	0.99	1.00
7	-	-	0.99	1.07	0.99	0.98
6	-	-	1.07	1.02	0.98	0.93
5	-	-	1.02	0.95	0.94	0.88
4	1.32	1.35	1.02	1.00	0.93	0.94
3	1.11	1.19	0.95	0.94	0.83	0.90
2	0.82	0.67	0.77	0.60	0.63	0.67

1.  $\Delta$  is taken at the center of mass per ASCE 7 §12.8.6.

$$V_{y,i} = \frac{2 \sum_{j=1}^n M_{pr,j}}{h} \quad (\text{B-5})$$

$$h = \frac{h_{sx} + h_{sx+1}}{2} \quad (\text{B-6})$$

**Table B-33. Vertical Irregularity Type 5 (a and b) Verification, ELF (kip, feet)**

Floor (x)	$h^c$	MC4			MC8			MC16		
		$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$	$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$	$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$
Roof MC16	7	-	-	-	-	-	-	491.1	421.0	-
16	14	-	-	-	-	-	-	491.1	210.5	0.50
15	14	-	-	-	-	-	-	951.8	407.9	1.94
14	14	-	-	-	-	-	-	951.8	407.9	1.00
13	14	-	-	-	-	-	-	1242.1	532.3	1.31
12	14	-	-	-	-	-	-	1242.1	532.3	1.00
11	14	-	-	-	-	-	-	1242.1	532.3	1.00
10	14	-	-	-	-	-	-	1242.1	532.3	1.00
9 (Roof MC8)	14 / 7	-	-	-	491.1	421.0	-	1662.3	712.4	1.34
8	14	-	-	-	491.1	210.5	0.50	1662.3	712.4	1.00
7	14	-	-	-	951.8	407.9	1.94	1662.3	712.4	1.00
6	14	-	-	-	951.8	407.9	1.00	1662.3	712.4	1.00
5 (Roof MC4)	14 / 7	491.1	421.0	-	1161.6	497.8	1.22	1662.3	712.4	1.00
4	14	679.7	291.3	0.69	1161.6	497.8	1.00	1662.3	712.4	1.00
3	14	754.6	323.4	1.11	1161.6	497.8	1.00	1662.3	712.4	1.00
2	16	754.6	283.0	0.88	1161.6	435.6	0.88	1662.3	623.3	0.88

a.  $M_{pr}$  is for a single beam plastic hinge at the center of the RBS.  
b.  $V_{y,x}$  is computed neglecting the plastic moment strength of the adjacent columns.  
c.  $h$  is taken as the distance from mid-height of a story to mid-height of the story above ( $\neq h_{sx}$ ).

**Table B-34. Vertical Irregularity Type 5 (a and b) Verification, RSA (kip, feet)**

Floor (x)	$h^c$	MC4			MC8			MC16		
		$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$	$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$	$M_{pr}^a$	$V_{y,x}^b$	$V_{y,x+1} / V_{y,x}$
Roof MC16	7	-	-	-	-	-	-	491.1	421.0	-
16	14	-	-	-	-	-	-	491.1	210.5	0.50
15	14	-	-	-	-	-	-	491.1	210.5	1.00
14	14	-	-	-	-	-	-	491.1	210.5	1.00
13	14	-	-	-	-	-	-	951.8	407.9	1.94
12	14	-	-	-	-	-	-	951.8	407.9	1.00
11	14	-	-	-	-	-	-	951.8	407.9	1.00
10	14	-	-	-	-	-	-	951.8	407.9	1.00
9 (Roof MC8)	14 / 7	-	-	-	358.7	307.5	-	1242.1	532.3	1.31
8	14	-	-	-	358.7	153.7	0.50	1242.1	532.3	1.00
7	14	-	-	-	491.1	210.5	1.37	1242.1	532.3	1.00
6	14	-	-	-	491.1	210.5	1.00	1242.1	532.3	1.00
5 (Roof MC4)	14 / 7	491.1	421.0	-	679.7	291.3	1.38	1662.3	712.4	1.34
4	14	491.1	210.5	0.50	679.7	291.3	1.00	1662.3	712.4	1.00
3	14	491.1	210.5	1.00	754.6	323.4	1.11	1662.3	712.4	1.00
2	16	491.1	184.2	0.88	754.6	283.0	0.88	1662.3	623.3	0.88

a.  $M_{pr}$  is for a single beam plastic hinge at the center of the RBS.  
b.  $V_{y,x}$  is computed neglecting the plastic moment strength of the adjacent columns.  
c.  $h$  is taken as the distance from mid-height of a story to mid-height of the story above ( $\neq h_{sx}$ ).

## B.2.2 Special Concentrically Braced Frame

Table B-35 through Table B-38 provide the results for the horizontal (type 1) and vertical (type 1 and 5) irregularity verifications.

**Table B-35. Horizontal Irregularity Type 1 (a and b) Verification**

Floor (x)	$\Delta_{max} / \Delta_{avg}^a$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof MC16	-	-	-	-	1.097	1.100
16	-	-	-	-	1.073	1.071
15	-	-	-	-	1.072	1.086
14	-	-	-	-	1.079	1.075
13	-	-	-	-	1.077	1.083
12	-	-	-	-	1.073	1.073
11	-	-	-	-	1.089	1.089
10	-	-	-	-	1.063	1.073
9 (Roof MC8)	-	-	1.079	1.084	1.098	1.094
8	-	-	1.081	1.086	1.060	1.070
7	-	-	1.073	1.077	1.102	1.097
6	-	-	1.073	1.082	1.057	1.060
5 (Roof MC4)	1.078	1.096	1.084	1.083	1.103	1.105
4	1.071	1.056	1.069	1.075	1.059	1.056
3	1.040	1.064	1.089	1.091	1.127	1.129
2	1.044	1.045	1.076	1.078	1.077	1.080

a. Values include accidental torsion with  $A_x = 1.0$ .

**Table B-36. Vertical Irregularity Type 1 (a and b) Verification (Using Exception 1)**

Floor (x)	$(\Delta / h_{sx})_x / (\Delta / h_{sx})_{x+1}^a$					
	MC4		MC8		MC16	
	ELF	RSA	ELF	RSA	ELF	RSA
Roof	-	-	-	-	-	-
16	-	-	-	-	1.17	1.20
15	-	-	-	-	1.07	1.08
14	-	-	-	-	1.04	1.02
13	-	-	-	-	0.95	0.91
12	-	-	-	-	0.97	0.94
11	-	-	-	-	0.96	1.00
10	-	-	-	-	0.95	0.94
9	-	-	-	-	0.99	0.99
8	-	-	1.10	1.11	0.94	0.93
7	-	-	0.97	1.03	0.96	0.91
6	-	-	0.92	0.91	0.92	0.93
5	-	-	1.00	0.88	0.95	1.01
4	1.26	1.14	0.79	0.77	0.86	0.91
3	0.87	1.02	0.88	0.93	0.78	0.82
2	0.83	0.63	0.68	0.61	0.76	0.85

a.  $\Delta$  is taken at the center of mass per ASCE 7 §12.8.6.

$$V_{y,i} = (P_{br,C} + P_{br,T}) \frac{b}{2\sqrt{\left(\frac{b}{2}\right)^2 + h_{sx}^2}} \quad (\text{B-7})$$

[ $b = 20$  ft. for MC4 and MC8,  $b = 30$  ft. for MC16]

**Table B-37. Vertical Irregularity Type 5 (a and b) Verification, ELF (kip, feet)**

Floor (x)	$h_{sx}$	MC4				MC8				MC16			
		$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$	$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$	$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$
Roof MC16	14	-	-	-	-	-	-	-	-	99.4	255.9	259.7	-
16	14	-	-	-	-	-	-	-	-	99.4	255.9	259.7	1.00
15	14	-	-	-	-	-	-	-	-	132.7	284.8	305.3	1.18
14	14	-	-	-	-	-	-	-	-	132.7	284.8	305.3	1.00
13	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.46
12	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.00
11	14	-	-	-	-	-	-	-	-	240.2	484.4	529.7	1.19
10	14	-	-	-	-	-	-	-	-	240.2	484.4	529.7	1.00
9 (Roof MC8)	14	-	-	-	-	131.7	255.9	225.3	-	297.9	480.2	568.9	1.07
8	14	-	-	-	-	131.7	255.9	225.3	1.00	297.9	480.2	568.9	1.00
7	14	-	-	-	-	252.8	403.2	381.3	1.69	297.9	480.2	568.9	1.00
6	14	-	-	-	-	252.8	403.2	381.3	1.00	297.9	480.2	568.9	1.00
5 (Roof MC4)	14	78.3	249.2	190.4	-	252.8	403.2	381.3	1.00	297.9	480.2	568.9	1.00
4	14	131.7	255.9	225.3	1.18	252.8	403.2	381.3	1.00	297.9	480.2	568.9	1.00
3	14	252.8	403.2	381.3	1.69	343.3	480.2	478.7	1.26	469.2	679.0	839.4	1.48
2	18	239.0	484.4	351.3	0.92	296.9	480.2	377.4	<b>0.79</b>	419.4	679.0	703.1	0.84

a. Design compression strength.  
b. Design tension strength.

**Table B-38. Vertical Irregularity Type 5 (a and b) Verification, RSA (kip, feet)**

Floor (x)	$h_{sx}$	MC4				MC8				MC16			
		$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$	$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$	$P_{br,C}^a$	$P_{br,T}^b$	$V_{y,x}$	$V_{y,x+1}/V_{y,x}$
Roof MC16	14	-	-	-	-	-	-	-	-	99.4	255.9	259.7	-
16	14	-	-	-	-	-	-	-	-	99.4	255.9	259.7	1.00
15	14	-	-	-	-	-	-	-	-	132.7	284.8	305.3	1.18
14	14	-	-	-	-	-	-	-	-	132.7	284.8	305.3	1.00
13	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.46
12	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.00
11	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.00
10	14	-	-	-	-	-	-	-	-	207.5	403.2	446.5	1.00
9 (Roof MC8)	14	-	-	-	-	131.7	255.9	225.3	-	207.5	403.2	446.5	1.00
8	14	-	-	-	-	131.7	255.9	225.3	1.00	207.5	403.2	446.5	1.00
7	14	-	-	-	-	166.5	284.8	262.3	1.16	240.2	484.4	529.7	1.19
6	14	-	-	-	-	166.5	284.8	262.3	1.00	240.2	484.4	529.7	1.00
5 (Roof MC4)	14	67.6	197.9	154.3	-	252.8	403.2	381.3	1.45	297.9	480.2	568.9	1.07
4	14	131.7	255.9	225.3	1.46	252.8	403.2	381.3	1.00	297.9	480.2	568.9	1.00
3	14	166.5	284.8	262.3	1.16	343.3	480.2	478.7	1.26	469.2	679.0	839.4	1.48
2	18	206.6	403.2	296.1	1.13	296.9	480.2	377.4	<b>0.79</b>	419.4	679.0	703.1	0.84

a. Design compression strength  
b. Design tension strength.

### B.3 SMF AISC Frame Stability (Effective Length Method)

Table B-39 through Table B-44 provide the results from AISC 360, appendix 7 Effective Length Method verifications.

**Table B-39. AISC 360 Frame Stability (Effective Length Method), 4-Story SMF ELF (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1314	2.24	499.9	168	0.954	35716	1.04
2936	2.92	897.8	168	0.954	49223	1.06
4574	3.21	1120.0	168	0.954	55854	1.09
6235	3.38	1208.0	216	0.954	73615	1.09

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .

b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-40. AISC 360 Frame Stability (Effective Length Method), 4-Story SMF RSA (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1309	2.51	435.5	168	0.954	27764	1.05
2925	3.50	765.8	168	0.954	35055	1.09
4547	3.97	938.0	168	0.954	37806	1.14
6192	4.13	999.6	216	0.954	49870	1.14

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .

b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-41. AISC 360 Frame Stability (Effective Length Method), 8-Story SMF ELF (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1300	2.15	392.5	168	0.954	29312	1.05
2901	2.68	764.5	168	0.954	45678	1.07
4525	2.64	1045.2	168	0.954	63361	1.08
6158	2.79	1244.9	168	0.954	71414	1.09
7803	2.81	1377.1	168	0.954	78453	1.11
9452	2.83	1455.0	168	0.954	82282	1.13
11115	2.68	1493.0	168	0.954	89151	1.14
12806	2.66	1505.3	216	0.954	116595	1.12

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .

b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-42. AISC 360 Frame Stability (Effective Length Method), 8-Story SMF RSA (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1297	5.76	665.9	168	0.954	18506	1.08
2893	7.62	1297.1	168	0.954	27284	1.12
4501	8.56	1770.7	168	0.954	33134	1.16
6114	8.74	2107.1	168	0.954	38612	1.19
7741	8.11	2330.3	168	0.954	46054	1.20
9373	7.72	2462.1	168	0.954	51065	1.22
11021	6.83	2526.7	168	0.954	59299	1.23
12697	6.44	2547.5	216	0.954	81474	1.18

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .

b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-43. AISC 360 Frame Stability (Effective Length Method), 16-Story SMF ELF (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1297	1.62	278.1	168	0.954	27566	1.05
2895	1.97	578.3	168	0.954	47016	1.07
4509	2.09	843.4	168	0.954	64592	1.08
6133	2.26	1073.9	168	0.954	76131	1.09
7766	2.34	1272.1	168	0.954	86953	1.10
9403	2.49	1439.8	168	0.954	92517	1.11
11046	2.57	1579.7	168	0.954	98355	1.13
12695	2.50	1694.0	168	0.954	108744	1.13
14355	2.31	1785.7	168	0.954	123781	1.13
16020	2.27	1856.8	168	0.954	131214	1.14
17691	2.24	1909.9	168	0.954	136851	1.15
19369	2.18	1947.6	168	0.954	143441	1.16
21056	2.05	1972.5	168	0.954	154360	1.16
22754	1.91	1987.2	168	0.954	167096	1.16
24469	1.60	1994.5	168	0.954	199929	1.14
26227	1.32	1996.8	216	0.954	311432	1.09

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .  
 b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-44. AISC 360 Frame Stability (Effective Length Method), 16-Story SMF RSA (kip, inch)**

$P_{story}^a$	$\Delta_H^b$	$H$	$L$	$R_m$	$P_{e\ story}$	$B_2$
1296	2.83	390.9	168	0.954	22100	1.06
2893	3.88	812.9	168	0.954	33576	1.09
4496	4.75	1182.8	168	0.954	39868	1.13
6105	4.89	1503.8	168	0.954	49305	1.14
7728	4.56	1781.0	168	0.954	62558	1.14
9358	4.71	2015.7	168	0.954	68592	1.16
10993	4.83	2211.3	168	0.954	73302	1.18
12634	4.73	2371.3	168	0.954	80383	1.19
14282	4.45	2499.2	168	0.954	90046	1.19
15936	4.34	2598.5	168	0.954	95899	1.20
17595	4.17	2672.7	168	0.954	102632	1.21
19260	3.78	2725.3	168	0.954	115496	1.20
20939	3.25	2760.2	168	0.954	136170	1.18
22627	2.94	2780.8	168	0.954	151337	1.18
24328	2.50	2790.8	168	0.954	178505	1.16
26067	2.16	2794.1	216	0.954	267012	1.11

a.  $P_{story}$  is computed from  $1.2 \times \text{Dead} + 0.25 \times \text{Floor Live}$ .  
 b.  $\Delta_H$  and  $H$  are determined from a first-order static analysis using ASCE 7 §12.8.6.

**Table B-45. Adjusted Effective Length Factors – 4-Story SMF**

Story	ELF		RSA	
	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)
	Exterior	Interior	Exterior	Interior
4	2.23	2.98	2.46	3.08
3	2.44	3.26	2.99	3.74
2	2.54	3.37	3.08	3.86
1	2.42	3.21	2.58	3.23

a.  $x$  designates in-plane buckling about  $x$ -axis as depicted in AISC 360 Part 1.

**Table B-46. Adjusted Effective Length Factors – 8-Story SMF**

Story	ELF		RSA	
	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)
	Exterior	Interior	Exterior	Interior
8	2.18	2.75	2.59	2.74
7	2.12	2.67	2.61	2.76
6	2.09	2.80	2.26	3.21
5	2.04	2.74	2.16	3.08
4	2.04	2.88	2.20	3.38
3	1.99	2.81	2.27	3.48
2	2.09	3.21	2.44	3.82
1	2.03	3.11	2.24	3.51

a.  $x$  designates in-plane buckling about  $x$ -axis as depicted in AISC 360 Part 1.

**Table B-47. Adjusted Effective Length Factors – 16-Story SMF**

Story	ELF		RSA	
	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)	$K_{2x}$ (note a)
	Exterior	Interior	Exterior	Interior
16	3.09	2.46	2.51	2.64
15	3.33	2.65	2.41	2.53
14	2.66	2.80	2.11	2.73
13	2.46	2.59	2.02	2.61
12	2.29	2.52	2.17	2.66
11	2.20	2.43	2.29	2.81
10	2.05	2.49	2.11	2.90
9	2.01	2.43	2.05	2.81
8	1.97	2.70	2.21	2.89
7	2.07	2.84	2.32	3.04
6	2.03	3.21	2.22	3.43
5	1.97	3.12	2.09	3.22
4	2.08	3.21	2.88	3.11
3	2.07	3.20	3.79	4.09
2	2.69	3.25	3.48	4.20
1	2.62	3.17	2.62	3.17

a.  $x$  designates in-plane buckling about  $x$ -axis as depicted in AISC 360 Part 1.

## B.4 Example Design Calculations

The examples presented detail the strength design calculations for the following members and components of each SFRS for the RSA-designed 8-story buildings (MC8):

- SCBF brace, MC8 RSA
- SCBF column, MC8 RSA

Example calculations for components of the SMF can be found in Volume 1 (Harris and Speicher 2015).

### B.4.1 Special Concentrically Braced Frame Example

#### B.4.1.1 Member Selection

After several design and analysis iterations, the final member sizes are shown in Figure B-19.




Figure B-19. SCBF Member Sizes, 8-Story RSA

### B.4.1.2 SCBF Brace

The first story brace along grid line A between grid lines 2 and 3 was selected for this example (see circled elements in Figure B-19):

- HSS 7×7×1/2
- $L_{wp} = 247$  in,  $L_{br} \approx 0.9 \times L_{wp} = 222$  in
- A500 Gr. B,  $F_y = 46$  ksi,  $R_y = 1.4$ ,  $E = 29000$  ksi,  $G = 11200$  ksi

#### B.4.1.2.1 Axial Demand

The axial compression force in the brace is (assuming braces do not carry gravity loads):

$$P_u = P_G \pm P_E = 0 + 265 = 265 \text{ kips}$$

There is no significant moment in the brace.

#### A.1.1.1.1 Axial Strength

The axial compression strength of the brace is calculated per AISC 360 §E3—weak-axis ( $y$ ) governs.

$$P_{n,y} = A_g F_{cr,y}$$

$$\frac{K_y L_y}{r_y} \sqrt{\frac{F_y}{E}} = \frac{1.0(222)}{2.63} \sqrt{\frac{46}{29000}} = 3.36 \leq 4.71$$

$$F_{e,y} = \frac{\pi^2 E}{\left(\frac{K_y L_y}{r_y}\right)^2} = \frac{\pi^2 (29000)}{\left(\frac{1.0(222)}{2.63}\right)^2} = 40.0 \text{ ksi}$$

$$\therefore F_{cr,y} = \left[ 0.658^{(F_y/F_{e,y})} \right] F_y = 28.4 \text{ ksi}$$

$$\phi_c P_{n,y} = 0.9(11.6)28.4 = 0.9(330) = 297 \text{ kips}$$

#### B.4.1.2.2 Strength Check

$$\frac{P_u}{\phi_c P_{n,y}} = \frac{265}{297} = 0.89 \leq 1.0 \therefore \text{OK}$$

### B.4.1.3 SCBF Column

The first story column along grid line 3 was selected for this example (see circled elements in Figure B-19):

- W14×283
- $h_{sx} = 216$  in,  $L_{clear} = 197.4$  in
- A992 Steel:  $F_y = 50$  ksi,  $R_y = 1.1$ ,  $E = 29000$  ksi,  $G = 11200$  ksi

#### B.4.1.3.1 Axial and Flexural Demand

The demands in the column from the controlling load combinations from ASCE 7 are presented in Table B-48—maximum/minimum values for an individual action displayed with bolded text.

**Table B-48. Controlling Load Combinations (kips, feet)**

LC Index	$P_{u,A}$	$P_{u,B}$	$M_{u,A,x}$	$M_{u,B,x}$	Max/Min Action
179	602.97	<b>602.97</b>	222.35	45.65	$P_{u,min}$
133	<b>-1108.72</b>	-1102.21	-224.11	-42.20	$P_{u,max}$
179	599.72	602.97	<b>222.35</b>	45.65	$M_{u,A,min}$
133	-1108.72	-1102.21	<b>-224.11</b>	-42.20	$M_{u,A,max}$
123	414.63	421.14	221.69	<b>46.93</b>	$M_{u,B,min}$
189	-923.63	-920.38	-223.46	<b>-43.48</b>	$M_{u,B,max}$

$P_r = 1109$  kips and  $M_{r,x} = 224$  kip-ft.—from the load combination selected for this example (#133 in Table B-48).

The SCBF column design is also governed by the capacity design requirements specified in AISC 341 §F2.3. AISC 341 §F2.3, exception (1) permits flexural forces resulting from seismic drift of the frame to be neglected.

$$P_{r,CD} = 2841 \text{ kips}$$

#### B.4.1.3.2 Axial Strength

The axial compression strength of the column is calculated per AISC 360 §E3—weak-axis ( $y$ ) governs.

$$P_{n,y} = A_g F_{cr,y}$$

$$\frac{K_y L_y}{r_y} \sqrt{\frac{F_y}{E}} = \frac{1.0(216)}{4.17} \sqrt{\frac{50}{29000}} = 2.15 \leq 4.71$$

$$F_{e,y} = \frac{\pi^2 E}{\left(\frac{K_y L_y}{r_y}\right)^2} = \frac{\pi^2 (29000)}{\left(\frac{1.0(216)}{4.17}\right)^2} = 106.7 \text{ ksi}$$

$$\therefore F_{cr,y} = \left[ 0.658^{(F_y/F_{e,y})} \right] F_y = \left[ 0.658^{(50/106.7)} \right] 50 = 41.1 \text{ ksi}$$

$$\phi_c P_{n,y} = 0.9(83.3)41.1 = 0.9(3423) = 3081 \text{ kips}$$

#### B.4.1.3.3 Strength Check

$$\frac{P_{r,CD}}{\phi_c P_{n,y}} = \frac{2841}{3081} = 0.92 \leq 1.0 \therefore \text{OK}$$

The  $P$ - $M$  interaction values from AISC 360 Equation H1-1(a) and Equation H1-2 are 0.42 and 0.48, respectively.

## Appendix C Example Assessment Calculations

The examples presented in this appendix detail the assessment calculations for the following *primary* members and connections of each SFRS for the RSA-designed 8-story buildings (MC8):

- SCBF brace, MC8 RSA

Linear assessment example calculations are provided in C.1, and examples for the nonlinear assessment example calculations are provided in C.2.

### C.1 Linear Assessment Examples

The following example provides guidance to how the linear assessment calculations were conducted in this study. Linear assessment of the selected components is performed for the following criteria:

- Linear Dynamic Procedure (LDP)
- Collapse Prevention (CP) Building Performance Level (BPL) for the BSE-2 Earthquake Hazard Level (EHL)

#### C.1.1 SCBF Brace

The first story brace along grid line A between grid lines 2 and 3 was selected for this example (see circled elements in Figure B-19):

- HSS 7×7×1/2
- $L_{wp} = 247$  in,  $L_{br} \approx 0.9 \times L_{wp} = 222$  in
- A500 Gr. B,  $F_{y, LB} = F_y = 46$  ksi,  $F_{ye} = 64.4$  ksi,  $E = 29000$  ksi,  $G = 11154$  ksi

##### C.1.1.1 Axial Demand

The axial compression force in the brace is (assuming braces do not carry gravity loads):

$$P_E = 1.0E_y + 0.3E_x = 1353 \text{ kips}$$

$$P_{UD} = P_G \pm P_E = 0 + 1353 = 1353 \text{ kips}$$

##### C.1.1.2 Axial Strength

Per ASCE 41 §5.5.2.3, the expected axial compression strength is computed as  $P_n$  from AISC 360-05 §E3 with  $\phi_c = 1$  and  $F_{ye}$ .

$$P_{CE} = P_{n,y} = A_g F_{cr,y}$$

$$\frac{K_y L_y}{r_y} \sqrt{\frac{F_{ye}}{E}} = \frac{1.0(222)}{2.63} \sqrt{\frac{64.4}{29000}} = 3.98 \leq 4.71$$

$$F_{e,y} = \frac{\pi^2 E}{\left(\frac{K_y L_y}{r_y}\right)^2} = \frac{\pi^2 (29000)}{\left(\frac{1.0(222)}{2.63}\right)^2} = 40.0 \text{ ksi}$$

$$\therefore F_{cr,y} = \left[ 0.658^{(F_{ye}/F_{e,y})} \right] F_{ye} = 32.8 \text{ ksi}$$

$$P_{CE} = 11.6(32.8) = 381 \text{ kips} \rightarrow P_{ye} = 11.6(64.4) = 747 \text{ kips}$$

### C.1.1.3 Acceptance Criteria

The  $m$ -factor for a brace in compression is based on the slenderness of the member and the section type (HSS):

$$2.1 \sqrt{\frac{E}{F_y}} = 52.7 \leq \frac{KL}{r} = 84.6 < 4.2 \sqrt{\frac{E}{F_y}} = 105.5$$

Note that ASCE 41 defines  $F_{y,LB}$  and  $F_{ye}$ , but does not define  $F_y$  as a material strength.

Therefore, linear interpolation gives the following:

$$m = 6 + \frac{(7-6)(84.6-52.73)}{(105.5-52.73)} = 6.60$$

### C.1.1.4 Acceptance Criteria Check

The brace acceptance criteria check is:

$$DCR_N = \frac{DCR}{\kappa m} = \frac{P_{UD}}{\kappa m P_{CE}} = \frac{1353}{6.60(381)} = 0.54 < 1.0$$

Therefore, the brace satisfies the CP BPL acceptance criteria at the BSE-2 EHL.

## C.2 Nonlinear Assessment Examples

The following example provides guidance to how the nonlinear assessment calculations were conducted in this study. Nonlinear assessment of the selected components is performed for the following criteria:

- Nonlinear Dynamic Procedure (NDP) or Nonlinear Static Procedure (NSP)
- Median value of the record set is used for the NDP
- Collapse Prevention Building Performance Level for the BSE-2 EHL

### C.2.1 SCBF Brace

The first story brace along grid line A between grid lines 2 and 3 was selected for this example (see circled elements in Figure B-19):

- HSS 7×7×1/2
- $L_{wp} = 247$  in,  $L_{br} \approx 0.9L_{wp} = 222$  in.
- A500 Gr. B,  $F_{y,LB} = F_y = 46$  ksi,  $F_{ye} = 64.4$  ksi,  $E = 29000$  ksi,  $G = 11200$  ksi

The demands for the SCBF are taken from the median value of the record set from the NDP.

#### C.2.1.1 Deformation Demand

The brace demand in terms of axial compressive deformation is:

$$\Delta_{UD} = 1.69 \text{ in.}$$

#### C.2.1.2 Acceptance Criteria

The acceptance criteria in terms of plastic axial deformation are given in ASCE 41 Table 5-7. To compare against the strain results coming from PERFORM-3D, the plastic deformation is converted to total axial deformation.

$$2.1 \sqrt{\frac{E}{F_y}} = 52.8 < \frac{KL}{r} = 84.4 < 4.2 \sqrt{\frac{E}{F_y}} = 105.5$$

Therefore, linear interpolation gives

$$\Delta_{p,AC} = \left( \frac{105.5 - 84.4}{105.5 - 52.8} \right) (6\Delta_c - 7\Delta_c) + 7\Delta_c = \left( \frac{21.1}{52.7} \right) (6\Delta_c - 7\Delta_c) + 7\Delta_c = 6.6\Delta_c$$

$\Delta_c$  is the axial deformation at expected buckling (flexural):

$$P_{CE} = 11.6(32.8) = 381 \text{ kips (see Linear Assessment calculations above)}$$

$$\Delta_c = \frac{P_{CE} L_{br}}{AE} = \frac{381(222)}{11.6(29000)} = 0.252 \text{ in.} \rightarrow P_{CE} \approx 0.5P_{ye}, \text{ assume } \textit{elastic} \text{ cross-section response}$$

$$\therefore \Delta_{p,AC} = 6.6(0.252) = 1.66 \text{ in.}$$

$$\therefore \Delta_{total,AC} = \Delta_{p,AC} + \eta\Delta_c = 1.66 + 0.38(0.252) = 1.76 \text{ in.}$$

where  $\eta$  is the reduction in elastic deformation due to strength loss at the acceptance criterion.

### C.2.1.3 Acceptance Criteria Check

The brace acceptance criteria check is:

$$DCR_N = \frac{\Delta_{UD}}{\kappa \Delta_{total,AC}} = \frac{1.69}{1.0(1.76)} = 0.96 < 1.0$$

Therefore, the brace satisfies the CP BPL acceptance criteria at the BSE-2 EHL.

## Appendix D References

AISC (1989). *Specification for Structural Steel Buildings: Allowable Stress Design and Plastic Design*. American Institute of Steel Construction, Chicago, IL.

AISC (1999). *Wide-Flange Column Stiffening at Moment Connections – Design Guide 13*. American Institute of Steel Construction, Chicago, IL.

AISC (2002). *Seismic Provisions for Structural Steel Buildings – ANSI/AISC 341-02*. American Institute of Steel Construction, Chicago, IL.

AISC (2005). *Specification for Structural Steel Buildings – ANSI/AISC 360-05*. American Institute of Steel Construction, Chicago, IL.

AISC (2010a). *Specification for Structural Steel Buildings – ANSI/AISC 360-10*. American Institute of Steel Construction, Chicago, IL.

AISC (2010b). *Seismic Provisions for Structural Steel Buildings – ANSI/AISC 341-10*. American Institute of Steel Construction, Chicago, IL.

AISC (2010c). *Prequalified Connections for Special and Intermediate Steel Moment Frames for Seismic Applications – ANSI/AISC 358-10*. American Institute of Steel Construction, Chicago, IL.

AISC (2013). *Stability Design of Steel Buildings – Design Guide 28*. American Institute of Steel Construction, Chicago, IL.

ASCE (2005). *Minimum Design Loads for Buildings and Other Structures – ASCE/SEI 7-05*. American Society of Civil Engineers, Reston, VA.

ASCE (2006). *Seismic Rehabilitation of Existing Buildings – ASCE/SEI 41-06*. American Society of Civil Engineers, Reston, VA.

ASCE (2010). *Minimum Design Loads for Buildings and Other Structures – ASCE/SEI 7-10*. American Society of Civil Engineers, Reston, VA.

ASCE (2014). *Seismic Evaluation and Retrofit of Existing Buildings – ASCE/SEI 41-13*. American Society of Civil Engineers, Reston, VA.

ASCE (2016). *Minimum Design Loads for Buildings and Other Structures – ASCE/SEI 7-16*. American Society of Civil Engineers, Reston, VA. *In Progress*.

CBSC (2010) *California Code of Regulations, Part 2 – California Building Standards Code – Title 24*. California Building Standards Commission, Sacramento, California.

CSI (2011a). ETABS (Version 9.7.4) [Computer Software]. Computers and Structures, Inc., Berkeley, CA.

CSI (2011b). PERFORM-3D (Version 5.0) [Computer Software]. Computers and Structures, Inc., Berkeley, CA.

CSI (2011c). *Components and Elements for PERFORM-3D and PERFORM-COLLAPSE* (Version 5.0). Computers and Structures, Inc., Berkeley, CA.

CSI (2011d). *User Guide PERFORM-3D* (Version 5.0). Computers and Structures, Inc., Berkeley, CA.

Engelhardt, M.D., Winneberger, T., Zekany, A.J., and Potyraj, T.J. (1998). “Experimental Investigation of Dogbone Moment Connections”. *Engineering Journal*, AISC, 4<sup>th</sup> Quarter, pp. 128-139.

FEMA (1997). *NEHRP Guidelines for the Seismic Rehabilitation of Buildings – FEMA 273*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000a). *Recommended Seismic Design Criteria for New Steel Moment Frame Buildings – FEMA 350*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000b). *Recommended Seismic Evaluation and Upgrade Criteria for Existing Welded Steel Moment Frame Buildings – FEMA 351*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000c). *State of the Art Report on Connection Performance – FEMA 355D*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000d). *State of the Art Report on Performance Prediction and Evaluation – FEMA 355F*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000e). *Prestandard and Commentary for the Seismic Rehabilitation of Buildings – FEMA 356*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2000f). *Global Topics Report on the Prestandard and Commentary for the Seismic Rehabilitation of Buildings – FEMA 357*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2005). *Improvements of Nonlinear Static Seismic Analysis Procedures – FEMA 440*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2009a). *Quantification of Building Seismic Performance Factors – FEMA P695*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2009b). *NEHRP Recommended Seismic Provisions for New Buildings and Other Structures – FEMA P-750*. Federal Emergency Management Agency, Washington, D.C.

FEMA (2009c). *Effects of Strength and Stiffness Degradation on Seismic Response* – FEMA P-440A. Federal Emergency Management Agency, Washington, D.C.

FEMA (2012). *Seismic Performance Assessment of Buildings* – FEMA P-58. Federal Emergency Management Agency, Washington, D.C.

FEMA (2015). *NEHRP Recommended Seismic Provisions for New Buildings and Other Structures*. Federal Emergency Management Agency, Washington, D.C. *In Progress*.

GSA (2012). *Facilities Standards for the Public Buildings Service* – PBS-P100. U.S. General Services Administration, Washington, D.C.

Harris, J.L. and Speicher, M.S. (2015). *Assessment of First Generation Performance-Based Design Methods for New Steel Buildings, Volume 1: Special Moment Frames* – NIST TN 1863-1. National Institute of Standards and Technology, Gaithersburg, MD.

Haselton, C.B., Kircher, C.A., and Liel, A.B. (2009). “Concept Paper on Utilizing the FEMA P695 (ATC-63) Ground Motion Spectral Shape Guidelines to Adjust the Target Displacement in the ASCE/SEI 41 Nonlinear Static Procedure” *Proc.*: ATC & SEI 2009 Conference on Improving the Seismic Performance of Existing Buildings and Other Structures, San Francisco, CA Dec. 9-11, 2009.

ICC (2012a). *International Existing Building Code (IEBC)*. International Code Council, Washington, DC.

ICC (2012b). *International Building Code (IBC)*. International Code Council, Washington, DC.

Krawinkler, H., Bertero, V.V., and Popov, E.P. (1971). *Inelastic Behavior of Steel Beam-to-Column Subassemblages* – Report No. UCB/EERC-71/07. Earthquake Engineering Research Center, University of California, Berkeley, CA, October 1971.

Krawinkler, H. (1978). “Shear in Beam Column Joints in Seismic Design of Steel Frames”. *Engineering Journal*, AISC, 3<sup>rd</sup> Quarter, pp. 82-91.

Lee, D., Cotton, S.C., Dexter, R.J., Hajjar, J.F., Ye, Y. and Ojard, S.D. (2002). *Column Stiffener Detailing and Panel Zone Behavior of Steel Moment Frame Connections* – Report No. ST-01-3.2. Dept. of Civil Engineering, University of Minnesota, Minneapolis, MN, 2002.

NIBS (2013). *National Performance-Based Design Guide for Buildings*. National Institute of Building Sciences, Washington, D.C.

NIST (2009a). *Research Required to Support Full Implementation of Performance-Based Seismic Design* – NIST GCR 09-917-2. Produced by the Building Seismic Safety Council for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2009b). *Seismic Design of Steel Special Moment Frames: A Guide for Practicing Engineers*, NEHRP Seismic Design Technical Brief No. 2 – NIST GCR 09-917-3. Produced by the NEHRP Consultants Joint

Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2010a). *Nonlinear Structural Analysis for Seismic Design: A Guide for Practicing Engineers*, NEHRP Seismic Design Technical Brief No. 4 – NIST GCR 10-917-5. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2010b). *Evaluation of the FEMA P-695 Methodology for Quantification of Building Seismic Performance Factors* – NIST GCR 10-917-8. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2010c). *Applicability of Nonlinear Multi-Degree-of-Freedom Modeling for Design* – NIST GCR 10-917-9. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2011a). *Standards of Seismic Safety for Existing Federally Owned and Leased Buildings: ICSSC Recommended Practice 8 (RP 8)* – NIST GCR 11-917-12. Produced by the Building Seismic Safety Council of the National Institute of Building Sciences for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2011b). *Seismic Design of Composite Steel Deck and Concrete-filled Diaphragms: A Guide for Practicing Engineers*, NEHRP Seismic Design Technical Brief No. 5 – NIST GCR 11-917-10. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2011c). *Research Plan for the Study of Seismic Behavior and Design of Deep, Slender Wide-Flange Structural Steel Beam-Column Members* – NIST GCR 11-917-13. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2011d). *Selecting and Scaling Earthquake Ground Motions for Performing Response-History Analyses* – NIST GCR 11-917-15. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2012). *Tentative Framework for Development of Advanced Seismic Design Criteria for New Buildings* – NIST GCR 12-917-20. Produced by the NEHRP Consultants Joint Venture, a partnership of

the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

NIST (2013). *Seismic Design of Steel Special Concentrically Braced Frame Systems: A Guide for Practicing Engineers*, NEHRP Seismic Design Technical Brief No. 8 – NIST GCR 13-917-24. Produced by the NEHRP Consultants Joint Venture, a partnership of the Applied Technology Council and the Consortium of Universities for Research in Earthquake Engineering, for the National Institute of Standards and Technology, Gaithersburg, MD.

Paret, T.F., Searer, G.R., and Freeman, S.A. (2011). “ASCE 31 and 41: Apocalypse Now”. *Proc.: Structures Congress 2011*, Las Vegas, NV, April 14-16, 2011.

Pekelnicky, R. and Poland, C. (2012). “ASCE 41-13: Seismic ~~Evaluation and Retrofit~~ Evaluation and Retrofit Rehabilitation of Existing Buildings”. *Proc.: 2012 SEAOC-SEANM Convention*, Santa Fe, NM, Sept. 12-15, 2012.

SEAONC (2010) “Perspectives on ASCE 41 for Seismic Rehabilitation of Building – Survey by the Structural Engineers Association of Northern California”. *Structures Magazine*, Oct. 2010.

Toranzo-Dianderas, L.A. (2009). “Evaluation of the ASCE 41 Linear Elastic Procedure for Seismic Retrofit of Existing Structures: Pros and Cons of the Method.” *Proc.: ATC & SEI 2009 Conference on Improving the Seismic Performance of Existing Buildings and Other Structures*, San Francisco, CA Dec. 9-11, 2009.

Troup, E. (1999). “Effective Contract and Shop Drawings for Structural Steel”. *Proc.: North American Steel Construction Conference*, Toronto, Ontario, Canada, May 19-21, 1999.

White, D.W. and Hajjar, J.F. (1997). “Design of Steel Frames without Consideration of Effective Length”. *Engineering Structures*, Vol. 19(10), pp. 797-810.

Yang, F., and Mahin, S.A. (2005), “Limiting Net Section Fracture in Slotted Tube Braces”. *Steel Tips Series*, Structural Steel Education Council, Moraga, CA.

*Standards of Seismic Safety for Existing Federally Owned and Leased Buildings: ICSSC Recommended Practice 8 (RP 8)*